

New aluminium double glazed roof level windows painted grey.

Existing non original concrete roof tiles are to be stripped and replaced with grey slate tiles.

Non original timber windows to be replaced with white double glazed timber sash windows. Design to replicate the appearance of the original windows.

Elevation to be re-rendered and painted light grey.

Window surround stone detailing to be reinstated as original and painted white.

Window surround stone detailing to be reinstated as original.

Existing front elevation to be re-rendered and painted white.

Steps to lower ground floor to be reconfigured. New square section metal balustrade and handrail painted black.

Steps to lower ground floor to be reconfigured. Treads and risers and base of light well to be finished with stone.

STREET ELEVATION 1:100

0 1 2 3 4 5 m

rev	description	date
/*	first issue	16.10.15
A	client review	23.11.15
B	planning application	27.11.15

All dimensions are in millimetres unless noted otherwise. All dimensions are to be checked on site and any discrepancies noted in writing to the Architect immediately. All rights reserved. All drawings and written material appearing herein constitute original and unpublished work of the CRAEFT Architects and may not be duplicated, used or disclosed without written consent of the Architect.

35 Ossian Road, London, N4 4DX

PROPOSED STREET ELEVATION

CRÆFT ARCHITECTS

289 Green Lanes, Palmers Green, London N13 4XS
0203 624 3529 www.craeftarchitects.co.uk

Scale 1:100 @ A3

October 2015

PLANNING

OSN (300)010 B