## Skapoullis Jon

**From:** Planning Support
**Subject:** FW: Network Rail consultation - HGY/2016/1132

**From:** Toolan Adrian [mailto:Adrian.Toolan@networkrail.co.uk] **On Behalf Of** Town Planning SE
**Sent:** 27 April 2016 15:24
**To:** Planning Customer Care Team
**Subject:** Network Rail consultation - HGY/2016/1132

Dear Sir/Madam,

Thank you very much for consulting with Network Rail in regards to application HGY/2016/1132 and offering us the opportunity to comment.

The developer/applicant must ensure that their proposal, both during construction and after completion of works on site, does not:

- encroach onto Network Rail land
- affect the safety, operation or integrity of the company's railway and its infrastructure
- undermine its support zone
- damage the company's infrastructure
- place additional load on cuttings
- adversely affect any railway land or structure
- over-sail or encroach upon the air-space of any Network Rail land
- cause to obstruct or interfere with any works or proposed works or Network Rail development both now and in the future

I give below my comments and requirements for the safe operation of the railway and the protection of Network Rail's adjoining land.

**Future maintenance**
The development must ensure that any future maintenance can be conducted solely on the applicant's land. The applicant must ensure that any construction and any subsequent maintenance can be carried out to any proposed buildings or structures without adversely affecting the safety of, or encroaching upon Network Rail's adjacent land and air-space, and therefore all/any building should be situated at least 2 metres (3m for overhead lines and third rail) from Network Rail's boundary. The reason for the 2m (3m for overhead lines and third rail) stand off requirement is to allow for construction and future maintenance of a building and without requirement for access to the operational railway environment which may not necessarily be granted or if granted subject to railway site safety requirements and special provisions with all associated railway costs charged to the applicant. Any less than 2m (3m for overhead lines and third rail) and there is a strong possibility that the applicant (and any future resident) will need to utilise Network Rail land and air-space to facilitate works. The applicant / resident would need to receive approval for such works from the Network Rail Asset Protection Engineer, the applicant / resident would need to submit the request at least 20 weeks before any works were due to commence on site and they would be liable for all costs (e.g. all possession costs, all site safety costs, all asset protection presence costs). However, Network Rail is not required to grant permission for any third party access to its land. No structure/building should be built hard-against Network Rail's boundary as in this case there is an even higher probability of access to Network Rail land being required to undertake any construction / maintenance works. Equally any structure/building erected hard against the boundary with Network Rail will impact adversely upon our maintenance teams' ability to maintain our boundary fencing and boundary treatments.

**Drainage**

No Storm/surface water or effluent should be discharged from the site or operations on the site into Network Rail's property or into Network Rail's culverts or drains except by agreement with Network Rail. Suitable drainage or other works must be provided and maintained by the Developer to prevent surface water flows or run-off onto Network Rail's property. Proper provision must be made to accept and continue drainage discharging from Network Rail's property; full details to be submitted for approval to the Network Rail Asset Protection Engineer. Suitable foul drainage must be provided separate from Network Rail's existing drainage. Soakaways, as a means of storm/surface water disposal must not be constructed near/within 10 – 20 metres of Network Rail's boundary or at any point which could adversely affect the stability of Network Rail's property. After the completion and occupation of the development, any new or exacerbated problems attributable to the new development shall be investigated and remedied at the applicants' expense.

**Plant & Materials**
All operations, including the use of cranes or other mechanical plant working adjacent to Network Rail's property, must at all times be carried out in a "fail safe" manner such that in the event of mishandling, collapse or failure, no plant or materials are capable of falling within 3.0m of the boundary with Network Rail.

**Scaffolding**
Any scaffold which is to be constructed within 10 metres of the railway boundary fence must be erected in such a manner that at no time will any poles over-sail the railway and protective netting around such scaffold must be installed. The applicant/applicant's contractor must consider if they can undertake the works and associated scaffold/access for working at height within the footprint of their property boundary.

**Piling**
Where vibro-compaction/displacement piling plant is to be used in development, details of the use of such machinery and a method statement should be submitted for the approval of the Network Rail's Asset Protection Engineer prior to the commencement of works and the works shall only be carried out in accordance with the approved method statement.

**Fencing**
In view of the nature of the development, it is essential that the developer provide (at their own expense) and thereafter maintain a substantial, trespass proof fence along the development side of the existing boundary fence, to a minimum height of 1.8 metres. The 1.8m fencing should be adjacent to the railway boundary and the developer/applicant should make provision for its future maintenance and renewal without encroachment upon Network Rail land. Network Rail's existing fencing / wall must not be removed or damaged and at no point either during construction or after works are completed on site should the foundations of the fencing or wall or any embankment therein, be damaged, undermined or compromised in any way. Any vegetation on Network Rail land and within Network Rail's boundary must also not be disturbed. Any fencing installed by the applicant must not prevent Network Rail from maintaining its own fencing/boundary treatment.

**Lighting**
Any lighting associated with the development (including vehicle lights) must not interfere with the sighting of signalling apparatus and/or train drivers vision on approaching trains. The location and colour of lights must not give rise to the potential for confusion with the signalling arrangements on the railway. The developers should obtain Network Rail's Asset Protection Engineer's approval of their detailed proposals regarding lighting.

**Noise and Vibration**
The potential for any noise/ vibration impacts caused by the proximity between the proposed development and any existing railway must be assessed in the context of the National Planning Policy Framework which holds relevant national guidance information. The current level of usage may be subject to change at any time without notification including increased frequency of trains, night time train running and heavy freight trains.

**Landscaping**
Where trees/shrubs are to be planted adjacent to the railway boundary these shrubs should be positioned at a minimum distance greater than their predicted mature height from the boundary. Certain broad leaf deciduous species should not be planted adjacent to the railway boundary as the species will contribute to leaf fall which will have a detrimental effect on the safety and operation of the railway. We would wish to be involved in the approval

of any landscaping scheme adjacent to the railway. Where landscaping is proposed as part of an application adjacent to the railway it will be necessary for details of the landscaping to be known and approved to ensure it does not impact upon the railway infrastructure. Any hedge planted adjacent to Network Rail's boundary fencing for screening purposes should be so placed that when fully grown it does not damage the fencing or provide a means of scaling it. No hedge should prevent Network Rail from maintaining its boundary fencing. Lists of trees that are permitted and those that are not permitted are provided below and these should be added to any tree planting conditions:

**Permitted:** Birch (Betula), Crab Apple (Malus Sylvestris), Field Maple (Acer Campestre), Bird Cherry (Prunus Padus), Wild Pear (Pyrs Communis), Fir Trees – Pines (Pinus), Hawthorne (Cretaegus), Mountain Ash – Whitebeams (Sorbus), False Acacia (Robinia), Willow Shrubs (Shrubby Salix), Thuja Plicatat "Zebrina"

**Not Permitted:** Alder (Alnus Glutinosa), Aspen – Popular (Populus), Beech (Fagus Sylvatica), Wild Cherry (Prunus Avium), Hornbeam (Carpinus Betulus), Small-leaved Lime (Tilia Cordata), Oak (Quercus), Willows (Salix Willow), Sycamore – Norway Maple (Acer), Horse Chestnut (Aesculus Hippocastanum), Sweet Chestnut (Castanea Sativa), London Plane (Platanus Hispanica).

**Vehicle Incursion**
Where a proposal calls for hard standing area / parking of vehicles area near the boundary with the operational railway, Network Rail would recommend the installation of a highways approved vehicle incursion barrier or high kerbs to prevent vehicles accidentally driving or rolling onto the railway or damaging lineside fencing.

As the site is adjacent to Network Rail's operational railway infrastructure, Network Rail strongly recommends the developer contacts AssetProtectionAnglia@networkrail.co.uk prior to any works commencing on site. Network Rail strongly recommends the developer agrees an Asset Protection Agreement with us to enable approval of detailed works. More information can also be obtained from our website at www.networkrail.co.uk/aspx/1538.aspx.

Kind regards,

**Adrian Toolan,**
Town Planning Technician,
1 Eversholt Street ,
London,
NW1 2DN.
**Mobile** – 07710 959 611
**Adrian.Toolan@networkrail.co.uk**

**********

The content of this email (and any attachment) is confidential. It may also be legally privileged or otherwise protected from disclosure.
This email should not be used by anyone who is not an original intended recipient, nor may it be copied or disclosed to anyone who is not an original intended recipient.

If you have received this email by mistake please notify us by emailing the sender, and then delete the email and any copies from your system.

Liability cannot be accepted for statements made which are clearly the sender's own and not made on behalf of Network Rail.
Network Rail Infrastructure Limited registered in England and Wales No. 2904587, registered office Network Rail, 2nd Floor, One Eversholt Street, London, NW1 2DN

**********
**********

---

This email has been scanned by the Symantec Email Security.cloud service.
For more information please visit http://www.symanteccloud.com