



1A Glenwood Road, N15

Daylight and Sunlight Assessment

Job No: 4643

Issued: October 2022

Issue No.: 1

Contents

1.0	Introduction	3
2.0	Project Summary	4
3.0	Methodology	5
4.0	Modelling & Data Sources	6
5.0	BRE Guidance Targets	7
6.0	Window Schedules	8
7.0	Daylight Impact Results	9
8.0	Sunlight Impact Results	10
9.0	Sunlight to Neighbouring Gardens	12
10.0	Conclusions	13

Document Prepared By:

Document Authorised By:

Ollie Westover

Bernice Waterman

Dated:

Dated:

11.10.22

11.10.22

Signed:

Signed:




This report has been prepared for the exclusive use of the commissioning party and may not be reproduced without prior written permission from T16 Design.

All work has been carried out within the terms of the brief using all reasonable skill, care, and diligence. No liability is accepted by T16 Design for the accuracy of data or opinions provided by others in the preparation of this report, or for any use of this report other than for the purpose for which it was produced.

1.0 Introduction

- 1.1 This daylight and sunlight assessment has been prepared to support a planning application for the proposed extension of the dwelling at 1A Glenwood Road, London N15.
- 1.2 The report assesses the proposals in respect of daylight, sunlight and overshadowing matters, having regard to industry standard guidance. The report concludes that the proposal is acceptable and in accordance with planning policy requirements in relation to daylight and sunlight.
- 1.3 There is no existing specific National Planning Policy relating to the prospective impacts of developments on daylight and sunlight on their surrounding environment.
- 1.4 However, the BRE Report 'Site Layout Planning for Daylight and Sunlight: A Guide to Good Practice' (3rd Edition, 2022) is the established National guidance to aid the developer to prevent and/or minimise the impact of a new development on the availability of daylight and sunlight in the environs of the site.
- 1.5 This reference document is accepted as the authoritative work in the field on daylight, sunlight and overshadowing and is specifically referred to in many Local Authorities' planning policy guidance for daylighting.
- 1.6 The methodology therein has been used in numerous lighting analyses and the standards of permissible reduction in light are accepted as the industry standards.

2.0 Project Summary

- 2.1 The proposal site is a 2 storey, end of terrace dwelling at 1A Glenwood Road, N15.
- 2.2 The proposal is for ground level and first floor extensions, with a loft extension, following removal of the existing rear outbuildings.
- 2.3 The impacts of the scheme have been assessed, in line with BRE guidance. Generally, it is the impacts on residential neighbours which are of primary concern.
- 2.4 In this instance, the terrace of dwellings to the north of the site and the dwelling to the immediate south are the primary focus of the assessment.
- 2.5 Other dwellings are sufficiently distant from the site that adverse impact is not expected.
- 2.6 Further details on the location of the assessed neighbours and their windows are given in Section 5.0.



Site Location

3.0 Methodology

- 3.1 For this analysis, we have undertaken the most common calculations for the change in daylight and sunlight to existing buildings, as recommended in BRE Digest 209. These are:
- Vertical Sky Component (VSC) for daylight
 - Annual Probable Sunlight Hours and Winter Probable Sunlight Hours (A/WPSH) for sunlight impacts
- 3.2 The VSC method measures the general amount of light available on the outside plane of the window as a ratio (%) of the amount of total unobstructed sky viewable following introduction of visible barriers such as buildings. The maximum value is just under 40% for a completely unobstructed vertical wall.
- 3.3 The VSC is calculated using computer simulation under a CIE overcast sky. This works by simulating the amount of visible sky from the centre point of each window. It is not affected by orientation and so all potentially affected windows are assessed.
- 3.4 Annual Probable Sunlight Hours (APSH) and Winter Probable Sun light Hours (WPSH) are a measure of the amount of potential direct sunlight that is available to a given surface. APSH covers sunlight over the whole year and WPSH from September 21st to March 21st.
- 3.5 The number of total available hours is calculated from a data file in the software, built up over a number of years of actual weather data records.
- 3.6 Only windows which face within 90° of due south need be assessed for sunlight.
- 3.7 APSH can also be used to assess the impact on external spaces such as gardens. This is looked at in Section 9.

4.0 Modelling & Data Sources

- 4.1 The first stage of the analysis is to create the analysis model of the existing site condition and the proposal. This allows us to analyse the impact of the proposal when compared to the existing condition.
- 4.2 2D drawings and a 3D model have been provided by the design team. These drawings are used to construct a 3D analysis model which is exported into the specialist daylight software. Calculations are then run, for both existing and proposed scenarios.
- 4.3 Sufficient detail is added to the model for the analysis. In accordance with BRE recommendations, trees and foliage have been omitted from the calculations.
- 4.4 Information on the properties has been provided to us by the design team in the form of drawings and a model giving the site as existing and proposed, and photographs of the site and surroundings.
- 4.5 Web-based mapping sources and photos have been used to for location and size of neighbouring windows.




Architect's 3D Model – As Proposed


5.0 BRE Guidance Targets

- 5.1 The reference document for this analysis, BRE Digest 209, gives the methodology for undertaking the calculations. It also provides benchmark figures for the acceptable reduction in the daylight on existing properties which might be affected by development.
- 5.2 Specifically, the guidance gives figures for the VSC and APSH, as a percentage reduction that is "permissible" for the effect on existing windows.
- 5.3 It is worth noting the following statement in the Guidance introduction:
- 5.4 "The guide is intended for building designers and their clients, consultants and planning officials. The advice given here is not mandatory and this document should not be seen as an instrument of planning policy. Its aim is to help rather than constrain the developer.
- 5.5 Although it gives numerical guidelines, these should be interpreted flexibly because natural lighting is only one of the many factors in site layout design.
- 5.6 The relevant BRE recommendations for daylight and sunlight are:
 - The Vertical Sky Component measured at the centre of a window should be no less than 27, or if reduced to below this, no less than 0.8 times the former value.
 - The window should receive at least 25% of available annual sunlight hours and more than 5% during the winter months (September 21st to March 21st), or, where this is not the case, 80% of its former value.


6.0 Window Schedules



1-9 Hallam Road - Rear



2A Glenwood Road - Rear



2A Glenwood Road - Side

7.0 Daylight Impact Results

- 7.1 The Vertical Sky Component has been calculated for each of the 19 assessed windows for both the existing and proposed conditions.
- 7.2 As can be seen in the results below, all windows retain 80% of their current values.
- 7.3 The scheme is therefore compliant with BRE recommendations in relation to daylight impacts.

Vertical Sky Component				
Window	Existing VSC	Proposed VSC	% Retained	Meets BRE Guidance?
1	30.809	29.227	94.87%	Yes
2	34.387	33.218	96.60%	Yes
3	37.388	37.004	98.97%	Yes
4	27.905	25.399	91.02%	Yes
5	33.647	31.693	94.19%	Yes
6	37.263	36.664	98.39%	Yes
7	63.749	61.003	95.69%	Yes
8	33.033	30.976	93.77%	Yes
9	37.166	36.583	98.43%	Yes
10	26.899	25.353	94.25%	Yes
11	33.957	32.901	96.89%	Yes
12	37.400	37.277	99.67%	Yes
13	32.530	31.813	97.80%	Yes
14	36.327	36.027	99.17%	Yes
15	38.118	37.973	99.62%	Yes
16	15.423	17.913	116.14%	Yes
17	29.371	29.282	99.70%	Yes
18	16.256	15.699	96.57%	Yes
19	19.198	17.145	89.31%	Yes

8.0 Sunlight Impact Results

- 8.1 BRE guidance states that only windows which face within 90° of due south need be assessed for sunlight provision. In this instance, 15 windows fall into this category.
- 8.2 The Annual Probable Sunlight Hours has been calculated for these windows for both the existing and proposed conditions using the methodology described previously, over the whole year, and through the "winter months" (September 21st until March 21st).
- 8.3 The BRE guidance states that the sun lighting may be adversely affected if the centre of the window:
- Receives less than 25% of annual hours or less than 5% of winter hours
And
 - Receives less than 80% of its current sunlight hours during either period
and
 - Has a reduction in sunlight over the whole year greater than 4% of annual probable sunlight hours
- 8.4 It is clear from the wording of the above that all three clauses need to be met to qualify as an adverse impact. Thus, if the window does not meet any one of these criteria, the impact is acceptable.
- 8.5 The results below show that the assessed windows retain in excess of 80% of their existing values, both annually and over the winter months.
- 8.6 The scheme is therefore compliant with BRE guidance in relation to sunlight impacts.



8.0 Sunlight Impact Results

Window	Annual Sunlight Hours			Winter Sunlight Hours			Meets Guidance?
	Ex. Hrs Received (%)	Prop. Hrs Received (%)	% Retained	Ex. Hrs Received (%)	Prop. Hrs Received (%)	% Retained	
1	73.042	71.310	97.63%	19.751	18.711	94.74%	Yes
2	80.388	78.032	97.07%	24.879	22.523	90.53%	Yes
3	84.200	82.814	98.35%	30.353	28.967	95.43%	Yes
4	67.013	64.380	96.07%	16.840	14.622	86.83%	Yes
5	79.279	75.676	95.45%	23.770	20.166	84.84%	Yes
6	84.130	83.229	98.93%	30.284	29.383	97.03%	Yes
7	79.210	72.696	91.78%	17.879	14.325	80.12%	Yes
8	78.725	76.022	96.57%	23.216	20.513	88.36%	Yes
9	84.130	84.615	100.58%	30.284	30.769	101.60%	Yes
10	64.796	62.994	97.22%	14.414	12.405	86.06%	Yes
11	80.042	77.893	97.32%	24.532	22.384	91.24%	Yes
12	84.615	84.615	100.00%	30.769	30.769	100.00%	Yes
13	77.062	76.161	98.83%	23.493	22.315	94.99%	Yes
14	82.190	82.051	99.83%	26.681	26.542	99.48%	Yes
15	84.615	84.615	100.00%	30.769	30.769	100.00%	Yes

9.0 Sunlight to Neighbouring Gardens

- 9.1 Residential gardens are generally assessed using the sunlight hours test, but only on March 21st. The guidance describes a well-lit space as being one which receives at least 2 hours of direct sunlight on this date over 50% of its area.
- 9.2 BRE guidance also uses the "80%" rule for this test, whereby the effects are considered acceptable if the remaining sunlight is in excess of 80% of the existing level. This clause applies if the space is reduced to less than 50% of the area well sunlit.
- 9.3 The gardens of the nearest neighbouring properties to the site were assessed using this methodology.
- 9.4 As can be seen, the neighbouring gardens retains over 80% of their existing values and the scheme is therefore compliant with BRE guidance. 1 of the gardens already has zero percentage area that receives 2 hours of sunlight on March 21st.



Site Location

Amenity Sunlight Hours				
Garden	Existing Area Receiving 2 Hours	Proposed Area Receiving 2 Hours	% Retained	Meets BRE Guidance?
G1	34.73%	28.73%	82.72%	Yes
G2	28.83%	23.55%	81.68%	Yes
G3	0.00%	0.00%	100.00%	Yes
G4	21.83%	17.98%	82.38%	Yes
G5	22.52%	21.84%	96.96%	Yes

10.0 Conclusions

- 10.1 Using industry standard methodology, we have made numerical analyses to ascertain the effects of the proposal at 1A Glenwood Road and the levels of change in daylight and sunlight for the windows of the neighbouring properties.
- 10.2 The main criteria used in this analysis to show compliance are the Vertical Sky Component for daylight impacts and Annual and Winter Probable Sunlight Hours for sunlight impacts
- 10.3 As has been shown, the effect on VSC is within the 80% guidance value for all of the assessed windows.
- 10.4 There will therefore be no adverse impact on neighbouring residents in terms of daylight.
- 10.5 In terms of sunlight, the assessed windows retain in excess of 80% of their existing sunlight hours, both annually and over the winter months.
- 10.6 The neighbouring gardens retain over 80% of their existing area which receives 2 hours or more of sunlight on March 21st.
- 10.7 The scheme is therefore compliant with BRE guidance in relation to sunlight impacts.
- 10.8 From a planning perspective therefore, it is the conclusion of this report that the proposed development is entirely acceptable for planning, in daylight and sunlight terms.



T16 Design Ltd.

T: 01206 572452

E: info@t16design.com

W: www.t16design.com

© 2022