

NTS @ A3



Remove existing wall tie bar from full depth of the wall. On opening up consult the engineer for confirmation of final repair detail. For costing purposes allow for replacement with 2No 300x75x8mm ss plates and an M20 s/s bolt. Detail TBC on site.

BAY 13