

From: Planning Support
Subject: FW: Re: Planning Application HGY/2022/2594 at 312, High Road, London, N15 4BN

Sent: 05 December 2022 14:32

Subject: Re: Planning Application HGY/2022/2594 at 312, High Road, London, N15 4BN

Dear Kwaku

Re: Planning Application HGY/2022/2594 at 312, High Road, London, N15 4BN.

Thanks for contacting the Carbon Management Team (Pollution) regarding the above planning application for the Proposed addition of 42 emergency new short-term self-contained residential units, 6 residential flat units and refurbishment of commercial space and I will like to comment as follows.

Having considered the applicant submitted design and access statement and our contaminated land record which shows the site to be within 68m of a contaminated land site (Road haulage) of medium risk as well as within 55m of an hospital also of medium risk, **please be advise that we have no objection to the proposed development in relation to AQ and Land Contamination but the following planning conditions and informative are recommend should planning permission be granted considering the nature of the proposed development.**

1. Land Contamination

Before development commences other than for investigative work:

- a. A desktop study shall be carried out which shall include the identification of previous uses, potential contaminants that might be expected, given those uses, and other relevant information.
- b. Using this information, a diagrammatical representation (Conceptual Model) for the site of all potential contaminant sources, pathways and receptors shall be produced. The desktop study and Conceptual Model shall be submitted to the Local Planning Authority. If the desktop study and Conceptual Model indicate no risk of harm, development shall not commence until approved in writing by the Local Planning Authority.
- c. If the desktop study and Conceptual Model indicate any risk of harm, a site investigation shall be designed for the site using information obtained from the desktop study and Conceptual Model. The site investigation must be comprehensive enough to enable; a risk assessment to be undertaken, refinement of the Conceptual Model, and the development of a Method Statement detailing the remediation requirements.
- d. The risk assessment and refined Conceptual Model shall be submitted, along with the site investigation report, to the Local Planning Authority which shall be submitted to, and approved in writing by, the Local Planning Authority prior to that remediation being carried out on site.
- e. Where remediation of contamination on the site is required, completion of the remediation detailed in the method statement shall be carried out and a report that provides verification that the required works have been carried out, shall be submitted to, and approved in writing by the Local Planning Authority before the development is occupied.

Reason: To ensure the development can be implemented and occupied with adequate regard for environmental and public safety.

2. Unexpected Contamination

If, during development, contamination not previously identified is found to be present at the site then no further development (unless otherwise agreed in writing with the Local Planning Authority) shall be carried out until a remediation strategy detailing how this contamination will be dealt with has been submitted to and approved in writing by the Local Planning Authority. The remediation strategy shall be implemented as approved.

Reasons: To ensure that the development is not put at unacceptable risk from, or adversely affected by, unacceptable levels water pollution from previously unidentified contamination sources at the development site in line with paragraph 109 of the National Planning Policy Framework.

3. NRMM

- a. No works shall commence on the site until all plant and machinery to be used at the demolition and construction phases have been submitted to, and approved in writing by, the Local Planning Authority. Evidence is required to meet Stage IIIB of EU Directive 97/68/ EC for both NOx and PM. No works shall be carried out on site until all Non-Road Mobile Machinery (NRMM) and plant to be used on the site of net power between 37kW and 560 kW has been registered at <http://nrmm.london/>. Proof of registration must be submitted to the Local Planning Authority prior to the commencement of any works on site.
- b. An inventory of all NRMM must be kept on site during the course of the demolitions, site preparation and construction phases. All machinery should be regularly serviced and service logs kept on site for inspection. Records should be kept on site which details proof of emission limits for all equipment. This documentation should be made available to local authority officers as required until development completion.

Reason: To protect local air quality and comply with Policy 7.14 of the London Plan and the GLA NRMM LEZ

4. Demolition/Construction Environmental Management Plans

- a. Demolition works shall not commence within the development until a Demolition Environmental Management Plan (DEMP) has been submitted to and approved in writing by the local planning authority whilst
- b. Development shall not commence (other than demolition) until a Construction Environmental Management Plan (CEMP) has been submitted to and approved in writing by the local planning authority.

The following applies to both Parts a and b above:

- a) The DEMP/CEMP shall include a Construction Logistics Plan (CLP) and Air Quality and Dust Management Plan (AQDMP).
- b) The DEMP/CEMP shall provide details of how demolition/construction works are to be undertaken respectively and shall include:
 - i. A construction method statement which identifies the stages and details how works will be undertaken;
 - ii. Details of working hours, which unless otherwise agreed with the Local Planning Authority shall be limited to 08.00 to 18.00 Monday to Friday and 08.00 to 13.00 on Saturdays;
 - iii. Details of plant and machinery to be used during demolition/construction works;
 - iv. Details of an Unexploded Ordnance Survey;
 - v. Details of the waste management strategy;
 - vi. Details of community engagement arrangements;
 - vii. Details of any acoustic hoarding;
 - viii. A temporary drainage strategy and performance specification to control surface water runoff and Pollution Prevention Plan (in accordance with Environment Agency guidance);
 - ix. Details of external lighting; and,
 - x. Details of any other standard environmental management and control measures to be implemented.
- c) The CLP will be in accordance with Transport for London's Construction Logistics Plan Guidance (July 2017) and shall provide details on:
 - i. Monitoring and joint working arrangements, where appropriate;
 - ii. Site access and car parking arrangements;
 - iii. Delivery booking systems;
 - iv. Agreed routes to/from the Plot;
 - v. Timing of deliveries to and removals from the Plot (to avoid peak times, as agreed with Highways Authority, 07.00 to 9.00 and 16.00 to 18.00, where possible); and
 - vi. Travel plans for staff/personnel involved in demolition/construction works to detail the measures to encourage sustainable travel to the Plot during the demolition/construction phase; and

vii. Joint arrangements with neighbouring developers for staff parking, Lorry Parking and consolidation of facilities such as concrete batching.

d) The AQDMP will be in accordance with the Greater London Authority SPG Dust and Emissions Control (2014) and shall include:

- i. Mitigation measures to manage and minimise demolition/construction dust emissions during works;
- ii. Details confirming the Plot has been registered at <http://nrmm.london>;
- iii. Evidence of Non-Road Mobile Machinery (NRMM) and plant registration shall be available on site in the event of Local Authority Inspection;
- iv. An inventory of NRMM currently on site (machinery should be regularly serviced, and service logs kept on site, which includes proof of emission limits for equipment for inspection);
- v. A Dust Risk Assessment for the works; and
- vi. Lorry Parking, in joint arrangement where appropriate.

The development shall be carried out in accordance with the approved details. Additionally, the site or Contractor Company must be registered with the Considerate Constructors Scheme. Proof of registration must be sent to the Local Planning Authority prior to any works being carried out.

Reason: To safeguard residential amenity, reduce congestion and mitigate obstruction to the flow of traffic, protect air quality and the amenity of the locality.”

5. Combustion and Energy Plant

With the applicant silent on the source of energy to the site, therefore, prior to installation if any, details of the gas boilers to be provided for space heating and domestic hot water should be forwarded to the Local Planning Authority. The boilers to be provided for space heating and domestic hot water shall have dry NOx emissions not exceeding 40 mg/kWh (0%).

Reason: As required by The London Plan Policy 7.14.

6. Air Quality Assessment

In order to minimise increased exposure to existing poor air quality and make provision to address local problems of air quality (particularly within Air Quality Management Areas (AQMAs) where development is likely to be used by large numbers of those particularly vulnerable to poor air quality, such as children or older people),

- An Air Quality Neutral Assessment, taking into account emissions from the installation of temporary and permanent boilers, transport sources and all other sources of emissions must be undertaken and submitted for approval.
- Otherwise, the applicant will need to provide us a detailed AQ assessment of the proposed development taken into consideration all emission sources for the purposes of reaching a conclusion on its significance effects on local air quality.

Reason: To Comply with Policy 7.14 of the London Plan and the GLA SPG Sustainable Design and Construction.

Informative

1. Prior to the refurbishment of the commercial space where relevant, an asbestos survey should be carried out to identify the location and type of asbestos containing materials. Any asbestos containing materials must be removed and disposed of in accordance with the correct procedure prior to any refurbishment or construction works carried out.

I hope the above clarify our position on the application? Otherwise, feel free to revert back to us should you have any further query in respect of the application quoting M3 reference number WK/552730.

Yours sincerely

Kenny Abere
Lead Officer (Pollution)

Carbon Management
6th Floor North
River Park House
225 High Road
Wood Green
N22 8HQ