

Appendix A: Tree Schedule

Tree Nº	Species	Age Class	Height (m)	Diameter (mm)	Crown Spread (m)				Life Exp	Cat	Condition	General Observations	Preliminary Management Recommendations	RPA (m ²)	RPA Radius (m)
					N	E	S	W							
G1	Ash, Elm, Sycamore, Buddleia, Privet, Cherry, Hawthorn, Pear, Oak	EM (avg.)	8 (avg.)	150 (avg.)	/	/	/	/	20+	B2	Fair	Dense group of self-seeded trees. Predominantly SM ash and cherry in north section, with mainly ash and elm in southern section. Some larger scattered mature ash and sycamore trees were present along the southwest section of the group (approx. 300mm in diameter; 12m high, with dense ivy from ground to 10m). Scattered standing deadwood throughout group. North section of group on raised ground approx. 3m above ground level. South section on steep bank from ground level. Evidence of previous tree work - large tree stumps within group containing eco-plugs. [All measurements estimated, and survey limited, as trees were assessed from a distance due to no access permitted]	Remove standing deadwood throughout group. Monitor group due to steep bank and high target area.	/	1.8