

KEY:

- M10/150 Proprietary Renovation Screed
- M10/160 Proprietary self smoothing levelling latex screed

Localized PHS will be required in areas were there is cracking of the slab. Refer to Engineer's condition survey for more information

- K41/100A RAISED ACCESS FLOORING
- M10/140 - WATERPROOF MODIFIED POLYMER SCREED


- ENTRANCE MATTING
- RUBBER FLOORING
- RUBBER FLOORING ANTI-STATIC
- RUBBER FLOORING ANTI-SLIP
- CERAMIC TILE ANTI-SLIP
- BROADLOOM CARPET WITH PRINTED PATTERN
- BROADLOOM CARPET
- CARPET TILE
- NEW TERRAZO TILE
- EPOXY RESIN TERRAZO
- EPOXY RESIN HARDWEARING COATING

Refer to Outline Interior Finishes / Features Condition and Scope of Works HCC-HBA-CC-XX-SH-A-400001

- EFF-01 REPAIR OF EXISTING STONE FLOORING
- EFF-02 REPAIR OF EXISTING TERRAZO
- EFF-03 REPAIR OF EXISTING CORK FLOORING

Copyright Hawkins\Brown Architects
No implied licence exists. This drawing should not be used to calculate areas for the purposes of valuation. Do not scale this drawing. All dimensions to be checked on the site by the contractor and such dimensions to be their responsibility. All work must comply with relevant British Standards and Building Regulations requirements. Drawing errors and omissions to be reported to the architect. To be read in conjunction with Architect's specification and other consultant information.

Rev	Description	Date
P1	Planning Issue	05.04.23



159 St John Street
London EC1V 4QU

mail@hawkinsbrown.com
hawkinsbrown.com

Hawkins\Brown

Project
Haringey Civic Centre
High Rd,
Wood Green,
N22 8LE

Drawing
Level 00 - Civic Centre Ground
Floor Finishes Plan

Scale @ A1
1 : 200

Date
15.03.23

Drawn By
RK

Checked By
JM

Job Number
190149

Status
S2

Purpose of Issue
Issued for
Information

Drawing No.
HCC-HBA-CC-00-DR-A-438100

Rev
P1

