

Livingston Eyre Associates Ltd

67 Lawrence Road

LR2-LEA-00-00-SP-L-0Q30

Revision: P01

Information

19-04-2023

Q30 Seeding/ turfing

General information/requirements

115 Seeded and turfed areas

1. **Growth and development:** Healthy, vigorous grass sward, free from the visible effects of pests, weeds and disease.
2. **Appearance:** A closely knit, continuous ground cover of even density, height and colour.

120 Climatic conditions

1. **General:** Carry out the work while soil and weather conditions are suitable.

145 Watering

1. **Quantity:** Wet full depth of topsoil.
2. **Application:** Even and without displacing seed, seedlings or soil.
3. **Frequency:** As necessary to ensure the establishment and continued thriving of all seeding/turfing.

150 Water restrictions

1. **Timing:** If water supply is or is likely to be restricted by emergency legislation do not carry out seeding/turfing until instructed. If seeding/turfing has been carried out, obtain instructions on watering.

160 Notice

1. Give notice before
 - 1.1. Setting out.
 - 1.2. Applying herbicide.
 - 1.3. Applying fertilizer.
 - 1.4. Preparing seed bed.
 - 1.5. Seeding or turfing.
 - 1.6. Visiting site during maintenance period.
2. Period of notice: 1 week

170 Setting out

1. **Boundaries:** Mark clearly.
2. **Delineation:** In straight lines or smoothly flowing curves as shown on drawings.

Preparation

250 Soil requirements

1. Type
 - 1.1. Turfed areas: Soil for grass swards, as section Q28

Seeding - Not Used

Turfing

400 Cultivated turf

1. Description: FOR LAWNS
2. Supplier: Jubilee Seeds & Turf
 - 2.1. Product reference: JT1 Shade Turf
3. Properties of soil used for turf production: Well drained sandy loam

420 Delivery and storage

1. Timing: Lay turf with minimum possible delay after lifting. If delay occurs, lay turf out on topsoil and keep moist.
2. Frosty weather or waterlogged ground: Do not lift turf.
3. Delivery: Arrange to avoid need for excessive stacking.
4. Stacking height (maximum): 1 m.
5. Dried out or deteriorated turf: Do not use.
6. Certification
 - 6.1. Standard: To BS 3969.

430 Turfing generally

1. Time of year: To be agreed
2. Timing of laying
 - 2.1. Spring and summer: Within 18 hours of delivery.
 - 2.2. Autumn and winter: Within 24 hours of delivery.
3. Weather conditions: Do not lay turf when persistent cold or drying winds are likely to occur or soil is frost bound, waterlogged or excessively dry.
4. Working access: Planks laid on previously laid turf. Do not walk on prepared bed or newly laid turf.
5. Jointing: Laid with broken joints, well butted up. Do not stretch turf.
6. Edges: Whole turfs, trimmed to a true line.
7. Adjusting levels: Remove high spots and fill hollows with fine soil.
8. Consolidating: Lightly and evenly firm as laying proceeds to ensure full contact with substrate. Do not use rollers.
9. Dressing, brushed well in to completely fill all joints: None
10. Watering: Thoroughly water completed turf immediately after laying. Check that water has penetrated into the soil below.

Protecting/cutting

530 First cut of grassed areas

1. Timing: When grass is reasonably dry.
 - 1.1. Height of initial growth: 75 mm
2. Preparation
 - 2.1. Debris and litter: Remove.
 - 2.2. Stones and earth clods larger than 25 mm in any dimension: Remove
3. Height of first cut: 50 mm

4. Mower type: Cylinder
5. Arisings: Remove from site

590 Cleanliness

1. Soil and arisings: Remove from hard surfaces.
2. General: Leave the works in a clean, tidy condition at Completion and after any maintenance operations.

Maintenance

610 Failures of seeding/ turfing

1. Duration: Carry out the following operations from completion of seeding/ turfing until: the end of the rectification period.
2. Defective materials or workmanship: Areas that have failed to thrive.
 - 2.1. Exclusions: Theft or malicious damage.
3. Method of making good: Recultivation and returfing.
4. Timing of making good: Submit proposals

620 Maintaining

1. Description: LAWNS
2. Duration: Carry out the following operations from completion of seeding/ turfing until: the end of the rectification period.
3. Maximum height of growth at any time: 75 mm
4. Preparation: Before each cut remove all litter and debris.
5. Cutting: As and when necessary to a height of 35 mm.
 - 5.1. Arisings: Remove
6. Trimming: All edges.
 - 6.1. Arisings: Remove.
7. Stones brought to the surface: Remove regularly.
 - 7.1. Size: Exceeding 25 mm in any dimension.
8. Areas of settlement: Make good.
9. Watering: Contractor's choice

Ω End of Section



Specification created using NBS Chorus