

1. SUPPORTING HERITAGE STATEMENT

- 1.1.** This statement accompanies the Planning Application for the replacement of windows at 68 Florence Road, London, N4 4DP.
- 1.2.** The property is not listed but it does fall within the Stroud Green Conservation Area.
- 1.3.** The proposal is to replace the existing single-glazed timber sash windows with double glazed timber sash windows. The proposed replacement softwood windows will match the existing box-sash style with no glazing bars to preserve the appearance of the dwelling. The existing two panel part-glazed timber entrance door is to be replaced with a new two panel part-glazed timber entrance door, to match the existing style and appearance. The existing timber fascia, soffits and bargeboards are proposed to be repaired and redecorated to match the existing. The proposal also includes the replacement of the existing half-round black uPVC rainwater goods, to match the existing material, colour and profiles.
- 1.4.** New window frames to be painted white to match existing. New timber entrance door to be decorated and the style shall match existing. New timber fascia, soffits, and bargeboards to be decorated to match existing. New uPVC rainwater goods to be black to match existing appearance.
- 1.5.** The existing timber windows, front entrance door, and fascia/soffits are showing signs of rot and timber decay which are now considered to be beyond economical repair. The uPVC rainwater goods are also reaching the end of their serviceable life and require replacement.
- 1.6.** The proposed replacement windows and entrance door will have no impact on the heritage asset of the appearance of the conservation area. The windows will match the existing windows with the addition of double-glazing panels providing no visual difference to the property. The new timber entrance door shall match the existing style and size. The new rainwater goods, soffits and fascia will all match the existing style and appearance.
- 1.7.** A large number of properties within the Stroud Green Conservation have already installed double glazed windows and entrance doors of timber construction. Some have also received replacement rainwater goods and new fascia & soffits. It is therefore considered that the impact on the conservation area will be negligible and the improvement to the thermal efficiency of the property outweighs any impact.
- 1.8.** The proposed development matches the existing windows & doors and visually appear the same. Likewise, the fascia/soffit repairs and rainwater goods replacements proposed will ensure the property visually appears the same.



- 1.9.** The development will enable the properties occupants to enjoy the effect of modern and efficient windows, entrance door, and effective rainwater goods, which preserve the original appearance and charm of the existing materials securing the properties future.

2. DESIGN

2.1. AMOUNT

No building works is proposed as part of this application.

2.2. LAYOUT

The layout of the property will not be affected by the proposed works.

2.3. SCALE

The scale of the property will not be altered by the works. The existing window openings will remain unchanged with new windows manufactured to fit existing openings. The new timber entrance door will also be manufactured to fit the existing opening. Both the rainwater goods and fascia/soffits will match the existing scope, materials and appearance throughout.

2.4. APPEARANCE

The existing appearance of the property will remain unchanged. Replacement windows will match the box sash style and all fenestrations will remain as existing. The double-glazed panels will provide no visual difference to the existing windows. The new timber entrance door will match the existing, to be a decorated two panel part-glazed door. The repairs and decorations to the fascia and soffits will be in keeping with the existing appearance and will match the existing finish. Likewise, the new uPVC rainwater goods will be black in colour and will not alter the existing overall appearance of the property.

3. ACCESS

- 3.1.** The works are planned for September/October 2023 (pending planning approval) and will be carried out in a single phase of works.
- 3.2.** No part of the proposed works will impede members of the public using the footpath or road.
- 3.3.** The existing pedestrian and vehicle access will remain unaffected by the works.