



NOTES:
THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT F3 ARCHITECTS & INTERIORS DRAWINGS AND SPECIFICATIONS, M&E, FIRE COMPARTMENT STRATEGY, ACOUSTIC, AV, STRUCTURAL ENGINEERS DRAWINGS AND SPECIFICATIONS.



General notes:

- Works subject to further survey and review post trial investigations.
 - For external repairs to external elevations, please refer to proposed elevations.
1. Original C18th cornice. Repair where required and redecorate.
 2. Original C18th architrave. Repair where required and redecorate.
 3. Carefully dismantle original C18th door. Reuse and reinstate to suit new proposed layout.
 4. Allow to restore existing C18th door panel like for like to match historic detail.
 5. Reinstall/Repair like for like historic panelling, redecorate as required to match original historic design.
 6. Reinstall/Reinstall internal partition to original C18th detail to suit new proposed layout. Repair/redecorate as required.
 7. Allow to reinstate/restore panel below window, to match others existing adjacent to match original C18th.
 8. Floor finish TBC, subject to opening up works. Allow like for like where original floorboards survive but finish finishes, they are to be repaired and redecorated.
 9. Carefully restore original C18th ceiling like for like.
 10. Like for like window repairs. Allow to ease out and make good.
 11. Allow to remove modern window and window surrounds. Make good opening to suit proposed layout.
 12. Original C18th skirting. Repair where required and redecorate.

[illegible]

REVISION HISTORY



except for Planning purposes, figured dimensions only are to be taken from this drawing.
All dimensions are in millimetres unless otherwise stated.
All dimensions shall be checked on site prior to works commencing.
Any discrepancies shall be reported to the Architect.
© Copyright F3 Architecture + Design. All rights reserved.

Health and Safety

Refer to relevant Construction (Design and Management) documentation where applicable. The Contractor shall plan, manage and monitor the works inclusive of temporary erection stability. Any works that are found to be unstable in the temporary state are to be reported directly to the structural engineer and Main Contractor/ Package Manager in order to provide safe temporary support. Check on site prior to commencement of works/fabrication etc.

THE PRINTWORKS
819-829, HIGH ROAD, TOTTENHAM,
LONDON, N17 8ER

title
EXISTING ROOM 1 - 821 - FLAT 2 - L01
EXISTING INTERNAL ELEVATIONS

drawn by	scale	paper	project no
DG	As indicated	A1	220428

status	revision
A2 - ISSUED FOR PLANNING	A2.P1

PRINT-F3A-ZZ-ZZ-EL-A-89031