

PROTECTED TREE REPORT (TREE WORKS)

Haringey Council, L4,
Alexandra House, Station
Road N22 7TY

Application number	HGY/2026/1203
Application type	Conservation Area Notification
Site Address:	34 Avenue Road, Hornsey, London, N6 5DW
Proposal	Five Day Notice T1: Ash: Fell - Due to decay at the base, there is an imminent risk of failure in an area with large footfall. The tree has a large crown and is heavily clad with ivy increasing the sail effect and making it highly susceptible to wind throw. It is adjacent to tennis courts and a pathway used by large groups of people to access courts on the upper tier

RECOMMENDATION:	No Objection	
Application date	11/06/2026	
Tree Inspector	DM	Date: 15 th June 2026

Site

The large Ash tree, as marked on the plan, and seen in the photographs, is situated in the rear grounds of the property. It is publicly visible.

Two site visits were deemed necessary to determine the appropriateness of the proposed works.

The location is also within the Conservation Area. This protects every tree with a diameter at breast height (taken at 1.5m) >75mm.

Proposal

Tree works proposed.

Five Day Notice

T1: Ash: Fell - Due to decay at the base, there is an imminent risk of failure in an area with large footfall. The tree has a large crown and is heavily clad with ivy increasing the sail effect and making it highly susceptible to wind throw. It is adjacent to tennis courts and a pathway used by large groups of people to access courts on the upper tier

Issues

I hold no objections to the removal and making safe of the Ash tree under a Five-Day Notice.

The girdling of the ivy 2m at the base has revealed an extensive open cavity (>70% of the circumference) with extensive simultaneous rot, wood borers, very little sound residue or wound wood.

When probed, the 400mm probe disappears in all directions.

The tree is unsafe to climb and to carry out any violent techniques to dismantle. The area to the tennis courts has had to be cordoned off to the public until the Ash tree has been made safe.

Works have been scheduled with the use of a mobile elevated working platform.

The tree should be dismantled down to a safe height leaving some trunk for conservation purposes.

Recommendation

No Objection