Monday, 16 November 2026

Foundation for the Outbuilding

Flat A, 49 Warwick Gardens, N4 1 JD



Ground screw (helical pile)



Typical installation



Ground screw in place



Simple installation

1. Proposed Foundation System

The proposed outbuilding will be supported by galvanised steel ground screws (helical piles), providing a stable foundation without the need for traditional concrete strip foundations or extensive excavation.

The number, positioning and depth of the screws will be determined by the specialist contractor and structural engineer, taking account of the building loads and site-specific ground conditions.

2. Minimal Ground Disturbance and Tree Protection

Ground screws have been selected as a low-impact foundation solution, particularly given the presence of nearby trees.

Unlike conventional concrete foundations, this system requires minimal excavation and has a relatively small ground footprint. Individual screws can be positioned to help avoid significant tree roots, reducing potential disturbance to existing Root Protection Areas (RPAs).

The installation will be carefully managed to:

- Minimise excavation and disturbance to existing soil.
- Avoid significant tree roots wherever practicable.
- Preserve existing garden levels and natural drainage.
- Avoid unnecessary heavy machinery and concrete works.

3. Installation and Technical Considerations

Installation will be undertaken by a specialist contractor following a site-specific assessment of ground conditions and underground services.

The contractor and structural engineer will determine the appropriate screw type, depth, spacing and load-bearing capacity, taking account of the local clay soil conditions and potential seasonal ground movement.

Once installed, the screw heads will be levelled and fitted with suitable connection brackets to support the building's structural subframe.

4. Sustainability and Reversibility

Ground screws offer a more sustainable and potentially reversible alternative to conventional concrete foundations.

They reduce the need for concrete, excavation and removal of existing soil. If the outbuilding is removed in the future, the screws can generally be unscrewed.

5. Conclusion

The proposed ground screw system provides a practical, stable and low-impact foundation solution for the garden outbuilding.

Its use will minimise ground disturbance, reduce potential impacts on nearby tree roots and help preserve the existing garden environment.

The final foundation design and installation will be undertaken by a specialist contractor, with structural verification based on the actual site conditions.