

DRAWING NOTES

1. THIS SERVICES DRAWING IS TO BE READ IN CONJUNCTION WITH QODA'S, THE ARCHITECTURAL & STRUCTURAL ENGINEER'S SPECIFICATION / DRAWINGS.
2. ALL EQUIPMENT SHOWN ON THIS DRAWING DENOTES LOCATIONS OF EXISTING EQUIPMENT. ALL DEVICES WILL BE REPLACE WITH NEW EQUIPMENT USING EXISTING LOCATIONS AND CABLING EXCEPT WHERE NOTED OTHERWISE.
3. ALLOW TO CONNECT NEW OVERHEAD DOOR CLOSURE(S) ON EACH DOOR LEAF AS APPLICABLE ONTO FIRE ALARM SYSTEM LOOP.
4. NEW MAIN FIRE ALARM CONTROL PANEL TO REPLACE EXISTING REPEATER PANEL AND LINK BACK TO EXISTING PANEL ON FIRST FLOOR.
5. EXISTING BELL & CABLING TO BE REMOVED.
6. NEW LOOP SOUNDER ON NEW DETECTOR BASE.
7. NEW DEVICE ADDED.
8. INTERLINKING CABLE BETWEEN EXISTING FIRE ALARM PANEL ON FIRST FLOOR AND NEW GROUND FLOOR PANEL DROPS FROM ABOVE AND RUNS AT HIGH LEVEL IN REDDING TO WC AREA AND ALONG TO BACK ENTRY INTO NEW PANEL LOCATION IN LOBBY.

INDICATES MEND AREA OF WORKS

DO NOT SCALE

Rev	Description	Date
T	TENDER ISSUE	27.02.2023



Client:

Haringey Council
Capital Projects & Property

Project:

Bruce Castle Museum & Park

Drawing Title:
Electrical Services
Fire Alarm Services - Ground Floor

Designed:	Drawn:	Checked:	Scale:	Paper Size:
S.L	S.L	MNT	1:50	A0

Drawing Number:
3156-QODA-XX-00-DR-E-0401

Rev.
T

0 1.50 1m 2m 3m 4m 5m