

REBUILT TO ORIGINAL HEIGHT

DAMP PROOF COURSE UNDER HEADER COURSE

TOP OF HEADER COURSE

REBUILD BRICKWORK USING NEW AND SALVAGED BRICKS TO MATCH COLOUR, TEXTURE AND SIZE OF ORIGINAL WALL. REBUILD WALL TO MATCH EXISTING FLEMISH BOND AND REPOINTED IN 'HOT LIME' MORTAR MIX.

CEMENT RENDER TO BRICKWORK TO BE HACKED OFF AND EXPOSED WALL TO BE REPAIRED AND REBUILT IN BRICKWORK AND LIME RENDER TO MATCH EXISTING

LINE OF EXISTING WALL DOTTED IN RED

AFTER RENDER REMOVED, INSPECT BRICKS FOR FULL SCOPE OF REPAIRS

FACE BRICKWORK CAREFULLY REMOVED. SET ASIDE CLEAN BRICKS AND SET ASIDE FOR REUSE.

PIECING IN DAMAGED BRICKS INDIVIDUALLY AND IN SMALL GROUPS TO REPAIR WALL AFTER RENDER REMOVED AND WHOLE AREA REPOINTED.

REPOINT AREA IN 'HOT LIME' MORTAR IN A MIX TO MATCH EXISTING AND AGREED WITH ARCHITECT. EXISTING MORTAR SHOULD BE CUT OUT USING A PLUGGING CHISEL AND HAND TOOLS ONLY TO A MINIMUM DEPTH OF 25MM. LEAVING SQUARE CUT RECESS TO RECEIVE NEW POINTING. POINTING TO HAVE TAMPED FINISH TO MATCH EXISTING AND SAMPLE AGREED WITH ARCHITECT.

BRICK PIERS TO BE RETAINED AND REPOINTED IN LIME POINTING TO MATCH EXISTING

SOUTH-WEST SIDE

NORTH-EAST SIDE

GROUND LEVEL

INDICATIVE REPAIR OF WALL SECTION G

0 200mm 1m 1:10

Butler Hegarty Architects
Unit 3.2, Islington Studios, 159-163 Marlborough Road, London, N19 4NF
tel: 020 72638933 email: mail@butlerhegartyarchitects.co.uk

please see drawing 0722422/Su13 for existing wall section G.

please see drawing 0722422/Su03 & Su04 for existing wall elevations

Bruce Castle Wall
Title: Indicative Repair of Wall Section G
Drawing No: 0722422-Sk04 Scale: 1:10 @ A3