

AtkinsRéalis



Drainage Design Report

Haringey Borough Council

1 February 2024
5219902-ATK-XX-XX-RP-C-00001

CCCG TOTTENHAM NEW TEACHING BUILDING

Notice

This document and its contents have been prepared and are intended solely as information for Haringey Borough Council and use in relation to CCCG New Teaching Building.

AtkinsRéalis assumes no responsibility to any other party in respect of or arising out of or in connection with this document and/or its contents.

This document has 61 pages including the cover.

Document history

Document title: Drainage Design Report

Revision	Purpose description	Originated	Checked	Reviewed	Authorised	Date
1.0	Drainage Strategy Report	SK	AG	PS/AS	PO	01/02/2024

Client signoff

Client	Haringey Borough Council
Project	CCCG Tottenham New Teaching Building
Job number	5219902
Client signature/date	



Contents

1.	Introduction	
1.1	General.....	6
1.2	The Site	6
2.	Existing Site Features	7
2.1	Topography	7
2.2	Ground Investigation	7
2.3	Existing Drainage and Discharge rates.....	7
3.	Proposed Drainage Strategy	9
3.1	Overview	9
3.2	Planning Legislations	9
3.2.1	National Planning Policy Framework (NPPF) 2023	9
3.2.2	DEFRA Non-statutory Technical Standards for Sustainable Drainage Systems (2015)	9
3.2.3	Haringey London: SuDS Design Requirements for LLFA Technical Assessment	10
	Other	10
3.2.4	Design Standards.....	10
3.3	SuDS Evaluation	11
3.4	Outfall Strategy	12
3.5	Proposed Discharge Rate	13
3.6	Proposed Drainage Solution	14
3.7	Water Quality	15
3.8	Amenity and Biodiversity	15
3.9	Exceedance Assessment.....	16
4.	Foul Drainage.....	17
5.	Maintenance and Operation	19
6.	Conclusion	20

Tables

Table 2-1 – Existing Runoff Rates	8
Table 3-1 - SuDS Evaluation	11
Table 3-2 - CIRIA C753 Outfall Hierarchy Evaluation	12
Table 3-3 – Q_{BAR} Greenfield run off rates (lps)	13
Table 3-4 – Amenity and Biodiversity factors	16



Figures

Figure 1-1 - Site Location Plan (Ref: Google Map)	6
Figure 3-1 – Polystorm Attenuation Crates (Ref: Polystorm & Polystorm Lite Technical Guide, May 2011, pg. 17)..	15
Figure 4-1 – Existing Utilities and Proposed Building Footprint Overlay	17



1. Introduction

1.1 General

AtkinsRéalis has been commissioned to prepare a drainage strategy to support the planning application for the proposed redevelopment of a section of the existing main building at the College of Haringey, Enfield and Northeast London Tottenham Campus, N154RU, National Grid reference TQ 533598 189294. The proposed works involves the demolition of a section of the existing main building and the construction a new four-storey building.

This report reviews the existing surface water and foul sewer drainage networks around the proposed development. From the outcome of the drainage review, the report proposes an appropriate drainage strategy for the proposed development.

1.2 The Site

The entire college site area is 1.19 hectares, this is defined by redline boundary as shown in Figure 1-1. The section of site that is proposed for redevelopment is 620m², this is defined by the yellow boundary in figure 1-1. Access to the site is through the existing Town Hall Approach Road which leads to the High Road.

The proposed design consists of a new four-storey building that will comprise of construction workshops (carpentry, joinery, fabrication and welding, heating, and plumbing and electrical installation) along with science and ICT classrooms.




Figure 1-1 - Site Location Plan (Ref: Google Map)

2. Existing Site Features

2.1 Topography

The site is flat with levels ranging approximately from 14.40m Above Ordnance Datum (AOD) at the north of the site to 14.63m AOD to the south of the site (Refer Appendix A.3). The site is mainly made up of hardstanding area with pedestrian and vehicular parking provisions close the development. There is an existing Tower Block to the east of the development and existing Building Block to the west of the development, the primary access to the section of site that is being redeveloped is through the existing Town Hall Approach Road.

2.2 Ground Investigation

A geo-environmental and geotechnical assessment was carried out by RSK Geosciences in May 2023(Ref: 1922791-01(00)). The study indicates that the site comprises of London Clay and made ground.

The made ground, extends to a depth of 2.8m Below Ground Level (bgl), it is understood this is made up of a cohesive matrix with brick, asphalt, concrete and ceramic. The made ground is underlain by London Clay which extends to a depth of 28m below the existing made ground.

The site is identified as being in zone 2 of the groundwater source protection zone (SPZ).

2.3 Existing Drainage and Discharge rates

A drainage condition and connectivity survey (CCTV) was undertaken by Laser Surveys in June 2023 (Ref: 1879/2, Appendix A.1). From the outcome of the CCTV survey, there is a surface water drainage network that runs from west to east of the site. This discharges to an existing manhole located in the eastern section of the site (MH SW128, Cover Level (CL) 14.35m AOD, Invert level (IL) 12.27m AOD, Refer Appendix A.1).

A review of the foul water drainage network shows a similar route where the foul water discharges into an existing combined sewer manhole (MH CW132, CL 14.32m AOD) in the eastern section of the college's site boundary. It was noted in the CCTV Survey that an existing 150mm foul water pipe which runs underneath the existing main building at southern side of the proposed development was incomplete (Appendix A.1).

From the utility search report (Ref: 424990 A.2) obtained, there is an existing Thames Water (TW) surface water network within the college boundary. The surface water network discharges into existing Thames Water sewer TWMH 6326 (CL 14.11m AOD, IL 12.12m AOD) located within Town Hall Approach Road. The existing foul water network discharges into existing Thames Water manhole TWMH 6327 (CL 13.94m AOD, IL 9.88m AOD) in Town Hall Approach Road (Appendix A.2).

A high-level hydraulic model was prepared to assess existing discharge rates from the existing building. The following criteria were used for the development of the model.

- Impermeable area of 620 m².
- For simulations FEH data used,
- Cv value of 0.75 and 0.84 is used for summer and winter rainfall events.

Table 2-1 summarises the rates for surface water runoff rate events. It is noted that existing flows are discharged unattenuated into the existing drainage network. Refer to Appendix F for the hydraulic model output of the existing surface water model.

Table 2-1 – Existing Runoff Rates

Design Events	Existing runoff rates (l/sec)
1 in 1	8.2
1 in 30	17.1
1 in 100	21.3
1 in 100 + 40% CC	21.9

3. Proposed Drainage Strategy

3.1 Overview

This section provides details of the justification for the selected surface water drainage strategy. A completed Haringey Council drainage proforma as also been included in Appendix D.

3.2 Planning Legislations

The following local plans/policies/guidance and regulations have been reviewed and considered within the proposed Drainage Strategy.

3.2.1 National Planning Policy Framework (NPPF) 2023

The National Planning Policy Framework sets out the Government's planning policies for England and how these should be applied. It provides a framework within which locally prepared plans for housing and other development can be produced.

It states that developments should incorporate sustainable drainage systems, unless there is clear evidence that this would be inappropriate (Clause 173).

3.2.2 DEFRA Non-statutory Technical Standards for Sustainable Drainage Systems (2015)

This document sets out non-statutory technical standards for sustainable drainage systems. They should be used in conjunction with the National Planning Policy Framework and Planning Practice Guidance.

1. S5: *Where reasonably practicable, for developments which have been previously developed, the runoff volume from the development to any highway drain, sewer or surface water body in the 1 in 100-year, 6-hour rainfall event must be constrained to a value as close as is reasonably practicable to the greenfield runoff volume for the same event but should never exceed the runoff volume from the development site prior to redevelopment for that event.*
2. S6: *Where it is not reasonably practicable to constrain the volume of runoff to any drain, sewer or surface water body in accordance with S5 above, the runoff volume must be discharged at a rate that does not adversely affect flood risk.*
3. S7: *The drainage system must be designed so that, unless an area is designated to hold and/or convey water as part of the design, **flooding does not occur on any part of the site for a 1 in 30-year rainfall event.***
4. S8: *The drainage system must be designed so that, unless an area is designated to hold and/or convey water as part of the design, **flooding does not occur during a 1 in 100-year rainfall event in any part of:** a building (including a basement); or in any utility plant susceptible to water (e.g. pumping station or electricity substation) within the development.*
5. S9: *The design of the site must ensure that, so far as is reasonably practicable, **flows resulting from rainfall in excess of a 1 in 100-year rainfall event are managed in exceedance routes that minimise the risks to people and property.***

3.2.3 Haringey London: SuDS Design Requirements for LLFA Technical Assessment

The Haringey London SuDS Design Requirements for LLFA Technical Assessment states:

6. **S4.1: Source control** – *Runoff should be dealt with as close as possible to where it falls.*
Keeping runoff at or near the surface – *Careful consideration is required when determining how runoff will be collected and conveyed through the site.*
Controlling flow – *Flow controls should be designed so that they can be simply understood and easily accessible. No minimum threshold is set for the control of flows, however design should ensure that the flow control is protected from blockage.*
7. **S4.5:** *To decrease the risk of flooding and environmental impact, applicants should seek to minimise the quantity of runoff from a site. Applicants should consider all potential means for reuse and minimisation of discharge of flows from a site.*
8. **S4.7:** *Any rainfall on the site which does not infiltrate will occur as runoff. As rainfall intensities increase the rate of runoff increases. The rate of runoff from developed impermeable areas will be significantly greater than pre-development permeable areas. In accordance with Haringey Development DPD Policy DM25, developments should ensure that there is no increase in flood elsewhere and should seek to achieve Greenfield (GF) rates of runoff.*
9. **S4.7:** *In applying the 50% betterment approach, the applicant should seek to establish the capacity of the existing drainage network (where this solely serves the site), with the aim of reducing flows discharging from the site via the drainage infrastructure by 50%. Where the existing capacity of the storm sewer network serving the site cannot be determined then runoff rates should be limited to a maximum of 3 x GF rate for the respective return period.*
10. **S4.9.2: Climate Change** - *To account for climate change, rainfall intensities should be increased by intensity relevant at the time of submission with allowance made within conveyance and storage calculations. At the time of issue LBoH would recommend making allowance for 30% increase in rainfall intensities to allow for Climate Change with sensitivity testing carried out using 40% increase in rainfall intensities. Any reduction from DEFRA recommendations current at the time of making the application should be agreed as part of the pre-application discussion. Hence, 40% CC is considered for all further calculations.*
11. **SuDS Flows and Volumes – LLFA Technical Assessment Proforma:** *Storage for the 1 in 30 year must be fully contained within the SuDS components. Note that standing water within SuDS components such as ponds, basins and swales is not classified as flooding. Storage should be calculated for the critical duration rainfall event.*
12. **SuDS Flows and Volumes – LLFA Technical Assessment Proforma :** *Runoff generated from rainfall events up to the 1 in 100 year will not be allowed to leave the site in an uncontrolled way. Temporary flooding of specified areas to shallow depths (150-300mm) may be permitted in agreement with the LLFA.*

3.2.4 Other Design Standards

The surface water drainage system has been designed to the following design criteria in accordance with CIRIA C753 SuDS Manual:

- No surcharging in a 1 in 1-year storm event (Sewerage Sector Guidance, C 6.4, Page No 59).
- Minimum pipework self-cleaning velocity is 1m/s (BS EN 752:2017).
- Maximum allowed distance between manholes is 90m. (BS EN 752:2017, Table NA.4).
- Where possible, the excess runoff generated by the proposed development during the 1 in 100-year, 6-hour storm event shall be attenuated onsite.
- The following impermeable factors (PIMP) shall be used:
 - Access roads, hardstanding, parking and roofs: 100%
 - Landscape area: 0% (Sewerage Sector Guidance, C 6.1, Page No 57)

- For simulations, Cv value of 0.75 and 0.84 shall be used for summer and winter rainfall events.
- FEH data shall be used for simulation.

3.3 SuDS Evaluation

A full suite of the SuDS options was evaluated for the surface water drainage system. The evaluation considered the following:

- Attenuation, amenity, biodiversity, and treatment properties of each SuDS element.
- Planning legislation (as described in Section 3.2).
- Site spatial constraints; accessibility, maintenance, and ownership arrangements (which affect the implementation of SuDS).

The results of the evaluation and proposed solution are summarised in Table 3-1

Table 3-1 - SuDS Evaluation

SuDS Type	Evaluation Comments	Conclusion
Rainwater Harvesting	Rainwater harvesting is a viable option for recycling surface water runoff from rainfall events, however due to the intermittent nature of rainfall events throughout the year this methodology is considered not to be sustainable	Not proposed.
Green/Blue Roofs	A Green Roof is proposed on the rooftop (fourth floor) to provide biodiversity benefits. A blue roof is not proposed as it increases building loads, and the continuous movement of water within the membrane presents unquantifiable structural challenges.	Green Roof is proposed on the roof of the fourth floor.
Infiltration Systems	Infiltration systems are assumed not viable due to the makeup of the site's geology. It is understood that the London Clay formation at the site extends to a depth of 28m below the made ground. London Clay formation is considered impermeable in nature and not suitable for infiltration systems.	Not viable.
Proprietary Treatment Systems	Not deemed to be required to the surface water drainage system.	Not proposed.
Filter Strips	Space constraints and low permeability of the site prevents the use of filter strips.	Not viable.
Filter Drains	Space constraints limit the use of filter drains.	Not viable.
Dry/Wet Swales	Space constraints limit the use of swales.	Not viable.

Bio Retention Gardens	Space constraints limit the use of swales.	Not viable.
Tree Pit Drainage	Trees are not proposed within the development boundary due to area constraints.	Not proposed.
Porous Pavements	Most of the site is built up with buildings and hardstanding area, hence limited provision for porous pavements.	Not viable.
Attenuation Storage Tanks	Attenuation Tanks are considered as viable options to provide sufficient attenuation storage and manage surface water discharge into the drainage network.	Viable – Proposed.
Detention Basins	Insufficient space on site.	Not viable.
Ponds/Wetlands	Most of the site is currently covered with buildings and hardstanding and therefore this will limit the provision of pond / wetlands due to space constraints.	Not viable.

3.4 Outfall Strategy

The CIRIA C753 Drainage Hierarchy was assessed and is summarised in Table 3-2.

Table 3-2 - CIRIA C753 Outfall Hierarchy Evaluation

Hierarchy	Evaluation Comments
1. Infiltration	Infiltration systems are assumed not viable due to London Clay formation at shallow depths with approximate thickness of 28m below the made ground. London Clay formation is not suitable for infiltration systems since it is impervious by nature.
2. Discharge to Surface Waters	No watercourses in the vicinity of the site.
3. Discharge to surface water sewer, highway drain, or another drainage system	Proposed surface water discharge into existing Thames Water drainage network.

4. Discharge to a combined sewer	Not applicable.
----------------------------------	-----------------

The outcome of evaluation concludes that the viable option is to discharge surface water runoff to the existing drainage network, which discharges into the existing Thames Water's drainage network within the site.

The Lead Local Flood Authority (LLFA) has been engaged and it has been agreed with the LLFA to discharge surface water into the existing Thames Water drainage network.

The proposed surface water runoff from the new building will be attenuated in an underground attenuation tank. It is proposed to pump the attenuated surface water into an existing inspection chamber (IC SW 16, Ref- N 1879/3 Drainage condition and connectivity survey, CL 14.23m, IL 13.43m OAD) located at the northeast corner of the new building. The drainage network from the inspection chamber discharges into an existing manhole (MH SW 128, Ref- N 1879/3 Drainage condition and connectivity survey, CL 14.35m, IL 12.27m OAD, Refer Appendix A.1). Results from the hydraulic model is provided in Appendix G. A Section 106 indirect connection agreement will be required to discharge to Thames Water sewer network.

3.5 Proposed Discharge Rate

The greenfield flow rate for the site has been estimated using the Environment Agency (EA) guidance 'Rainfall runoff management for developments – Report – SC030219' using the 'Institute of Hydrology Report No. 124 (IH124) methodology for the Flood Estimation for Small Catchments'. The greenfield equivalent run-off rates have been calculated using the 'Interim Code of Practice for Sustainable Drainage Design variant of IH124'. The calculated greenfield rate is 0.24l/s (Appendix B).

In order to avoid blockage and to achieve self-cleansing velocity a practicable minimum discharge rate of 2l/s is proposed. This has been agreed with the London Borough of Haringey. The drainage strategy proposed involves discharging surface water from the proposed development into an existing surface water manhole located within the site boundary at a rate of 2l/s. The proposed discharge rate will provide betterment to the existing runoff. The rates of betterment are shown in Table 3-3.

Table 3-3 – Q_{BAR} Greenfield Run-Off Rates (lps)

Discharge rates(l/s)	Q1 year	Q30 year	Q100 year	Q100 year+40%cc
Pre-redevelopment existing rates	8.2	17.1	21.3	21.9
Proposed rates	2	2	2	2
% Betterment	75.60%	88.30%	90.61%	90.86%

3.6 Proposed Drainage Solution

The proposed drainage strategy is designed to reduce peak flows using the following viable SuDS features below:

- Green Roofs
- Attenuation Storage Tanks

Green Roofs

A green roof is proposed for biodiversity on the fourth floor roof of the new building with a plan area of 273m².

The green roof will have an area of living vegetation, installed on the roof of the building. This will provide biodiversity benefits with ecological value as well as reduction in the rate of surface water runoff.

There are two types of a green roof:

- Intensive: deeper substrates that can support a wide variety of planting.
- Extensive: low substrate depths, simple planting with low maintenance requirements.

The key principles for these systems include:

- The green roof does not only create a biodiverse habitat but also will absorb the first 5mm of rainfall.
- The green roof systems are recommended to have zero fall along the subgrade which is appropriate for structural roof finish.
- Improvement of water quality by retaining the first 5mm of rainfall onsite. Contaminants and silts are often mobilised by the first flush rainfall event (5mm). Thus, by retaining this 5mm of rainfall, contaminants are managed upstream whereby reducing the likelihood of polluting downstream watercourses. Some contaminants can also be filtered out or broken down by bacteria living in the green roof substrate.

Attenuation Storage Tank

The attenuation tanks are proposed to be a geo-cellular units construction such as the Polystorm modular cell system (or similar approved), see Figure 3-1. The attenuation strategy and the upstream green roof catchments will contribute to the reduction of silt build-up in the network.

The proposed attenuation tank is proposed to have a storage volume of 36.5m³, plan area of 32m² and depth of 1.20m (with 95% voids).




Figure 3-1 – Polystorm Attenuation Crates (Ref: Polystorm Technical Guide, May 2011, pg. 17)

3.7 Water Quality

As noted in Section 3.3 SuDS are proposed for the drainage strategy of the development, and will enhance the water quality as follows:

- Green Roofs: Treatment is provided as the rainwater percolates through the Green Roofs substrata (including physical, biological, and chemical treatment through the soil and root up-take zone).

The interception of surface water runoff from the Green Roof will be for the first 5mm of a rainfall event, whereby improving water quality from the site. This benefit is also identified in CIRIA C753.

3.8 Amenity and Biodiversity

Table 3-4 summarises the amenity and biodiversity benefits achieved through implementation of the currently proposed SuDS features. Landscape design is encouraged to propose any additional elements where possible to maximise the amenity and biodiversity of the site.

Table 3-4 – Amenity and Biodiversity Factors

SuDS Type	Amenity Benefits	Biodiversity Benefits
Green Roofs	Green Roofs provide valuable amenity if the roof is to be accessed or overlooked. They also improve the thermal efficiency of the building, improve air quality, and reduce noise levels.	Green Roofs provide high ecological value. They can help to conserve valuable habitat and biodiversity and can provide an oasis of life in an urban environment.
Attenuation Storage Tanks	Attenuation tanks do not provide any direct amenity benefits.	Attenuation tanks do not provide any direct biodiversity benefits.

3.9 Exceedance Assessment

As per Haringey council's SuDS design guidance, the design must ensure that extreme flows i.e. rainfall in excess of a 1 in 100-year (+CC% allowance) can be managed in a safe and predictable manner. Haringey LLFA advocates the distribution of storage within sub catchments across the site layout and design of the site must ensure that flows resulting from rainfall in excess of a 1 in 100-year (+CC allowance) rainfall event are managed in exceedance routes that minimise the risks to people and property, and do not increase flood risk off site. The current design ensures that no flooding occurs during 1 in 100-year (+40% climate change) rainfall event.

4. Foul Drainage

An existing 150mm foul sewer line and 100mm combined sewer was identified as running along the existing building. The construction of the proposed building will show these drainage lines running underneath the proposed building's footprint (Refer Figure 4-1).

It is proposed to divert these sewers over the extent of the new building footprint and reconnect them to the existing drainage network outside the footprint of the proposed building.

The foul sewer will be connected through a new inspection chamber IC FW13 (CL 12.90m, IL 11.55m OAD) built on the line of the existing drainage route (Appendix C). The combined sewer will be connected to existing combined sewer manhole (Appendix C).




Figure 4-1 – Existing Utilities and Proposed Building Footprint Overlay.

The foul discharge generated from the new building is proposed to drain by gravity in accordance with BS EN 752:2017. Considering the number of toilets and washbasins proposed for the building, the anticipated discharge rate from the building is 3.76l/sec. A new 150mm diameter network is proposed to carry foul water from the new building, this will be connected to the existing re-routed foul water

network. It is noted in the CCTV survey there is limited trace of the foul network (Appendix A.1), hence, invert levels of the section diverted foul sewer have been computed based on assumed self-cleansing slope values. The proposed foul drainage strategy is provided in Appendix C.

A Section 106 indirect connection agreement to discharge to the public sewer network will be required in advance of any works. Thames Water has confirmed adequate capacity within the network to manage foul water discharge from the proposed development (Appendix E).

5. Maintenance and Operation

The maintenance of the proposed drainage systems are summarised below:

- Pipework system: Litter, debris removal and periodical jetting. The surface water and foul water drainage has been designed for a self-cleansing velocity of 1m/s.
- Green Roofs (Table 12.5 in CIRIA C753): This will require biannual or annual maintenance, except in the establishment stage (first 12 to 15 months) where more regular maintenance will be required. All maintenance at roof level should comply with strict health and safety requirements.
- Attenuation tank (Table no 21.3 in CIRIA C753): Monthly maintenance will be required to clear out any debris from the catchment where it may cause risk to performance. A unit has been selected that has full maintenance access to allow the unit to be flushed out.
- The pump equipment must be maintained at intervals of four times per year in commercial premises and in accordance with the manufacturer's recommendation (specification for the surface water pumping station, Quote no:MM1316R1, Refer Appendix F).

It is the responsibility of the contractor to ensure the integrity of the drainage system is maintained during construction works. The contractor is to manage the drainage runoff including any pollutants until the drainage system becomes fully operational.

6. Conclusion

The proposed development involves demolition of a section of the existing main building and construction of a new teaching building at The College of Haringey, Enfield and Northeast London Tottenham Campus.

The surface water flows from new building is proposed to attenuate in an underground attenuation tank and pumped into an existing inspection chamber (IC SW 16, Ref- N 1879/3 Drainage condition and connectivity survey, CL 14.23m, IL 13.43m OAD) at a controlled rate of 2l/s, located at the northeast corner of the new building. The existing inspection chamber ultimately discharges into the existing Thames Water (TW) manhole (MH SW 128, Ref- N 1879/3 Drainage condition and connectivity survey, CL 14.35m, IL 12.27m OAD).

Existing foul water drainage and a combined network present to the west of the existing building was identified to clash with the footprint of proposed building. It is proposed to be rerouted to avoid the identified clashes (Appendix C). The foul discharge generated from the new building is proposed to be drained by gravity to a new 150mm diameter drainage network which will convey foul drainage from the new building and proposed to be connected to the existing rerouted foul water network with a new manhole IC FW11 (CL 14.20m, IL 12.70m OAD). Refer to Appendix C for the foul and storm water drainage strategy.

A Section 106 indirect connection agreement will be required to discharge to Thames Water sewer network. Thames water has confirmed there is adequate capacity within their network to accommodate the proposed foul water discharge from the new development.

APPENDICES

Appendix A. Existing Information

A.1 CCTV Condition Survey

[illegible]

- Drainage pipe sizes (where shown) have been gauged from the surface for safety reasons and should be regarded as approximate only.
- Tree species (where shown) should be treated with caution and expert identification is advised.
- Although this is a digital survey the accuracy and amount of detail shown is only commensurate with the graphical scale of mapping as specified. Care should be exercised when working to larger scales.
- Visible features in the vicinity of the boundaries as shown above, may not represent the extent of legally conveyed ownership.
- Whilst every effort has been made to achieve accuracy on this plan, CRUCIAL clearance dimensions, levels and invert levels should be checked prior to design and construction.
- Kerb levels have been taken in the bottom of the channel.


(UNIT TO SCALE)

CAPITAL CITY COLLEGE GROUP		
PO BOX 541	SURVEYOR	S.L. / P.J.
TELFORD		
TF2 2LN	DATE	07.06.202

NO	DATE	REVISION		
		DRAWING NO	N 1879/3	REV 0
		SCALE	1 : 100	
		SEE ALSO DWG NOS	11378-E	
		SHEET	3 OF 3	
		REF NO	N 1879	

A.2 Utility Search Maps

Asset Location Search Sewer Map - ALS/ALS Standard/2023 4771990



The width of the displayed area is 500 m and the centre of the map is located at OS coordinates 533601,189323
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map (2020) with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
751C	n/a	n/a
751A	n/a	n/a
7536	n/a	n/a
7539	n/a	n/a
7537	n/a	n/a
751D	n/a	n/a
7538	n/a	n/a
751B	n/a	n/a
7508	15.5	12.89
7510	15.7	14.09
7509	15.46	14.14
7507	15.27	13.71
7512	n/a	n/a
7506	15.12	12.3
8502	15.51	13.28
631A	15.7	12.56
6301	15.62	10.94
8302	14.8	13.24
8401	14.78	13.49
7408	14.73	12.56
6403	15.96	11.33
7407	14.89	13.67
7406	14.77	13.38
741D	n/a	n/a
741C	n/a	n/a
6408	16.24	14.49
741F	n/a	n/a
641A	n/a	n/a
7403	n/a	n/a
7404	15.25	13.5
7405	15.54	13.62
6407	16.6	14.78
741E	n/a	n/a
74XR	n/a	n/a
741A	n/a	n/a
7402	15.61	14.56
6404	16.85	14.98
741B	n/a	n/a
641B	n/a	n/a
6409	16.86	12.35
6402	16.9	15.01
7401	15.65	14.62
831C	n/a	n/a
831I	n/a	n/a
821E	n/a	n/a
831F	n/a	n/a
831G	n/a	n/a
6217	12.87	11.29
6216	12.76	11.31
7207	11.58	10.09
721C	n/a	10.27
721Q	n/a	n/a
721R	n/a	n/a
722N	n/a	n/a
721I	n/a	n/a
721H	n/a	n/a
7233	12.41	n/a
721S	n/a	n/a
721G	n/a	n/a
721T	n/a	n/a
721P	n/a	n/a
721F	n/a	n/a
721O	n/a	n/a
722L	n/a	n/a
721N	n/a	n/a
721E	n/a	n/a
721M	n/a	n/a
721D	n/a	n/a
721L	n/a	n/a
721J	n/a	n/a
721K	n/a	n/a
722M	n/a	n/a
7232	12.4	n/a
7229	12.38	10.27
721U	n/a	n/a
722Q	n/a	n/a
7238	12.63	10.72
7228	12.13	10.41
722F	n/a	n/a
722G	n/a	n/a
722H	n/a	n/a
722A	n/a	n/a
722I	n/a	n/a
722J	n/a	n/a
722B	n/a	n/a
722K	n/a	n/a
722C	n/a	n/a
722D	n/a	n/a
721Z	n/a	n/a
721Y	n/a	n/a
721X	n/a	n/a

Manhole Reference	Manhole Cover Level	Manhole Invert Level
721W	n/a	n/a
721V	n/a	n/a
7206	11.55	10.61
7205	11.55	10
821H	n/a	n/a
821C	n/a	n/a
82XQ	n/a	n/a
82WY	n/a	n/a
821G	n/a	n/a
82XR	n/a	n/a
6104	10.75	10.09
711D	n/a	n/a
6106	10.57	9.14
711F	n/a	n/a
8102	10.51	9.63
8105	n/a	n/a
71XT	n/a	n/a
8113	n/a	n/a
8103	n/a	n/a
711E	n/a	n/a
8108	n/a	n/a
8107	n/a	n/a
7102	11.2	10.58
711C	n/a	n/a
711A	n/a	n/a
8110	n/a	n/a
7103	11.28	10.42
8109	n/a	n/a
6107	11.15	9.98
8101	11.04	9.82
8112	n/a	n/a
711B	n/a	n/a
8111	n/a	n/a
6108	11.28	8.61
6201	11.77	10.54
82XT	n/a	n/a
721A	n/a	n/a
8201	11.2	8.82
82WZ	n/a	n/a
8106	n/a	n/a
8104	n/a	n/a
7111	n/a	n/a
70TS	n/a	n/a
70RZ	n/a	n/a
70TT	n/a	n/a
70TP	n/a	n/a
701B	n/a	n/a
70VT	n/a	n/a
4504	16.65	14.46
4505	16.66	14.47
4506	17.01	16.04
5502	16.8	15.82
5501	16.85	14.06
5505	16.88	15.31
5504	16.91	15.33
5503	16.94	13.8
551A	n/a	n/a
551D	n/a	n/a
35WP	n/a	n/a
35WR	n/a	n/a
351C	n/a	n/a
35WW	n/a	n/a
35VY	n/a	n/a
6405	16.89	15.14
6406	16.74	15.24
6401	16.99	12.61
6504	16.97	14.92
7501	16.3	15.19
6503	17.09	14.32
6502	16.93	13.75
65WS	n/a	n/a
65WX	n/a	n/a
5507	17.22	15.52
651C	n/a	n/a
651B	n/a	n/a
551C	n/a	n/a
551F	n/a	n/a
651A	n/a	n/a
65WW	n/a	n/a
65WZ	n/a	n/a
34SS	n/a	n/a
34VQ	n/a	n/a
3412	15.61	13.82
34RZ	n/a	n/a
34WT	n/a	n/a
3411	15.79	13.38
34WR	n/a	n/a
34SR	n/a	n/a
3410	15.71	14.13
3409	15.84	14.67
3405	15.34	13.6
3407	15.28	14.35
3406	15.39	12.37

Manhole Reference	Manhole Cover Level	Manhole Invert Level
34WW	n/a	n/a
3408	16.1	14.89
34WX	n/a	n/a
34WP	n/a	n/a
4401	16.8	14.88
4402	17.12	15.52
4403	16.98	15.6
5401	17.04	15.46
5406	17.09	16.08
5402	17.11	15.73
5405	17.15	16.31
5404	16.98	15.74
5403	16.97	14.37
3311	n/a	n/a
321F	n/a	n/a
3308	13.96	11.9
3309	14.02	13.31
4303	13.92	11.07
4302	14.01	13.13
4301	13.83	12.99
431I	n/a	n/a
431J	n/a	n/a
431G	n/a	n/a
431E	n/a	n/a
431H	n/a	n/a
431K	n/a	n/a
521B	n/a	n/a
521A	n/a	n/a
5201	n/a	10.08
5202	14.61	13.15
531A	n/a	n/a
7237	n/a	n/a
7204	12.95	9.43
722O	n/a	n/a
722P	n/a	n/a
7236	n/a	n/a
7227	12.8	10.98
6214	13.34	11.91
7226	12.9	11.06
7202	12.97	11.14
7203	13.09	11.08
7201	12.79	11.74
6213	13.9	12.1
6202	14.72	12.24
6324	14.47	12.63
7307	13.42	12.36
6325	14.38	12.67
6327	13.94	9.88
6326	14.11	12.12
7306	13.7	12.89
7304	13.67	12.28
6315	15.35	12.23
6314	15.05	10.47
6313	15.15	12.47
6312	15.14	10.54
7301	14.39	12.93
7303	14.51	13.73
7302	14.84	13.15
311I	n/a	n/a
311J	n/a	n/a
311H	n/a	n/a
4104	11.76	10.6
4103	11.8	9.86
4101	11.97	10.1
4102	11.93	10.94
311K	n/a	n/a
321C	n/a	n/a
321D	n/a	n/a
4201	12.41	11.51
4202	12.5	10.37
4203	12.48	11.49
5002	10.99	9.61
5001	11.01	9.2
5011	10.58	9.71
5104	11.1	9.05
5106	10.64	8.64
5105	10.74	9.94
5103	11.1	9.75
511A	n/a	n/a
5102	11.16	9.33
5101	11.13	9.83
5118	11.25	9.42
5117	11.4	9.98
5119	11.5	9.5
5121	12.15	10.13
5120	12.15	9.63
5206	n/a	n/a
5205	12.85	9.76
5203	13.79	9.93
5204	13.8	10.6
301F	n/a	n/a
6011	10.44	8.39
6001	10.35	9.8

Manhole Reference	Manhole Cover Level	Manhole Invert Level
6102	10.37	9.41
601A	n/a	n/a
601B	n/a	n/a
6103	10.5	9.26
6003	10.35	7.75
6105	10.41	7.89
6004	10.36	9.05
6118	n/a	n/a
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.		



Asset Location Search - Sewer Key

Public Sewer Types (Operated and maintained by Thames Water)

	Foul Sewer: A sewer designed to convey waste water from domestic and industrial sources to a treatment works.
	Surface Water Sewer: A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.
	Combined Sewer: A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.
	Storm Sewer
	Sludge Sewer
	Foul Trunk Sewer
	Surface Trunk Sewer
	Combined Trunk Sewer
	Foul Rising Main
	Surface Water Rising Main
	Combined Rising Main
	Vacuum
	Thames Water Proposed
	Vent Pipe
	Gallery

Other Sewer Types (Not operated and maintained by Thames Water)

	Sewer		Culverted Watercourse
	Proposed		Decommissioned Sewer
	Content of this drainage network is currently unknown		Ownership of this drainage network is currently unknown

Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plan are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate the direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.

Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

	Air Valve		Meter
	Dam Chase		Vent
	Fitting		

Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

	Ancillary		Drop Pipe
	Control Valve		Weir

End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol. Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

	Inlet		Outfall
	Undefined End		

Other Symbols

Symbols used on maps which do not fall under other general categories.

	Change of Characteristic Indicator		Public / Private Pumping Station
	Invert Level		Summit

Areas

Lines denoting areas of underground surveys, etc.

	Agreement
	Chamber
	Operational Site

Ducts or Crossings

	Casement	Ducts may contain high voltage cables. Please check with Thames Water.
	Conduit Bridge	
	Subway	
	Tunnel	

5) 'na' or '0' on a manhole indicates that data is unavailable.

6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimeters. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology, please contact Property Searches on 0800 009 4540.

A.3 Topographical Survey



Appendix B. Micro drainage Source Control Calculations

Rural Runoff Calculator

Micro Drainage

IH 124

IH 124 Input

Return Period (Years)

Area (ha)

SAAR (mm)

Soil

Growth Curve

Partly Urbanised Catchment (QBAR)

Urban

Region

Calculate

Results

QBAR rural (l/s)

189.9

QBAR urban (l/s)

189.9

Return Period Flood

Region	QBAR (l/s)	Q (100yrs) (l/s)	Q (1 yrs) (l/s)	Q (2 yrs) (l/s)	Q (5 yrs) (l/s)	Q (10 yrs) (l/s)	Q (20 yrs) (l/s)	Q (25 yrs) (l/s)	Q (30 yrs) (l/s)	Q (50 yrs) (l/s)	Q (100 yrs) (l/s)	Q
Region 1	189.9	470.9	161.4	172.5	227.8	274.3	324.4	343.3	358.7	403.3	470.9	
Region 2	189.9	499.3	165.2	173.5	224.0	269.6	324.2	344.0	360.2	412.8	499.3	
Region 3	189.9	394.9	163.3	179.2	237.3	275.3	311.8	323.9	333.7	359.6	394.9	
Region 4	189.9	487.9	157.6	170.2	233.5	282.9	337.5	356.6	372.0	418.1	487.9	
Region 5	189.9	675.9	165.2	169.7	244.9	314.2	397.0	429.5	456.1	539.6	675.9	
Region 6/Region 7	189.9	605.7	161.4	167.3	243.0	307.6	380.3	407.8	430.3	497.4	605.7	
Region 8	189.9	459.5	148.1	167.8	233.5	282.9	332.1	348.6	361.9	402.1	459.5	
Region 9	189.9	413.9	167.1	176.3	229.7	269.6	309.7	323.5	334.8	367.6	413.9	
Region 10	189.9	394.9	165.2	176.8	225.9	262.0	298.5	311.4	321.9	351.2	394.9	
Ireland National	189.9	349.3	161.4	182.3	227.8	256.3	285.1	294.3	301.8	322.8	349.3	
Ireland East	189.9	360.7	161.4	182.3	229.7	262.0	292.2	301.9	309.4	330.4	360.7	
Ireland South	189.9	349.3	161.4	182.3	225.9	256.3	285.1	294.3	301.8	322.8	349.3	
Ireland West	189.9	338.0	161.4	182.3	224.0	252.5	278.4	286.7	293.2	311.4	338.0	
Ireland Greater Dublin	189.9	495.5	161.4	174.7	260.1	317.1	371.7	389.2	403.3	442.4	495.5	

OK Cancel Help

Enter Return Period between 1 and 1000



QBAR rural for 50ha: = 189.9l/s

QBAR rural for 1ha: = 3.8l/s

QBAR rural for .062ha: = 0.24l/s

Appendix C. Proposed Drainage Strategy Layout

100
0 10
Millimetres



LEGEND :

EXISTING :

- EXISTING FOUL WATER SEWER
- EXISTING COMBINED SEWER
- EXISTING SURFACE WATER DRAINAGE
- EXISTING FOUL WATER NETWORK TO BE DIVERTED
- EXISTING COMBINED SEWER TO BE DIVERTED
- TO BE DEMOLISHED

PROPOSED :

- PROPOSED/DIVERTED FOUL WATER NETWORK
- DIVERTED COMBINED SEWER
- PROPOSED SURFACE WATER NETWORK
- PROPOSED RISING MAIN FOR SURFACE WATER
- PROPOSED VENT PIPE (100Ø)
- PROPOSED CELLULAR STORAGE TANK
POLYSTORM ATTENUATION TANK OR SIMILAR
APPROVED
- PROPOSED SURFACE WATER PUMPING MANHOLE
- PROPOSED SURFACE WATER INSPECTION CHAMBER
- PROPOSED FOUL WATER INSPECTION CHAMBER
- PROPOSED SURFACE WATER INSPECTION CHAMBER
INSIDE BUILDING
- PROPOSED FOUL WATER INSPECTION CHAMBER
INSIDE BUILDING
- PROPOSED VENT (100 X 100)
- COVER LEVEL
- INVERT LEVEL
- REFER NOTE 7
- RWP(RA)
- RODDING EYE
- BACKDROP
- SOIL VENT PIPE
- STUB STACK
- CHANNEL DRAIN

**SAFETY, HEALTH AND ENVIRONMENTAL
INFORMATION**

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following:


MAINTENANCE/CLEANING

1. POSSIBILITY OF MULTIPLE BURIED SERVICES.

DECOMMISSIONING/DEMOLITION


1. POSSIBILITY OF MULTIPLE BURIED SERVICES.

It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement.



- NOTES:**
- PIPE DIAMETERS ARE NOT TO SCALE.
 - ALL DIMENSIONS AND PIPE DIAMETERS ARE IN MILLIMETRES UNLESS STATED OTHERWISE.
 - DRAINAGE LAYOUT IS DEPENDENT ON AGREEMENT FROM LEAD LOCAL FLOOD AUTHORITY AND EARLY ENGAGEMENT SHOULD BE ENSURED.
 - THE DRAINAGE NETWORK DESIGN SHOWN IS IN LINE WITH APPROVED DOCUMENT 'H'. CONTRACTOR TO ENSURE THE EXTERNAL DRAINAGE DESIGN ALIGNS WITH THE FINAL BUILDING SERVICES DESIGN BEFORE CONSTRUCTION.
 - LOCATION OF RAINWATER PIPES AND FOUL CONNECTIONS TO BE READ FROM BUILDING SERVICES/PUBLIC HEALTH DRAWINGS AS APPLICABLE.
 - SLOPES, COVER AND INVERT LEVELS MENTIONED ARE ASSUMED. VALUES TO BE CONFIRMED AND ADJUSTED ON SITE TO MEET DESIGN REQUIREMENTS.
 - LOCATION OF PROPOSED CHAMBERS AND PIPES TO BE COORDINATED AND REVISED AS REQUIRED ONCE EXTERNAL SITE LEVELS ARE RECEIVED.
 - IMPERMEABLE 1MM HDPE MEMBRANE WITH WOVEN GEOTEXTILE LINER TO BE PROVIDED BELOW ATTENUATION STORAGE TANK.
 - THE MEP DRAINAGE NETWORK SHOWN INSIDE BUILDING IS INDICATIVE ONLY.

P01	29/01/2024	FOR STAGE 3 APPROVAL	SK	AG	PO
Rev.	Date	Description	By	Chk'd	App'd
Drawing Suitability					Status
FOR STAGE APPROVAL					S3
Nova North 11 Bressenden Place Victoria London SW1E 5BY Tel: +44 1454 662000 www.atkinsrealis.com © AtkinsRéalis (2023)					
Client					
CAPITAL CITY COLLEGES GROUP					
Project Title					
CCCG TOTTENHAM NEW TEACHING BUILDING					
Drawing Title					
DRAINAGE STRATEGY LAYOUT					
Scale	Designed	Drawn	Checked	Authorised	
1:150	SK	KNS	AG	PO	
Original Size	Date	Date	Date	Date	
A1	15/01/2024	15/01/2024	15/01/2024	29/01/2024	
Drawing Number				Revision	
5219902-ATK-XX-XX-DR-CI-00001				P01	



Appendix D. Haringey Council SuDS Proforma

SuDS Flows and Volumes – LLFA Technical Assessment Proforma

This form identifies the information required by Haringey LLFA to enable technical assessment of flows and volumes determined as part of drainage / SuDS calculations.

*Note : * means delete as appropriate; Numbers in brackets refer to accompanying notes.*

SITE DETAILS

- 1.1 Planning application reference ...CCCG TOTTENHAM, NEW TEACHING BILDING
- 1.2 Site name: ...CCCG TOTTENHAM, NEW TEACHING BUILDING...
- 1.3 Total application site area ⁽¹⁾ 620...m² 0.062...ha

VOLUME AND FLOW DESIGN INPUTS

- 2.1 Site area which is positively drained by SuDS ⁽²⁾ ...620...m²
- 2.2 Impermeable area drained pre development ⁽³⁾ 620m² ...
- 2.3 Impermeable area drained post development ⁽³⁾ ...620...m²
- 2.4 Additional impermeable area (2.3 minus 2.2) ...0...m²
- 2.5 Predevelopment use ⁽⁴⁾ ~~Greenfield~~ /-Brownfield / ~~Mixed~~*
- 2.6 Method of discharge ⁽⁵⁾ ~~Infiltration / waterbody / storm sewer / combined sewer~~*
- 2.7 Infiltration rate (where applicable) N/A
- 2.8 Influencing factors on infiltration N/A.....
- 2.9 Depth to highest known ground water table.....NA.....
- 2.10 Coefficient of runoff (Cv) ⁽⁶⁾ Cv of 100% for impermeable area.....
- 2.11 Justification for Cv used Sewer for Adoption
- 2.12 FEH rainfall data used (Note that FSR is no longer the preferred rainfall calculation method) Y/N–
- 2.13 Will storage be subject to surcharge by elevated water levels in watercourse / sewer Y/~~N~~
- 2.14 Invert level at outlet (invert level of final flow control) 12.415...mAOD
- 2.15 Design level used for surcharge water level at point of discharge⁽¹⁴⁾...Not available...mAOD

SuDS Flows and Volumes – LLFA Technical Assessment Proforma

CALCULATION OUTPUTS

Sections 3 and 4 refer to site where storage is provided by attenuation and / or partial infiltration. Where all flows are infiltrated to ground omit Sections 3 -5 and complete Section 6.

3.0 Defining rate of runoff from the site

- 3.1 Max. discharge for 1 in 5 year rainfall ...32.25...l/s/ha, ...2...l/s for the site
- 3.2 Max. discharge for Q_{med} rainfall ...32.25.....l/s/ha, ...2...l/s for the site
- 3.3 Max. discharge for 1 in 30 year rainfall 32.25...l/s/ha, ...2.....l/s for the site
- 3.4 Max. discharge for 1 in 100 year rainfall ...32.25...l/s/ha, ...2.....l/s for the site
- 3.5 Max. discharge for 1 in 100 year plus 30%CC 32.25...l/s/ha, ...2...l/s for the site

4.0 Attenuation storage to manage peak runoff rates from the site

- 4.1 Storage - 1 in 5 year 9m³ ...0.014m³/m² (of developed impermeable area)
- 4.2 Storage - 1 in 30 year ⁽⁷⁾ 15m³ ...0.024m³/m²
- 4.3 Storage - 1 in 100 year ⁽⁸⁾ 21m³ ...0.034m³/m²
- 4.4 Storage - 1 in 100 year plus 40%CC ⁽⁹⁾ 28.5m³ ...0.051m³/m²

5.0 Controlling volume of runoff from the site

- 5.1 Pre development runoff volume⁽¹⁰⁾ ...N/A for the site
- 5.2 Post development runoff volume (unmitigated) ⁽¹⁰⁾ ...NA for the site
- 5.3 Volume to be controlled/does not leave site ^(5.2 - 5.1) ...NA for the site
- 5.4 Volume control provided by
 - Interception losses⁽¹¹⁾ NA
 - Rain harvesting⁽¹²⁾ NA
 - Infiltration (even at very low rates) NA
 - Separate area designated as long term storage⁽¹³⁾ NA
 - Attenuation 36.5m³
- 5.5 Total volume control (sum of inputs for 5.4) 36.5m³

SuDS Flows and Volumes – LLFA Technical Assessment Proforma

Notes

1. All area with the proposed application site boundary to be included.
2. The site area which is positively drained includes all green areas which drain to the SuDS system and area of surface SuDS features. It excludes large open green spaces which do not drain to the SuDS system.
3. Impermeable area should be measured pre and post development. Impermeable surfaces includes, roofs, pavements, driveways and paths where runoff is conveyed to the drainage system.
4. Predevelopment use may impact on the allowable discharge rate. The LLFA will seek for reduction in flow rates to GF status in all instances. The design statement and drawings explain / demonstrate how flows will be managed from the site.
5. Runoff may be discharge via one or a number of means.
6. Sewers for Adoption 6th Edition recommends a Cv of 100% when designing drainage for impermeable area (assumes no loss of runoff from impermeable surfaces) and 0% for permeable areas. Where lower Cv's are used the application should justify the selection of Cv.
7. Storage for the 1 in 30 year must be fully contained within the SuDS components. Note that standing water within SuDS components such as ponds, basins and swales is not classified as flooding. Storage should be calculated for the critical duration rainfall event.
8. Runoff generated from rainfall events up to the 1 in 100 year will not be allowed to leave the site in an uncontrolled way. Temporary flooding of specified areas to shallow depths (150-300mm) may be permitted in agreement with the LLFA.
9. Climate change is specified as 30% increase to rainfall intensity, unless otherwise agreed with the LLFA / EA.
10. To be determined using the 100 year return period 6 hour duration rainfall event.
11. Where Source Control is provided Interception losses will occur. An allowance of 5mm rainfall depth can be subtracted from the net inflow to the storage calculation where interception losses are demonstrated. The Applicant should demonstrate use of subcatchments and source control techniques.
12. Please refer to Rain harvesting BS for guidance on available storage.
13. Flow diverted to Long term storage areas should be infiltrated to the ground, or where this is not possible, discharged to the receiving water at slow flow rates (maximum 2 l/s/ha). LT storage would not be allowed to empty directly back into attenuation storage and would be expected to drain away over 5-10 days. Typically LT storage may be provided on multi-functional open space or sacrificial car parking areas.
14. Careful consideration should be used for calculations where flow control / storage is likely to be influenced by surcharged sewer or peak levels within a watercourse. Storm sewers are designed for pipe full capacity for 1 in 1 to 1 in 5year return period. Beyond this, the pipe network will usually be in conditions of surcharge. Where information cannot be gathered from Thames Water, engineering judgement should be used to evaluate potential impact (using sensitivity analysis for example).
15. In controlling the volume of runoff the total volume from mitigation measures should be greater than or equal to the additional volume generated.

Appendix E. Confirmation from Thames Water & LLFA on Capacity and proposed rates

To: Leung, Ka Po <KaPo.Leung@atkinsrealis.com>
Cc: Salako, Ade <Ade.Salako@atkinsrealis.com>
Subject: RE: New Engineering Building at the College of Haringey, Enfield and North East London

Hi Ka,

I hope you are well. It was nice seeing you and Ade this morning.

I am happy with the methodology, Discharge rates and as the strategy proposed within your email below.

Thank you again.

Best Regards,

Pankit Shah PG Dip, B.Eng., MCHT
Flood & Water Management Lead

Haringey London
4th Floor Alexandra House, 10 Station Road, Wood Green, London N22 7TR

Mob: 07974620315
E: Pankit.Shah@haringey.gov.uk

www.haringey.gov.uk
pankit@haringeycouncil.gov.uk
[facebook.com/haringeycouncil/](https://www.facebook.com/haringeycouncil/)



Please consider the environment before printing this email.



From: Leung, Ka Po <KaPo.Leung@atkinsrealis.com>
Sent: Thursday, December 14, 2023 11:44 AM
To: Pankit Shah <Pankit.Shah@haringey.gov.uk>
Cc: Salako, Ade <Ade.Salako@atkinsrealis.com>
Subject: RE: New Engineering Building at the College of Haringey, Enfield and North East London

Hi Pankit,

As discussed in the pre-application meeting regarding the new engineering building for the College of Haringey, Enfield and North East London, please could Haringey Council confirm they are in agreement with the following discussion points from the outcome of meeting:

- A minimum discharge rate of 2 l/s will be applied to discharge into existing surface water sewer.
- The strategy will manage rainfall event of 1 in 100-year +40% climate change on-site.
- Hydraulic calculations will be provided within the drainage strategy to show required on-site storage volumes.
- Green roof will provide biodiversity and reduces the rate of surface water runoff.
- Attenuation will be provided by an underground geocellular storage tank northeast of the proposed development to attenuate surface water runoff from the proposed development.

Warm regards,

Ka Po Leung MEng GMICE
Graduate Civil Engineer
Design & Advanced Technology
AtkinsRéalis
Nova North | 11 Bressenden Place
London, SW1E 8BY, UK

From: Natalya Bacon <Natalya.Bacon@thameswater.co.uk>
Sent: 04 October 2023 10:02
To: Salako, Ade <Ade.Salako@atkinsrealis.com>
Subject: RE: DS6107911: Pre-Planning Enquiry College of Haringey, Enfield and East London

Hi Ade,

Thanks for your email.

Is the area highlighted in purple only the area you propose to redevelop?

Since the number of students is not changing there should be no issues with a foul water capacity. The proposed point of the connection you have chosen is between TWMH7204 and 6105. I cannot locate MH6105.

However, when there is any re-development proposed we would expect to see a reduction in surface water discharge rates.

Please confirm if the area you have provided for overall college site or only for the area you are redeveloping?

What is the proposed surface water discharge rate?

Management of surface water from new developments should follow London Plan Policy SI 13 Sustainable drainage, subsection B (the drainage hierarchy). Typically, greenfield run off rates of 5l/s/ha should be aimed for using the drainage hierarchy.

The hierarchy lists the preference for surface water disposal as follows;

- Store Rainwater for later use
- Use infiltration techniques, such as porous surfaces in non-clay areas
- Attenuate rainwater in ponds or open water features for gradual release
- Discharge rainwater direct to a watercourse > Discharge rainwater direct to a surface water sewer/drain
- Discharge rainwater to the combined sewer.

If possible, prioritise green SuDS such as tree pits and green roofs [rain gardens and swales for small sites] that are more effective in low-return period storms, as opposed to attenuation tanks. The proposed 5l/s is too high for the size of the proposed development.

Please also provide the total surface water run-offs data (flows) for existing vs. proposed site for various range of storms (1:1yr, 1:30yr & 1:100yr).


	Existing Runoff (l/s)	Proposed Runoff (l/s)
1 in 1		
1 in 30		
1 in 100		
1 in 100yr+40%CC		

Once the above information has been received, I will proceed with further review and provide feedback on the capacity within the foul and surface water network.

Should you have any queries please do not hesitate to contact me.

Thanks
Natalya

Appendix F. MicroDrainage Output for existing surface water network

Atkins Global		Page 2
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...		
Date 29/01/2024 15:32 File CCCG - Model.MDX		
Designed by AVUN1620 Checked by		
XP Solutions		Network 2020.1.3

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	2.000
Hot Start Level (mm)	0	Inlet Coeffiecient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	0	Number of Storage Structures	0	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 533635 189276 TQ 33635 89276
Data Type	Point
Cv (Summer)	0.750
Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0	DVD Status	OFF
Analysis Timestep	Fine	Inertia Status	OFF
DTS Status	ON		

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years)	1, 30, 100
Climate Change (%)	0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S3	15 Winter	2	+0%	30/15 Summer				13.605
S2.000	S1	15 Winter	2	+0%	30/15 Summer	100/15 Summer			13.587
S1.001	S3	15 Winter	2	+0%	2/15 Summer	100/15 Winter			13.561
S1.002	S5	15 Winter	2	+0%	2/15 Summer				13.548

Surcharged Flooded					Half Drain	Pipe		
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Overflow Cap. (l/s)	Time (mins)	Flow (l/s)	Status	Level Exceeded
S1.000	S3	-0.170	0.000	0.13		5.8	OK	
S2.000	S1	-0.093	0.000	0.30		4.0	OK	4

©1982-2020 Innovyze

Atkins Global								Page 3	
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...									
Date 29/01/2024 15:32								Designed by AVUN1620	
File CCCG - Model.MDX								Checked by	
XP Solutions					Network 2020.1.3				
<u>2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for Storm</u>									
		Surcharged Flooded				Half Drain Pipe			
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Level Exceeded
S1.001	S3	0.128	0.000	0.77			8.3	SURCHARGED	1
S1.002	S5	0.054	0.000	1.71			8.2	SURCHARGED	
©1982-2020 Innovyze									

Atkins Global

Page 4

18th Fl, Tower C, Cyber Green...
DLF Cyber City, DLF Phase - III
Gurgaon, Haryanan - 122 002, ...

Date 29/01/2024 15:32
File CCCG - Model.MDX

Designed by AVUN1620
Checked by

XP Solutions

Network 2020.1.3

Micro
Drainage

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000
Hot Start (mins) 0
Hot Start Level (mm) 0
Manhole Headloss Coeff (Global) 0.500
Foul Sewage per hectare (l/s) 0.000

Additional Flow - % of Total Flow 0.000
MADD Factor * 10m³/ha Storage 2.000
Inlet Coeffiecient 0.800
Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0
Number of Online Controls 0

Number of Offline Controls 0
Number of Storage Structures 0

Number of Time/Area Diagrams 0
Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
FEH Rainfall Version 2013
Site Location GB 533635 189276 TQ 33635 89276
Data Type Point
Cv (Summer) 0.750
Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep
DTS Status ON

DVD Status OFF
Fine Inertia Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S3 15	Winter	30	+0%	30/15 Summer				13.936
S2.000	S1 15	Winter	30	+0%	30/15 Summer	100/15 Summer			13.942
S1.001	S3 15	Winter	30	+0%	2/15 Summer	100/15 Winter			13.912
S1.002	S5 15	Winter	30	+0%	2/15 Summer				13.834

Surcharged Flooded

Half Drain Pipe

US/MH Name

Depth (m)

Volume (m³)

Flow / Cap.

Overflow (l/s)

Time (mins)

Pipe Flow (l/s)

Status

Level Exceeded

PN

US/MH Name

Depth (m)

Volume (m³)

Flow / Cap.

Overflow (l/s)

Time (mins)

Pipe Flow (l/s)

Status

Level Exceeded

S1.000

S3

0.161

0.000

0.25

11.1

SURCHARGED

S2.000

S1

0.262

0.000

0.54

7.1

SURCHARGED

4

©1982-2020 Innovyze

Atkins Global								Page 5	
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...									
Date 29/01/2024 15:32				Designed by AVUN1620					
File CCCG - Model.MDX				Checked by					
XP Solutions						Network 2020.1.3			
<u>30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)</u> <u>for Storm</u>									
		Surcharged	Flooded			Half Drain	Pipe		
PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Time (mins)	Flow (l/s)	Status	Level Exceeded
S1.001	S3	0.479	0.000	1.59			17.3	FLOOD RISK	1
S1.002	S5	0.340	0.000	3.55			17.1	SURCHARGED	
©1982-2020 Innovyze									

Atkins Global

Page 6

18th Fl, Tower C, Cyber Green...
DLF Cyber City, DLF Phase - III
Gurgaon, Haryanan - 122 002, ...

Date 29/01/2024 15:32
File CCCG - Model.MDX

Designed by AVUN1620
Checked by

Micro Drainage

XP Solutions

Network 2020.1.3

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for Storm

Simulation Criteria

Areal Reduction Factor 1.000
Hot Start (mins) 0
Hot Start Level (mm) 0

Additional Flow - % of Total Flow 0.000
MADD Factor * 10m³/ha Storage 2.000
Inlet Coefficient 0.800

Manhole Headloss Coeff (Global) 0.500
Foul Sewage per hectare (l/s) 0.000

Flow per Person per Day (l/per/day) 0.000

Number of Input Hydrographs 0
Number of Online Controls 0

Number of Offline Controls 0
Number of Storage Structures 0

Number of Time/Area Diagrams 0
Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model FEH
FEH Rainfall Version 2013
Site Location GB 533635 189276 TQ 33635 89276
Data Type Point
Cv (Summer) 0.750
Cv (Winter) 0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep Fine Inertia
DTS Status ON

DVD Status OFF
Status OFF

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
Return Period(s) (years) 2, 30, 100
Climate Change (%) 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surcharge	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
S1.000	S3 15	Winter	100	+40%	30/15 Summer				14.272
S2.000	S1 15	Winter	100	+40%	30/15 Summer	100/15 Summer			14.281
S1.001	S3 15	Winter	100	+40%	2/15 Summer	100/15 Winter			14.202
S1.002	S5 15	Winter	100	+40%	2/15 Summer				14.084

PN	US/MH Name	Depth (m)	Volume (m³)	Flow / Cap.	Overflow (l/s)	Half Drain Time (mins)	Pipe Flow (l/s)	Status	Level Exceeded
S1.000	S3	0.497	0.000	0.61			26.4	FLOOD RISK	
S2.000	S1	0.601	0.732	0.93			12.4	FLOOD	4

©1982-2020 Innovyze

Appendix G. MicroDrainage Output for Proposed surface water network

Atkins Global		Page 1
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...		
Date 25/01/2024 19:49 File CCCG_Model_21s.MDX		
Designed by AVUN1620 Checked by		
XP Solutions		Network 2020.1.3

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for Storm

Pipe Sizes STANDARD Manhole Sizes STANDARD

FEH Rainfall Model

Return Period (years)	100
FEH Rainfall Version	2013
Site Location	GB 533635 189276 TQ 33635 89276
Data Type	Point
Maximum Rainfall (mm/hr)	250
Maximum Time of Concentration (mins)	30
Foul Sewage (l/s/ha)	0.000
Volumetric Runoff Coeff.	0.750
PIMP (%)	100
Add Flow / Climate Change (%)	0
Minimum Backdrop Height (m)	0.200
Maximum Backdrop Height (m)	1.500
Min Design Depth for Optimisation (m)	0.900
Min Vel for Auto Design only (m/s)	1.00
Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Network Design Table for Storm

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	HYD SECT	DIA (mm)	Section Type	Auto Design
S1.000	36.298	0.267	135.9	0.070	5.00	0.0	0.600	o	225	Pipe/Conduit	
S1.001	3.755	0.038	100.0	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	
S2.000	1.980	0.034	57.5	0.000	5.00	0.0	0.600	o	150	Pipe/Conduit	
S2.001	3.042	0.015	208.2	0.000	0.00	0.0	0.600	o	225	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL (m)	Σ I.Area (ha)	Σ Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
S1.000	198.78	5.54	13.100	0.070	0.0	0.0	0.0	1.12	44.5	37.8
S1.001	198.12	5.59	12.833	0.070	0.0	0.0	0.0	1.31	52.0	37.8
S2.000	206.33	5.02	13.640	0.000	0.0	0.0	0.0	1.33	23.5	0.0
S2.001	205.45	5.08	12.430	0.000	0.0	0.0	0.0	0.90	35.9	0.0

©1982-2020 Innovyze

Atkins Global		Page 4
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...		
Date 25/01/2024 19:49 File CCCG_Model_21s.MDX	Designed by AVUN1620 Checked by	
XP Solutions	Network 2020.1.3	

PIPELINE SCHEDULES for Storm

Upstream Manhole

PN	Hyd Sect	Diam (mm)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	o	225	S1	14.300	13.100	0.975	Open Manhole	600
S1.001	o	225	S2	14.500	12.833	1.442	Open Manhole	600
S2.000	o	150	S3	14.230	13.640	0.440	Junction	
S2.001	o	225	SAT	14.230	12.430	1.575	Open Manhole	1200
S1.002	o	150	SOutfall	14.230	12.415	1.665	Open Manhole	1200

Downstream Manhole

PN	Length (m)	Slope (1:X)	MH Name	C.Level (m)	I.Level (m)	D.Depth (m)	MH Connection	MH DIAM., L*W (mm)
S1.000	36.298	135.9	S2	14.500	12.833	1.442	Open Manhole	600
S1.001	3.755	100.0	SOutfall	14.230	12.795	1.210	Open Manhole	1200
S2.000	1.980	57.5	SAT	14.230	13.606	0.474	Open Manhole	1200
S2.001	3.042	208.2	SOutfall	14.230	12.415	1.590	Open Manhole	1200
S1.002	4.360	90.0	S	14.230	12.367	1.713	Open Manhole	660 x 660

Atkins Global		Page 5
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...		
Date 25/01/2024 19:49	Designed by AVUN1620	
File CCCG_Model_21s.MDX	Checked by	
XP Solutions		Network 2020.1.3

Area Summary for Storm

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	User	-	100	0.043	0.043	0.043
	User	-	100	0.018	0.018	0.061
	User	-	100	0.009	0.009	0.070
1.001	-	-	100	0.000	0.000	0.000
2.000	-	-	100	0.000	0.000	0.000
2.001	-	-	100	0.000	0.000	0.000
1.002	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.070	0.070	0.070

Atkins Global		Page 6																																																																																													
18th Fl, Tower C, Cyber Green... DLF Cyber City, DLF Phase - III Gurgaon, Haryanan - 122 002, ...																																																																																															
Date 25/01/2024 19:49	Designed by AVUN1620																																																																																														
File CCCG_Model_21s.MDX	Checked by																																																																																														
XP Solutions	Network 2020.1.3																																																																																														
Online Controls for Storm Hydro-Brake® Optimum Manhole: SOutfall, DS/PN: S1.002, Volume (m³): 2.2 Unit Reference MD-SHE-0064-2000-1200-2000 Design Head (m)1.200 Design Flow (l/s)2.0 Flush-Flo™Calculated ObjectiveMinimise upstream storage ApplicationSurface Sump AvailableYes Diameter (mm)64 Invert Level (m)12.415 Minimum Outlet Pipe Diameter (mm)100 Suggested Manhole Diameter (mm)1200 <table><tr><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td><td>Control Points</td><td>Head (m)</td><td>Flow (l/s)</td></tr><tr><td>Design Point (Calculated)</td><td>1.200</td><td>2.0</td><td>Kick-Flo®</td><td>0.573</td><td>1.4</td></tr><tr><td>Flush-Flo™</td><td>0.282</td><td>1.8</td><td>Mean Flow over Head Range</td><td>-</td><td>1.6</td></tr></table> The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated <table><tr><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td><td>Depth (m)</td><td>Flow (l/s)</td></tr><tr><td>0.100</td><td>1.5</td><td>1.200</td><td>2.0</td><td>3.000</td><td>3.0</td><td>7.000</td><td>4.5</td></tr><tr><td>0.200</td><td>1.7</td><td>1.400</td><td>2.1</td><td>3.500</td><td>3.3</td><td>7.500</td><td>4.7</td></tr><tr><td>0.300</td><td>1.8</td><td>1.600</td><td>2.3</td><td>4.000</td><td>3.5</td><td>8.000</td><td>4.8</td></tr><tr><td>0.400</td><td>1.7</td><td>1.800</td><td>2.4</td><td>4.500</td><td>3.7</td><td>8.500</td><td>5.0</td></tr><tr><td>0.500</td><td>1.6</td><td>2.000</td><td>2.5</td><td>5.000</td><td>3.9</td><td>9.000</td><td>5.1</td></tr><tr><td>0.600</td><td>1.5</td><td>2.200</td><td>2.6</td><td>5.500</td><td>4.0</td><td>9.500</td><td>5.2</td></tr><tr><td>0.800</td><td>1.7</td><td>2.400</td><td>2.7</td><td>6.000</td><td>4.2</td><td></td><td></td></tr><tr><td>1.000</td><td>1.8</td><td>2.600</td><td>2.8</td><td>6.500</td><td>4.4</td><td></td><td></td></tr></table> <tr><td colspan="3">©1982-2020 Innovyze</td></tr>			Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)	Design Point (Calculated)	1.200	2.0	Kick-Flo®	0.573	1.4	Flush-Flo™	0.282	1.8	Mean Flow over Head Range	-	1.6	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	0.100	1.5	1.200	2.0	3.000	3.0	7.000	4.5	0.200	1.7	1.400	2.1	3.500	3.3	7.500	4.7	0.300	1.8	1.600	2.3	4.000	3.5	8.000	4.8	0.400	1.7	1.800	2.4	4.500	3.7	8.500	5.0	0.500	1.6	2.000	2.5	5.000	3.9	9.000	5.1	0.600	1.5	2.200	2.6	5.500	4.0	9.500	5.2	0.800	1.7	2.400	2.7	6.000	4.2			1.000	1.8	2.600	2.8	6.500	4.4			©1982-2020 Innovyze		
Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)																																																																																										
Design Point (Calculated)	1.200	2.0	Kick-Flo®	0.573	1.4																																																																																										
Flush-Flo™	0.282	1.8	Mean Flow over Head Range	-	1.6																																																																																										
Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)																																																																																								
0.100	1.5	1.200	2.0	3.000	3.0	7.000	4.5																																																																																								
0.200	1.7	1.400	2.1	3.500	3.3	7.500	4.7																																																																																								
0.300	1.8	1.600	2.3	4.000	3.5	8.000	4.8																																																																																								
0.400	1.7	1.800	2.4	4.500	3.7	8.500	5.0																																																																																								
0.500	1.6	2.000	2.5	5.000	3.9	9.000	5.1																																																																																								
0.600	1.5	2.200	2.6	5.500	4.0	9.500	5.2																																																																																								
0.800	1.7	2.400	2.7	6.000	4.2																																																																																										
1.000	1.8	2.600	2.8	6.500	4.4																																																																																										
©1982-2020 Innovyze																																																																																															



Micro
Drainage

Simulation Criteria

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Rainfall Model	FEH
FEH Rainfall Version	2013
Site Location	GB 533635 189276 TQ 33635 89276
Data Type	Point
Cv (Summer)	0.750
Cv (Winter)	0.840

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080
n Period(s) (years)	2, 5, 30, 100
Climate Change (%)	0, 0, 0, 40

©1982-2020 Innovyze

AtkinsRéalis



Ade Salako
AtkinsRéalis
Nova North
11 Bressenden Place
Victoria
London
SW1E 5BY

Tel: +44 1454 662000

© AtkinsRéalis except where stated otherwise