

Drainage Strategy

Land to the rear of 10 Bidwell Gardens
London, N11 2AX

for

Ellen Wibye
A20193

February 2024

Drainage Strategy
Land to the rear of 10 Bidwell Gardens
for
Ellen Wibye

Revision	Date of issue	Comments	Prepared By	Checked By
1.0	01/09/2020	Initial Issue	AJ	DB
2.0	15/02/2024	Site Layout updated	AM	DB
3.0	19/02/2024	Green Roof removed	AM	DB

Should you have any queries relating to this document please contact:

David Brooke
PPCP Limited T/A Patrick Parsons
Satelliet House
2 Nexus Park
Lysons Avenue
Ash Vale
GU12 5QE

T: +44 (0) 1276 700 400

E: david.brooke@patrickparsons.co.uk

Executive Summary

Description	
Patrick Parsons has been instructed by Ellen Wibye , to produce a Drainage Strategy to support the Planning Application for the site at Land to the rear of 10 Bidwell Gardens , London, N11 2AX.	
Site Parameters	
Total Area:	310m ² (0.031 Ha)
Greenfield:	NO
Brownfield:	NO
Mixed Green and Brownfield:	YES
Existing Runoff Location:	Ground
Ground Conditions:	Clay
Method of Study:	Desk Investigation
Ground Infiltration Potential:	Low
Flood Risk Assessment	
Coastal:	Zone 1
Fluvial:	Zone 1
Pluvial:	Low
Groundwater:	Low
Other sources:	Low
Drainage Strategy / SuDS	
Infiltration Viable:	NO
Discharge Point (SW):	Sewer
Flow Control:	1.2 l/s
Storage Provided:	1 in 100 Year + 40% Climate Change
Discharge Point (FW):	Sewer
SuDS Elements:	Porous Surfacing, Hydro-Brake, Water Butt, Orifice
Water Quality Measures:	Catchpits, Geotextiles, and rainwater planter
Exceedance flows:	Managed within site
Conclusions	
The proposed development will have the opportunity to introduce sustainable drainage and the site is not at risk any form of flooding.	

Contents

1.0	Introduction.....	1
2.0	Location of Site	1
3.0	Site Description.....	2
4.0	Site Run-Off	4
5.0	Proposed Development.....	5
6.0	Sustainable Drainage Assessment	6
7.0	Drainage Proposal	9
8.0	Water Quality	14
9.0	Flooding Information.....	18
10.0	Flood Risk.....	19
11.0	Maintenance.....	23
12.0	Summary and Conclusions	26

Appendices

Appendix A	Location Plan
Appendix B	Topographical Survey
Appendix C	Thames Water Sewer Records
Appendix D	Magic Map Geology Information
Appendix E	Greenfield Run-Off
Appendix F	Site Plan
Appendix G	Schematic Drainage Layout
Appendix H	Hydraulic Calculations
Appendix J	Environment Agency Flood Map

1.0 Introduction

- 1.1 Ellen Wibye is planning a proposed development on the site at Land to the rear of 10 Bidwell Gardens , London, N11 2AX.
- 1.2 Patrick Parsons has been instructed by Ellen Wibye , to produce a Drainage Strategy to support the Planning Application.
- 1.3 This report aims to demonstrate that a reduction in surface water run-off from the site can be achieved.
- 1.4 The general limitations of this assessment are that:
 - Several data sources have been used in compiling this report. Whilst Patrick Parsons believe them to be trustworthy; it is unable to guarantee the accuracy of the information that has been provided by others.
 - This report is based on information available at the time of preparation. There is potential for further information to become available, which may create a need to modify conclusions drawn in this report.

2.0 Location of Site

- 2.1 The site is located at Bidwell Gardens in London. A location plan is enclosed in **Appendix A**.
- 2.2 The Local Authority is the London Borough of Haringey.

3.0 Site Description

3.1 Existing Site

- 3.1.1 The site is currently the rear gardens to No. 10 Bidwell Gardens. A topographical survey has been commissioned for the site and can be found in **Appendix B**.
- 3.1.2 The site falls from north to south with a split level required for the development, with levels ranging between 62.0m AOD and 59.0m AOD.

3.2 Existing Drainage System

- 3.2.1 Sewer records were obtained from Thames Water and can be found at **Appendix C**. There are public foul water and surface water sewers located within Bidwell Gardens and Wroxham Gardens.
- 3.2.2 There is a public 229mm diameter foul water sewer within Bidwell Gardens. The closest public manhole is No. 5001 with cover level 54.46m AOD and an invert level of 50.43m AOD.
- 3.2.3 There is a public 229mm diameter foul water sewer within Bidwell Gardens. The closest public manhole is No. 5001 with cover level 54.45m AOD and an invert level of 50.90m AOD.
- 3.2.4 There are also public surface and foul water sewers located within the rear garden of No. 10 Bidwell gardens, which may be the most appropriate point of connection.

3.3 Existing Geology

- 3.3.1 The geology of the site has been ascertained by reference to the 1:50,000 British Geological Survey website. The data provided on the website indicates the bedrock and superficial drift geology for the site.
- 3.3.2 The strata of the site (bedrock geology) comprises London Clay formation, described as follows:

“London Clay Formation - Clay, Silt and Sand. Sedimentary Bedrock formed approximately 48 to 56 million years ago in the Palaeogene Period. Local environment previously dominated by deep seas. These sedimentary rocks are marine in origin. They are detrital and comprise coarse- to fine-grained slurries of debris from the continental shelf flowing into a deep-sea environment, forming distinctively graded beds.”

3.4 Geological Assessment

- 3.4.1 Boreholes in the local area indicate clay with no head deposits.
- 3.4.2 It has not been possible to undertake site investigations at the time of writing this report to determine the underlying geology. It is recommended that a full geotechnical investigation be completed prior to any detailed design of the scheme.

- 3.4.3 Based on the desk study information on the geology of the site, infiltration is not likely to be suitable for the development. The requirement for a positive surface water discharge has been considered in this report.

3.5 Hydrogeology Setting

- 3.5.1 The Environment Agency (EA) mapping service, as provided by Magic Map, indicates the aquifer designation for the bedrock and superficial drift geology and the groundwater vulnerability in the area. The mapping, as included at **Appendix D**, provide the following information for the site:

Geology Map	Site Description
Aquifer Designation (Bedrock)	Unproductive
Aquifer Designation (Superficial Drift)	Unproductive
Groundwater Vulnerability	Unproductive
Groundwater Source Protection Zone	None

3.6 Hydrology

- 3.6.1 The nearest strategic watercourse is the New River, located 1.2km to the south east of the site.

4.0 Site Run-Off

4.1 Existing Surface Water Runoff

- 4.1.1 The site has been previously developed, but an analysis of the Greenfield run-off rate is appropriate and will be made for the developable site area of 0.031 hectares.
- 4.1.2 The Greenfield run-off rates have been calculated for the existing site. The existing site run-off rates have been calculated based on the Interim Code of Practice for Sustainable Drainage Systems, Chapter 6 using the Micro Drainage design software. The output from the software analysis can be found at **Appendix E**.
- 4.1.3 The Qbar (rural) value for the site is 0.2 litres per second. A technical assessment has been made for the site of the most appropriate flow rate suiting the site constraints as follows:

Flow Rate (Standard)	Flow Rate (l/s)	Method of control	Constraints
Qbar Rural	0.2	-	Too low for a flow control
3 x Qbar	0.6	-	Too low for a flow control
-	2.0	Hydro-Brake	1. Low flow rate indicates high level of silt removal required. 2. Hydrobrake chamber must be constructible.
Infiltration	0	None	Site must be suitable for infiltration

4.2 Greenfield Run-Off Assessment

- 4.2.1 An assessment of the most appropriate flow restriction on site can be made with an engineering judgement made on the following parameters:
- Proposed depth of surface water system. Shallow systems will not be able to construct certain flow controls.
 - Risk of blockages, open drainage systems and conventional piped systems will have a significantly higher chance of blockage.
 - Potential for soakage or a hybrid solution with some infiltration and some positive discharge.
 - The existing use of the site (green/brown field) and the most appropriate reduction in surface water flows from the proposed development.
 - Potential development costs and the viability of achieving very low flow rates on sites.
 - Manufacturer limits, with Hydro-International stating they can achieve between 0.7 and 550 l/s on their product range.
- 4.2.2 Infiltration has not been selected, based on the geotechnical information provided within this report.
- 4.2.3 A flow control of 2.0 litres per second is recommended, which is the minimum recommended to prevent blockages. However, the proposed system results in flows less than this (1.2 l/s).

5.0 Proposed Development

5.1.1 The proposal is for 1 No. residential unit. A site layout can be found at **Appendix F**.

5.2 Infiltration Potential

5.2.1 The geotechnical information provided in this report indicates that standard infiltration methods will not be suitable on site, subject to BRE testing. In addition, there is limited space to site any infiltration devices.

5.2.2 The table below summarises the potential for infiltration.

Low infiltration potential: There is a low potential for infiltration SuDS in parts of the Site. Comments: It is likely that the underlying geology at the Site, or in areas of the site, is relatively impermeable which would limit the effectiveness of a proposed infiltration SuDS scheme. Recommendations: Infiltration SuDS should be focused in more suitable parts of the site. If a site investigation confirms that infiltration SuDS are not possible at the site, then attenuation SuDS with a controlled discharge into a nearby surface water feature or existing surface water drainage is recommended.	YES
Moderate infiltration potential: There is a moderate potential for infiltration SuDS in parts of the Site. Comments: It is likely that the permeability of the underlying material at the site would be suitable for infiltration drainage. However, there may be constraints on the use of infiltration SuDS because of any of the following: a high water-table, the limited thickness of the receiving formation, the potential for a significant range in permeability in the underlying geology and confirmation of the infiltration capacity is recommended. Recommendations: A site investigation is recommended to investigate groundwater levels and formation thickness and to confirm that infiltration rates at the site are sufficient to accommodate an infiltration SuDS feature. If a site investigation confirms that infiltration SuDS are possible at the Site then assorted options can be considered for infiltration SuDS and these include infiltration trenches, soakaways, swales, permeable pavements and infiltration basins without outlets.	NO
High infiltration potential: There is a high potential for infiltration SuDS in parts of the Site. Comments: It is likely that the underlying geology at the Site is highly permeable and an infiltration SuDS scheme should be possible at the Site. Groundwater levels are expected to be sufficiently deep at the site. Recommendations: A site investigation is recommended to confirm the high infiltration capacity and the depth of the winter water table. Assorted options can be considered for infiltration SuDS and these include infiltration trenches, soakaways, swales, permeable pavements and infiltration basins without outlets.	NO

6.0 Sustainable Drainage Assessment

6.1 SuDS Hierarchy

- 6.1.1 Options for the destination for the run-off generated on site have been assessed in line with the prioritisation set out in the Building Regulations Part H document and DEFRA's Draft National Standards for SuDS as follows:

Discharge to Ground	Not viable based on desk study
Discharge to Watercourse	No watercourses in area
Discharge to Surface Water Sewer	Selected Option
Discharge to Other Sewer	N/A

- 6.1.2 The indicative potential for different SuDS devices has been assessed and can be seen in the table below:

SuDS Feature	Environmental benefits	Water quality improvement	Suitability for low permeability soils ($k < 10^{-6}$)	Ground-water recharge	Suitable for small / confined sites?	Site specific restrictions	Appropriate for subject site?
Wetlands	✓	✓	✓	X	X	Site Constraints	No
Retention ponds	✓	✓	✓	X	X	Site Constraints	No
Detention basins	✓	✓	✓	X	X	Site Constraints	No
Infiltration basins	✓	✓	X	✓	X	Site Constraints	No
Soakaways	X	✓	X	✓	✓	Poor Ground	No
Underground storage	X	X	✓	X	✓	None	Yes
Swales	✓	✓	✓	✓	X	Site Constraints	No
Filter strips	✓	✓	✓	✓	X	Site Constraints	No
Rainwater harvesting	X	✓	✓	✓	✓	None	Yes
Permeable paving	X	✓	✓	✓	✓	None	Tanked
Green roofs	✓	✓	✓	X	✓	Site Constraints	No
Rain Garden (external)	✓	✓	✓	X	X	None	Yes
Rain Garden (planter)	✓	✓	✓	X	X	None	Yes

6.2 Detailed SuDS Assessment

6.2.1 To maximize the potential use of SuDS at the site, a review has been undertaken in accordance with the SuDS Hierarchy (refer to SuDS: A Practical Guide prepared by the Environment Agency).

6.2.2 The following table indicates the potential setting for SuDS elements:

	Description	Setting	Required Area
Green Roof	A planted soil layer is constructed on the roof of a building to create a living surface. Water is stored in the soil layer and absorbed by vegetation.	Building	Building integrated
Rainwater Harvesting	Rainwater is collected from the roof of a building or from other paved surfaces and stored in an overground or underground tank for treatment and reuse locally. Water could be used for toilet flushing and irrigation.	Building	Water storage (underground or above ground)
Soakaway	A soakaway is designed to allow water to quickly soak into permeable layers of soil. Constructed like a dry well, an underground pit is dug filled with gravel or rubble. Water can be piped to a soakaway where it will be stored and allowed to gradually seep into the ground.	Open Space	Dependant on Run-off volumes and soils
Filter Strip	Filter strips are grassed or planted areas that runoff can run across to promote infiltration and cleansing.	Open Space	Maximum length 5 metres
Permeable Paving	Paving which allows water to soak through. Can be in the form of paving blocks with gaps between solid blocks or porous paving where water filters through the block itself. Water can be stored in the sub-base beneath or allowed to infiltrate into ground below.	Street / Open Space	Can typically drain double its area
Bioretention Area	A vegetated area with gravel and sand layers below designed to channel, filter and cleanse water vertically. Water can infiltrate into the ground below or drain to a perforated pipe and be conveyed elsewhere. Bioretention systems can be integrated with tree-pits or gardens.	Street / Open Space	Typically, surface area is 5-10% of drained area with storage below.
Swale	Swales are vegetated shallow depressions designed to convey and filter water. These can be 'wet' where water gathers above the surface, or 'dry' where water gathers in a gravel layer beneath. Can be lined or unlined to allow infiltration.	Street / Open Space	Account for width to allow safe maintenance typically 2-3 metres wide.
Hardscape Storage	Hardscape water features can be used to store run-off above ground within a constructed container. Storage features can be integrated into public realm areas with a more urban character.	Open Space	Could be above or below ground and sized to storage need.
Pond / Basin	Ponds can be used to store and treat water. 'Wet' ponds have a constant body of water and run-off is additional, while 'dry' ponds are empty during periods without rainfall. Ponds can be designed to allow infiltration into the ground or to store water for a period of time before discharge.	Open Space	Dependant on runoff volumes and soils.
Wetland	Wetlands are shallow vegetated water bodies with a varying water level. Specially selected plant species are used to filter water. Water flows horizontally and is gradually treated before being discharged. Wetlands can be integrated with a natural or hardscape environment.	Open Space	Typically, 5-15% of drainage area to provide good treatment.
Underground Storage	Water can be stored in tanks, gravel or plastic crates beneath the ground to provide attenuation.	Open Space	Dependant on runoff volumes and soils.

6.2.3 This review highlights the components referenced in the SuDS Hierarchy and provides recommendations on whether the components could be incorporated into the development.

Component	Recommendation / Opinion	
Green (living) roofs or Blue/Green roof systems	There is no scope for a green roof on the development due to the format of the roof.	↓
Basins and Ponds	There is no potential for basins and ponds on the site.	↓
Filter Strips and Swales	There is no scope for use of surface mounted SuDS on the scheme to convey water	↓
Infiltration Devices	Infiltration devices will not be viable on site.	↓
Permeable Surfaces and Filter Drains	Porous surfaces are viable to manage surface water run-off.	↓
Tanked Systems	It is unlikely that these will be required.	↓

6.2.4 The proposed drainage system incorporates sustainable drainage features in accordance with the SuDS hierarchy, current legislation and best practice as much as practicable on site.

6.2.5 There may be an opportunity for further small-scale bespoke SuDS elements (such as planters and filtration beds) to be included as part of the landscaping proposals. These should be considered fully before construction commences.

7.0 Drainage Proposal

7.1 Surface Water Drainage

- 7.1.1 Surface water drainage at the site will follow the Sustainable Drainage Systems (SuDS) management train. The surface water from the site will discharge into the existing public sewer at a restricted rate. A Drainage Plan can be found at **Appendix G**.
- 7.1.2 New climate change allowances have been in force since February 19th 2016. The new allowances take into consideration the design life of the development, flood zone, development type and geographical location.
- 7.1.3 Based on these parameters, the Central value for rainfall intensity should be used. Based on Table 2 (shown below), this is a range between 20% and 40% for the central and upper end values. Therefore, it is appropriate to use 40% on this development for design.

Table 2 peak rainfall intensity allowance in small and urban catchments (use 1961 to 1990 baseline)

Applies across all of England	Total potential change anticipated for the '2020s' (2015 to 2039)	Total potential change anticipated for the '2050s' (2040 to 2069)	Total potential change anticipated for the '2080s' (2070 to 2115)
Upper end	10%	20%	40%
Central	5%	10%	20%

- 7.1.4 Any water up to a 1 in 100 year storm event including 40% climate change will be attenuated within the curtilage of the site in the proposed drainage system.
- 7.1.5 National SuDS standards, the Design and Construction Guidance 2020 and Sewers for Adoption recommend that the 1 in 30 year storm event is managed below ground with exceedance flows managed above ground.
- 7.1.6 Hydraulic calculations have been undertaken, which can be found at **Appendix H**.

7.2 Adoptable Drainage

- 7.2.1 Sewers for Adoption (7th and 6th Edition) are guidance documents used by the water companies to approve and review drainage designs that are offered to them (or vested) for adoption. This is usually via a S104 or similar agreement.
- 7.2.2 As of 1st April 2020, the Design and Construction Guidance documentation will replace both the previous versions and will be mandatory as part of the Code for Adoption agreements.

7.2.3 Appendix C of the Design and Construction Guidance (DCG) is in effect the replacement for Sewers for Adoption (SfA) 6th and 7th edition.

7.2.4 The table below indicates the type of drainage element that is currently allowed to be offered for adoption under DCG 2020, with the previous allowances shown for reference.

	SfA6 / 7	DCG	LA	PRIVATE
Rainwater Harvesting	X	X	X	✓
Green Roofs	X	X	X	✓
Infiltration Systems	X	✓	✓	✓
Proprietary Treatment Systems	✓	✓	✓	✓
Filter Strips	X	X	✓	✓
Filter Drains	X	✓	✓	✓
Swales	X	✓	✓	✓
Bioretention Systems	X	✓	X	✓
Trees	X	X	✓	✓
Pervious Pavements	X	X	✓	✓
Attenuation Storage Tanks	✓	✓	✓	✓
Detention Basins	X	✓	✓	✓
Ponds and Wetlands	X	✓	✓	✓

7.2.5 The drainage elements on this system that are intended to be offered for adoption have been shown on the drainage plan.

7.3 Designing for Exceedance Events

7.3.1 Current best practice guidance on flood risk requires an evaluation of how rainfall events beyond the design capacity of the proposed drainage system would be managed and what effects they are likely to have on flood risk at the site or surrounding areas.

7.3.2 Should a rainfall event exceeding the 1.0% AEP (1 in 100 year) event plus climate change event occur, the proposed storage and flow paths of surface water should be considered.

7.3.3 The site ground conditions indicate that surplus water will flow from the north to the south, with reasonably good infiltration into the ground.

7.3.4 The surface water SuDS features included for the 1 in 100-year storm will be designed with sufficient resilience to manage and convey exceedance flows away from any properties to minimise risk.

7.3.5 Indicative exceedance pathways have been shown on the drainage layout, with further information to be defined once the detailed levels of the scheme have been developed.

7.4 Designing for System Failure

7.4.1 Current best practice on sustainable drainage design should consider failure of the surface water system and potential blockages from multiple sources.

7.4.2 The potential risks to the surface water system have been indicated below:

Risk	Description	Comments / Recommendations
Blockage	Potential blockage of outfall from surface water system	Regular inspection and maintenance of the drainage system should be undertaken in line with the findings of this report.
Failure	Potential blockage of outfall from flow control failure or build-up of debris	Regular inspection and maintenance of the drainage system should be undertaken in line with the findings of this report.
Surcharge	Potential back-up of system due to surcharging or poorly maintained public surface water infrastructure or watercourse	Regular inspection and maintenance of the drainage system should be undertaken in line with the findings of this report.
Blockage	Potential risk of flooding due to build-up of sediment within system	Catchpit manholes have been provided to remove solids and sediment. Regular inspection and maintenance of the drainage system should be undertaken in line with the findings of this report.
Failure	Potential risk of surface water flows from poor maintenance of surface mounted SuDS features (such as porous paving or swales)	Regular inspection and maintenance of the surface mounted SuDS should be undertaken in line with the findings of this report.
Surcharge	Potential risk of additional surface water flows or overland flows from extreme (exceedance storm) events in adjacent sites causing the surface water system to be overloaded.	Exceedance flow routes have been assessed and shown on the drainage layout.
Failure	Potential risk from failure of third-party specialist equipment such as pump stations or interceptors	Not applicable
Blockage	Potential risk from poor maintenance of gullies	Not applicable
Blockage	Potential reduction in infiltration on site from compaction of soils during the construction phase	Ground consolidation should not have a major impact.
Failure	Poor planting and maintenance of green areas could reduce the hydraulic properties of SuDS devices (and amenity/biodiversity benefits)	Not applicable

7.5 Urban Creep

7.5.1 Urban Creep is the conversion of permeable surfaces to impermeable over time. e.g. impermeable surfacing of front gardens to provide additional parking spaces, extensions to existing buildings, creation of large patio areas. The consideration of urban creep (is best) assessed on a site by site basis but is limited to residential development only.

7.5.2 It is important that the appropriate allowance for urban creep is included in the design of the drainage system over the lifetime of the proposed development. The allowances set out below are applied to the impermeable area within the property curtilage:

Residential development density Dwellings per hectar	Change allowance % of impermeable area
≤ 25	10
30	8
35	6
45	4
≥ 50	2
Flats & apartments	0

7.5.3 Note where the inclusion of the appropriate allowance would increase the total impermeable area to greater than 100%, 100% should be used as the maximum.

7.5.4 The proposed development has scope for expansion. Based on this, 10% allowance for urban creep is required for the development and has been allowed for in the calculations.

7.6 Construction Phase Drainage

7.6.1 It is an offence to cause or knowingly permit the entry of poisonous, noxious or polluting material into the water environment. Prosecution may ensue if the pollution is serious enough to lower the ecological status of the water body in terms set by the Water Framework Directive (2000/60/EC).

7.6.2 The polluter does not have to be prosecuted first for remediation of damage to be required. If water pollution is serious enough to be classed as environmental damage the damage will require to be remediated such that the area is returned to the condition it would have been in if the damage had not occurred.

7.6.3 An offence may also be committed if environmental damage or the threat of environmental damage is not reported by the polluter or if no action is taken by the polluter to prevent further damage. Third parties (e.g. private water supply users, landowners, recreational users and the public) who may be affected by possible damage may also report 'risk' of environmental damage to the enforcing authority; in this instance an offence may be committed if action is not taken to prevent the potential environmental damage occurring.

7.6.4 The principles of Sustainable Drainage Systems (SuDS) shall be applied to all components of design and construction regarding surface water management. Any design or site works that may impact on the site drainage or water quality shall:

- Soakaway where soils allow
- Consider and manage erosion
- Retain any silts on site and prevent silts from discharging into watercourses or drains
- Remove pollutants in surface water
- Keep runoff rates at existing greenfield runoff

- Prevent accidental spillages reaching watercourses.
- 7.6.5 As infiltration is not expected to be viable on site, the temporary drainage for the development will be in the form of land drainage with discharge into the existing sewer, with the appropriate levels of treatment.
- 7.6.6 Pollution will be controlled via the use of catchpit manholes and geotextiles.
- 7.6.7 Any potentially hazardous substances (i.e. from plant / deliveries) will be within a controlled compound with a separate drainage system that will contain a penstock valve / containment kit in the event of a spillage.
- 7.7 Foul Water Drainage**
- 7.7.1 The foul water for the development will discharge into the existing public sewer. Foul water flows are anticipated to be 0.046 litres per second based on 4000 litres per dwelling per day in accordance with Sewers for Adoption 7th Edition and the Design and Construction Guidance 2020.

8.0 Water Quality

8.1 Water Quality Overview

- 8.1.1 A key requirement of any SuDS system is that it protects the receiving water body from the risk of pollution. This can be effectively managed by an appropriate “train” or sequence of SuDS components that are connected in series.
- 8.1.2 The frequent and short duration rainfall events are those that are most loaded with potential contaminants (silts, fines, heavy metals and various organic and inorganic contaminants). Therefore, the first 5-10 mm of rainfall (first flush) should be adequately treated with SuDS.
- 8.1.3 The minimum number of treatment stages will depend on the sensitivity of the receiving water body and the potential hazard associated with the proposed development SuDS Manual (CIRIA, 2015).
- 8.1.4 The proposed development is a combination of very low (roof water) to low hazard (runoff from small car parking areas), as indicated on the table below:

Hazard	Source of Hazard	Present
Very Low	Residential Roof drainage.	YES
Low	Residential amenity uses including low usage car parking spaces and roads, other roof drainage	YES
Medium	Commercial, industrial uses including car parking spaces and roads (excluding low usage road, trunk roads and motorways)	NO
High	Areas used for handling and storage of chemicals and fuels, handling of storage and waste	NO

- 8.1.5 The site does lie within a source protection zone and therefore additional treatment stages are required. However, infiltration is not viable for this scheme.
- 8.1.6 The treatment processes provided by different SuDS components will have varying capabilities for removal of different types of contaminants as per the table below:

Hazard	Requirements for discharge to surface water and groundwater	Present
Very Low	Removal of gross solids and sediments only.	YES
Low	Simple index approach	YES
Medium	Surface water: Simple index approach Ground water: Simple index approach and risk screening	NO
High	Guidance and risk assessment process in HA (2009). Discharge may require environmental permit or licence. Obtain pre-permitting advice from environmental regulator. Risk assessment likely to be required.	NO

8.2 Simple Index Approach

- 8.2.1 The index approach as defined by CIRIA C753 (the SuDS Manual) defines the index approach to water quality in three steps as defined in Box 26.2 below:

BOX 26.2 Steps of the simple index approach

Step 1 – Allocate suitable pollution hazard indices for the proposed land use

Step 2 – Select SuDS with a total pollution mitigation index that equals or exceeds the pollution hazard index

Step 3 – Where the discharge is to protected¹ surface waters or groundwater, consider the need for a more precautionary approach

Note:

¹ Designated as those protected for the supply of drinking water (Table 4.3).

8.3 Step 1- Allocate Potential Hazards

- 8.3.1 To deliver adequate treatment, the selected SuDS components should have a total pollution mitigation index (for each contaminant type) that equals or exceeds the pollution hazard index (for each contaminant type):

Total SuDS mitigation index $\geq$ pollution hazard index

(for each contaminant type) (for each contaminant type)

- 8.3.2 Where the only destination of the runoff is to a surface water – that is there is no infiltration from the SuDS to groundwater – the surface water indices should be used.
- 8.3.3 In England and Wales, where the principal destination of the runoff is to a surface water, but small amounts of infiltration may occur from unlined components (Interception), then the groundwater indices should be used for the discharge to groundwater, and the surface water indices should be used for the main surface water discharge (as suggested in Table 26.3).
- 8.3.4 Where the principal destination of the runoff is to groundwater, but discharges to surface waters may occur once the infiltration capacity is exceeded, the groundwater indices should be used, as suggested in Table 26.4. The risk to surface waters will be low, as dilution will be high for large events, so treatment is not required.
- 8.3.5 The pollution indices for this site have been selected using the guidance in CIRIA C753 and are as per Table 26.2 below:



TABLE 26.2 Pollution hazard indices for different land use classifications

Land use	Pollution hazard level	Total suspended solids (TSS)	Metals	Hydrocarbons
Residential roofs	Very low	0.2	0.2	0.05
Other roofs (typically commercial/ industrial roofs)	Low	0.3	0.2 (up to 0.8 where there is potential for metals to leach from the roof)	0.05
Individual property driveways, residential car parks, low traffic roads (eg cul de sacs, homezones and general access roads) and non-residential car parking with infrequent change (eg schools, offices) ie < 300 traffic movements/day	Low	0.5	0.4	0.4
Commercial yard and delivery areas, non-residential car parking with frequent change (eg hospitals, retail), all roads except low traffic roads and trunk roads/motorways ¹	Medium	0.7	0.6	0.7
Sites with heavy pollution (eg haulage yards, lorry parks, highly frequented lorry approaches to industrial estates, waste sites), sites where chemicals and fuels (other than domestic fuel oil) are to be delivered, handled, stored, used or manufactured; industrial sites; trunk roads and motorways ¹	High	0.8 ²	0.8 ²	0.9 ²

Notes

- 1 Motorways and trunk roads should follow the guidance and risk assessment process set out in Highways Agency (2009).
- 2 These should only be used if considered appropriate as part of a detailed risk assessment – required for all these land use types (Table 4.3). When dealing with high hazard sites, the environmental regulator should first be consulted for pre-permitting advice. This will help determine the most appropriate approach to the development of a design solution.

Where a site land use falls outside the defined categories, the indices should be adapted (and agreed with the drainage approving body) or else the more detailed risk assessment method should be adopted.

Where nutrient or bacteria and pathogen removal is important for a particular receiving water, equivalent indices should be developed for these pollutants (if acceptable to the drainage approving body) or the risk assessment method adopted.

8.3.6 The identified hazard levels are as follows:

- Total Suspended Solids (TSS) 0.70
- Metals 0.60
- Hydrocarbons 0.45

8.3.7 Treatment has been provided in the form of catchpit manholes to remove sediment and contaminated particles and geotextiles within the porous paving as a filter medium.

8.4 Treatment with Discharge to Surface Water

8.5 As the site is discharging to a watercourse or sewer, Table 26.3 of the CIRIA C753 manual is used to evaluate the water quality mitigation measures offered by the proposed drainage system.

TABLE 26.3 Indicative SuDS mitigation indices for discharges to surface waters				
Type of SuDS component	Mitigation indices ¹			
	TSS	Metals	Hydrocarbons	
Filter strip	0.4	0.4	0.5	
Filter drain	0.4 ²	0.4	0.4	
Swale	0.5	0.6	0.6	
Bioretention system	0.8	0.8	0.8	
Permeable pavement	0.7	0.6	0.7	
Detention basin	0.5	0.5	0.6	
Pond ⁴	0.7 ³	0.7	0.5	
Wetland	0.8 ³	0.8	0.8	
Proprietary treatment systems ^{5,6}	These must demonstrate that they can address each of the contaminant types to acceptable levels for frequent events up to approximately the 1 in 1 year return period event, for inflow concentrations relevant to the contributing drainage area.			

Notes

- 1 SuDS components only deliver these indices if they follow design guidance with respect to hydraulics and treatment set out in the relevant technical component chapters.
- 2 Filter drains can remove coarse sediments, but their use for this purpose will have significant implications with respect to maintenance requirements, and this should be taken into account in the design and Maintenance Plan.
- 3 Ponds and wetlands can remove coarse sediments, but their use for this purpose will have significant implications with respect to the maintenance requirements and amenity value of the system. Sediment should normally be removed upstream, unless they are specifically designed to retain sediment in a separate part of the component, where it cannot easily migrate to the main body of water.
- 4 Where a wetland is not specifically designed to provide significantly enhanced treatment, it should be considered as having the same mitigation indices as a pond.
- 5 See **Chapter 14** for approaches to demonstrate product performance. A British Water/Environment Agency assessment code of practice is currently under development that will allow manufacturers to complete an agreed test protocol for systems intended to treat contaminated surface water runoff. Full details can be found at: <http://tinyurl.com/qf7yuj7>
- 6 SEPA only considers proprietary treatment systems as appropriate in exceptional circumstances where other types of SuDS component are not practicable. Proprietary treatment systems may also be considered appropriate for existing sites that are causing pollution where there is a requirement to retrofit treatment. SEPA (2014) also provides a flowchart with a summary of checks on suitability of a proprietary system.

8.5.1 The identified hazard remediation levels are as follows:

	Hazard	Treatment	Result
– Total Suspended Solids (TSS)	0.70	0.7	0
– Metals	0.60	0.6	0
– Hydrocarbons	0.45	0.7	0

9.0 Flooding Information

- 9.1.1 As set out in the National Planning Policy Framework (NPPF), inappropriate development in areas at risk of flooding should be avoided by directing development away from areas at highest risk, but where development is necessary, making it safe without increasing flood risk elsewhere. For these purposes:
- “areas at risk of flooding” means land within Flood Zones 2 and 3; or land within Flood Zone 1 which has critical drainage problems, and which has been notified to the local planning authority by the Environment Agency;
 - “flood risk” means risk from all sources of flooding - including from rivers and the sea, directly from rainfall on the ground surface and rising groundwater, overwhelmed sewers and drainage systems, and from reservoirs, canals and lakes and other artificial sources.
- 9.1.2 Flooding information for Planning from the Environment Agency (EA) has shown that the site lies within Flood Zone 1, as found in the map at **Appendix J**.
- 9.1.3 As the site is within Flood Zone 1, no further data was requested from the Environment Agency.
- 9.1.4 As part of the data capture, data and mapping from the Haringey Strategic Flood Risk Assessment (SFRA) was sought. This will be included and references in the relevant sections below.

10.0 Flood Risk

- 10.1.1 The data on the EA's website in their updated mapping, shows the site has a "very low" risk of flooding.
- 10.1.2 The EA confirmed that the proposed development site is located in Flood Zone 1 for Planning.
- 10.1.3 According to Table 2 of National Planning Policy Framework (NPPF), the development, being residential, is classed as 'more vulnerable'.
- 10.1.4 According to NPPF Table 3 'Flood Risk Vulnerability and Flood Zone Compatibility', the development should be permitted.

Table 3: Flood risk vulnerability and flood zone 'compatibility'

Flood risk vulnerability classification (see table 2)		Essential infrastructure	Water compatible	Highly vulnerable	More vulnerable	Less vulnerable
Flood zone (see table 1)	Zone 1	✓	✓	✓	✓	✓
	Zone 2	✓	✓	Exception Test required	✓	✓
	Zone 3a	Exception Test required	✓	✗	Exception Test required	✓
	Zone 3b functional floodplain	Exception Test required	✓	✗	✗	✗

Key: ✓ Development is appropriate.
 ✗ Development should not be permitted.

10.2 Sequential Test

- 10.2.1 Local Planning Authorities (LPA) are encouraged to take a risk-based approach to proposals for development in or affecting flood risk areas through the application of the Sequential Test and the objectives of this test are to steer new development away from high risk areas towards those at lower risk of flooding.
- 10.2.2 However, in some areas where developable land is in short supply, there can be an overriding need to build in areas that are at risk of flooding. In such circumstances, the application of the Sequential Test is used to ensure that the lower risk sites are developed before the higher risk ones.
- 10.2.3 NPPF (PPS25) states that the Sequential Test should be applied at all stages of the planning process and the starting point is generally the Environment Agency's flood zone maps.
- 10.2.4 These maps and the associated information are intended for guidance and cannot provide details for individual properties. They do not consider other considerations such as existing flood defences, alternative flooding mechanisms and detailed site-based surveys. They do, however, provide high level information on the type and likelihood of flood risk in any area of the country.
- 10.2.5 The site is within Flood Zone 1 and therefore the sequential test is not applicable.

10.3 Exception Test

- 10.3.1 The Exception Test is an additional test to be applied by decision-makers following application of the Sequential Test. The Exception Test has two elements as shown below, both of which must be satisfied for development in a flood risk area to be considered acceptable.
- 10.3.2 The Exception Test is only appropriate for use when there are large areas in Flood Zones 2 and 3, where the Sequential Test alone cannot deliver acceptable sites, but where some continuing development is needed for wider sustainable development reasons, considering the need to avoid social or economic blight and the need for essential civil infrastructure to remain operational during floods.
- 10.3.3 For the Exception Test to be passed:
 - a. It must be demonstrated that the development provides wider sustainability benefits to the community that outweigh flood risk, informed by a SFRA; and,
 - b. A site-specific FRA must demonstrate that the development will be safe for its lifetime, without increasing flood risk elsewhere and, where possible, reducing flood risk overall.
- 10.3.4 The NPPF does not request an exception test.

10.4 Fluvial Flooding Risk

10.4.1 The Environment Agency flood information there is no risk of fluvial flooding on site.

10.5 Historic Flood Data

10.5.1 The Environment Agency and Haringey Council have no information indicating that the site was flooded historically from fluvial sources.

10.6 Groundwater

10.6.1 Groundwater flooding is caused by the emergence of water originating from sub-surface permeable strata. A ground water flood event results from a rise in ground water level, enough for the water table to intersect the ground surface and inundate low lying land. Groundwater floods may emerge from either a single point or diffuse locations.

10.6.2 The underlying strata throughout the area and investigations into the SFRA geology data suggest that there is a risk of groundwater emergence which is likely to relate to the geology of the area. However, groundwater flooding risks are often highly localised, and dependent upon geological interfaces between permeable and impermeable subsoils. Therefore, sustainable construction techniques for surfacing will minimise any potential groundwater risk.

10.6.3 The Haringey SFRA has no information indicating that the site is at an elevated risk of groundwater flooding.

10.7 Flooding from Sewers

10.7.1 Flooding from sewers can occur because of different reasons; if sewers are blocked during the heavy rainfalls, or if sewer cannot provide adequate capacity, then flooding can cause a large amount of damage.

10.7.2 The Haringey SFRA has no records indicating the site has been flooded by sewers historically.

10.8 Flooding from Reservoirs

10.8.1 Reservoir flooding is extremely unlikely to happen. There has been no loss of life in the UK from reservoir flooding since 1925. All large reservoirs must be inspected and supervised by reservoir panel engineers. As the enforcement authority for the Reservoirs Act 1975 in England, the Environment Agency ensures that reservoirs are inspected regularly, and essential safety work is carried out.

10.8.2 However, in the unlikely event that a reservoir dam failed, a large volume of water would escape at once and flooding could happen with little or no warning. If the site is within a risk area, plans should be made for safe evacuation and escape. Residents may need to evacuate immediately, know the safest route to safety, and be ready to follow the advice of emergency services.

10.8.3 The EA data indicates that the site is not at risk from reservoir flooding.

10.9 Surface Water Flooding

10.9.1 Overland flow / surface water flooding typically arise because of intense rainfall, often of short duration, that is unable to soak into the ground or enter drainage systems. It can run quickly off land and result in localised flooding.

10.9.2 The Environment Agency has produced illustrative mapping (Flood Map for Surface Water) relating to flooding risks from surface water. They are classified as Flood Hazard Maps for the purpose of the Flood Risk Regulations 2009. These maps are the next generation on from the previous “Area Susceptible to Surface Water Flooding” maps, which are contained within the SFRA.

10.9.3 The EA maps show high resolution image and indicative flow paths for pluvial events. The maps are based on coarse level data and indicate ridges, valleys and flat spots where water would collect. Typically, the flow paths follow valleys, rivers and watercourses.

10.9.4 The surface water maps and the associated information are intended for guidance only and cannot provide details for individual properties. They do, however, provide high level information and indicate areas in which surface water flooding issues should be investigated further. The risk categories are classified as follows:

- Very low probability of flooding – This zone is assessed as having less than a 1 in 1000 annual probability of surface water flooding.
- Low probability of flooding – This zone comprises land assessed as having between a 1 in 100 and 1 in 1000 annual probability of surface water flooding.
- Medium probability of flooding - This zone comprises land assessed as having between a 1 in 30 and 1 in 100 annual probability of surface water flooding.
- High probability of flooding – This zone is assessed as having greater than a 1 in 30 annual probability of surface water flooding.

10.9.5 A review of the EA mapping indicates there is no risk of surface water flooding to the site.

11.0 Maintenance

11.1.1 Maintenance of SuDS drainage should be in accordance with the guidance presented in CIRIA Factsheet “Maintenance of SuDS” May 2017. A detailed maintenance plan for the scheme will be generated by the appointed owner/maintainer of the site or a selected maintenance company and this section is for guidance only.

11.1.2 Maintenance operations can be divided into the following categories:

- Regular (or routine frequent) - this covers items that are carried out typically with a frequency from monthly to annually. It includes items such as inspection and monitoring, litter removal, grass cutting or other vegetation management, sweeping permeable pavements.
- Infrequent (or routine infrequent) - this covers items that are required typically with a frequency from annually up to 25 years (or possibly greater). It includes items such as wetland vegetation management, silt removal from swales, ponds or wetlands, scarifying and spiking infiltration basins and gravel replacement to filter drains.
- Remedial (or reactive) - this covers maintenance that is not usually required, but may be necessary as a result of vandalism, accidental damage, rainfall that exceeds the design capacity or similar events. Examples include repair of erosion in a swale or repair of permeable surfaces blocked for example by mixing concrete on them.

11.2 Riparian Responsibility

11.2.1 If a resident owns land adjoining, above or with a portion of the drainage system running through it, they have certain rights and responsibilities. In legal terms they are a ‘riparian owner’. If they rent the land, they should agree with the owner who will manage these rights and responsibilities.

11.2.2 It is recommended that the owner’s appointed Management Company handle the maintenance of all underground drainage and all SuDS devices, with the following exceptions:

- Inspecting and cleaning out any surface mounted hard drainage systems (such as channel drains);
- Inspecting and cleaning out (or reporting) SuDS systems on a small scale (such as garden ditches and swales).

11.3 Allowing for Replacement

11.3.1 The design life of some SuDS elements and drainage elements of the proposed system is shorter than the predicted design life of the development. Therefore, the design and maintenance regime consider any potential replacement works (such as replacing permeable paving).

11.3.2 Regular inspection of the drainage system should be as per the tables below.


Operation and maintenance requirements for Surface Water Systems		
Maintenance Schedule	Required Action	Typical Frequency
Regular Maintenance	Inspect for sediment and debris in catchpit manholes and gullies. Clean out as required	Twice Annually
	Cleaning of gutters and any filters on downpipes	Annually (or as required based on inspections)
	Trimming any roots that may be causing blockages	Annually (or as required)
Occasional Maintenance	Remove sediment and debris from catchpits, gullies, attenuation devices and inside of concrete manhole rings	As required, based on inspections
Remedial Actions	Reconstruct and/or replace components, if performance deteriorates or failure/blockage occurs	As required
	Replacement of clogged components (flow restriction)	As required
Monitoring	Inspect silt traps/gullies/catchpits and note rate of sediment accumulation	Monthly in the first year and then annually
	Check flow control chamber and attenuation devices	Annually

Operation and maintenance requirements for Pervious Pavements		
Maintenance Schedule	Required Action	Typical Frequency
Regular Maintenance	Brushing and vacuuming (standard cosmetic sweep over whole surface)	Once a year, after autumn leaf fall, or reduced frequency as required, based on site-specific observations of clogging or manufacturer's recommendations – pay attention to areas where water runs onto pervious surface from adjacent impermeable areas as this area is most likely to collect the most sediment
	Stabilise and mow contributing and adjacent areas	As required
Occasional Maintenance	Removal of weeds or management using glyphosate (or suitable alternative as approved by the WHO) applied directly into the weeds by an applicator rather than spraying	As required – once per year on less frequently used pavements
	Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50 mm of the level of the paving	As required
Remedial Actions	Remedial work to any depressions, rutting and cracked or broken blocks considered detrimental to the structural performance or a hazard to users, and replace lost jointing material	As required
	Rehabilitation of surface and upper substructure by remedial sweeping	Every 10 to 15 years or as required (if infiltration performance is reduced due to significant clogging)
	Initial inspection	Monthly for three months after installation
Monitoring	Inspect for evidence of poor operation and/or weed growth – if required, take remedial action	Three-monthly, 48 h after large storms in first six months
	Inspect silt accumulation rates and establish appropriate brushing frequencies	Annually
	Monitor inspection chambers	Annually

12.0 Summary and Conclusions

- 12.1.1 Ellen Wibye is planning a proposed development on the site at Land to the rear of 10 Bidwell Gardens , London, N11 2AX.
- 12.1.2 Patrick Parsons has been instructed by Ellen Wibye , to produce a Drainage Strategy to support the Planning Application.
- 12.1.3 No documentary or anecdotal evidence has been found to show previous flooding events for this site.
- 12.1.4 The surface water system will discharge into the public surface water sewer at a restricted rate.
- 12.1.5 The foul water will discharge into the existing public sewer.
- 12.1.6 The report has demonstrated that the proposed drainage measures ensure that no property will be at risk of flooding if the development proceeds and that suitable means of surface water and foul drainage can be achieved for the proposed development.


Appendix A Location Plan



0 5 10 50
1:1250@A4

Appendix B

Topographical Survey



1

14

Elevation 3.

Section 1.

Elevation 3.

WROXHAM GARDENS

Elevation 2.

Elevation 1.

Elevation 1.



1:200@A3

Project : Land To Rear Of 10-12 Bidwell Gardens London N11

Drawing : Existing Site Plan

Dwg No : EX-100


Scale : 1:100@A3

Date : Sept 2020

Rev :

gtaassociates

gtaassociates@btinternet.com



Project : Land To Rear Of 10-12 Blomwell Gardens London N11

Date : Sept 2020

Rev :

Drawing : Existing Elevation 01


Dwg No : EX-101

Scale : 1:100@A3



gassociates

25, Cedar Lane, Cambridge, London, N11 2 7YU | Tel: 0203 8383 7744 | E: studio@gassociates.com | W: www.gassociates.com



Project : Land To Rear Of 10-12 Bidwell Gardens London N11


Drawing : Existing Elevation 02

Dwg No : EX-102

Scale : 1:100@A3


Date : Sept 2020

Rev :



gtaassociates

10, Colindale Avenue, London N11 2 7YU | Tel: 0203 8363 7744 | enquiries@gtassociates.com



Project : Land To Rear Of 10-12 Bidwell Gardens London N11

Date : Sept 2020

Rev :

Drawing : Existing Elevation 03

Dwg No : EX-103


Scale : 1:100@A3



1:100@A3

gtaassociates

10, Cedar Road, Camden, London, N1C 2 7YJ | Tel: 020 8361 7744 | Email: info@gtasoc.com



Project : Land To Rear Of 10-12 Bidwell Gardens London N11


Date : Sept 2020

Rev :

Drawing : Existing Section 01

Dwg No : EX-104

Scale : 1:200@A3




gtaassociates

10, Cedar Lane, Cambridge, London, N11 2 7YJ | Tel: 0203 938 8774 | E: enquiries@gtasociates.com

Appendix C

Thames Water Sewer Records



The width of the displayed area is 200 m and the centre of the map is located at OS coordinates 529553,191112

The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.

Based on the Ordnance Survey Map with the Sanction of the controller of H.M. Stationery Office, License no. 100019345 Crown Copyright Reserved.

NB. Levels quoted in metres Ordnance Newlyn Datum. The value -9999.00 indicates that no survey information is available

Manhole Reference	Manhole Cover Level	Manhole Invert Level
52ZS	n/a	n/a
52YY	n/a	n/a
52ZR	n/a	n/a
52YX	n/a	n/a
52ZY	n/a	n/a
52ZX	n/a	n/a
62WV	n/a	n/a
62WW	n/a	n/a
62VT	n/a	n/a
51WS	n/a	n/a
51ST	n/a	n/a
51RQ	n/a	n/a
51RW	n/a	n/a
5101	63.18	59.14
5102	62.96	59.61
51SV	n/a	n/a
51RX	n/a	n/a
51SW	n/a	n/a
51VR	n/a	n/a
51RY	n/a	n/a
51TV	n/a	n/a
51SX	n/a	n/a
51RZ	n/a	n/a
51VS	n/a	n/a
51SP	n/a	n/a
51SY	n/a	n/a
51TW	n/a	n/a
51VT	n/a	n/a
51VV	n/a	n/a
51TX	n/a	n/a
51VW	n/a	n/a
51TY	n/a	n/a
51VX	n/a	n/a
51TZ	n/a	n/a
51VY	n/a	n/a
51VP	n/a	n/a
51XP	n/a	n/a
51XY	n/a	n/a
51XQ	n/a	n/a
51XZ	n/a	n/a
51XR	n/a	n/a
51YP	n/a	n/a
51XS	n/a	n/a
51YQ	n/a	n/a
41VZ	n/a	n/a
51WT	n/a	n/a
41TW	n/a	n/a
41VR	n/a	n/a
41TX	n/a	n/a
41VS	n/a	n/a
41TY	n/a	n/a
41VT	n/a	n/a
51WP	n/a	n/a
51WR	n/a	n/a
41TZ	n/a	n/a
41VV	n/a	n/a
41TT	n/a	n/a
41VP	n/a	n/a
41VW	n/a	n/a
41VX	n/a	n/a
51TR	n/a	n/a
51TP	n/a	n/a
41TV	n/a	n/a
50YT	n/a	n/a
50YR	n/a	n/a
50XZ	n/a	n/a
50YP	n/a	n/a
501A	n/a	n/a
51ZT	n/a	n/a
511A	n/a	n/a
51YX	n/a	n/a
51YR	n/a	n/a
51YY	n/a	n/a
51YS	n/a	n/a
51YZ	n/a	n/a
51YT	n/a	n/a
51ZP	n/a	n/a
51ZQ	n/a	n/a
51YV	n/a	n/a
51YW	n/a	n/a
5103	57.83	53.99
51WY	n/a	n/a
51XW	n/a	n/a
51WZ	n/a	n/a
51SR	n/a	n/a
51XX	n/a	n/a
51RT	n/a	n/a
51WX	n/a	n/a
51XV	n/a	n/a
51RP	n/a	n/a
5104	57.87	54.61

Manhole Reference	Manhole Cover Level	Manhole Invert Level
51QW	n/a	n/a
51SS	n/a	n/a
5003	55.05	49.87
51RV	n/a	n/a
51QZ	n/a	n/a
5004	54.74	50.45
51QY	n/a	n/a
51QV	n/a	n/a
50XY	n/a	n/a
61ZV	n/a	n/a
61YZ	n/a	n/a
60VX	n/a	n/a
61YY	n/a	n/a
61ZS	n/a	n/a
61YX	n/a	n/a
61ZR	n/a	n/a
61YW	n/a	n/a
61ZQ	n/a	n/a
61YV	n/a	n/a
61ZP	n/a	n/a
61YT	n/a	n/a
61YS	n/a	n/a
40XT	n/a	n/a
5002	54.45	50.9
5001	54.46	50.43
40WV	n/a	n/a
50YV	n/a	n/a
50YW	n/a	n/a
40XV	n/a	n/a
40WW	n/a	n/a
40XP	n/a	n/a
40XW	n/a	n/a
40XX	n/a	n/a
40WR	n/a	n/a
40WX	n/a	n/a
40XQ	n/a	n/a
40WY	n/a	n/a
40XY	n/a	n/a
40WS	n/a	n/a
50ZP	n/a	n/a
40WZ	n/a	n/a
50ZQ	n/a	n/a
50YY	n/a	n/a
50ZR	n/a	n/a
40XR	n/a	n/a
50YZ	n/a	n/a
51ZR	n/a	n/a
51ZS	n/a	n/a
41WP	n/a	n/a
5006	48.69	46.46
60XZ	n/a	n/a
60WX	n/a	n/a
6005	49.74	44.99
60YP	n/a	n/a
6006	50.26	46.88
60WY	n/a	n/a
60YQ	n/a	n/a
60WZ	n/a	n/a
60XP	n/a	n/a
60YR	n/a	n/a
60VZ	n/a	n/a
6004	50.1	47.06
6002	50.01	46.91
60XQ	n/a	n/a
6003	50.26	46.3
60YT	n/a	n/a
60XR	n/a	n/a
6010	51.57	48.56
6009	51.62	47.74
6001	52.3	47.06
5005	52.72	48.13
4002	53.22	51.13
4001	53.31	50.88
40WP	n/a	n/a
41WR	n/a	n/a
41WQ	n/a	n/a
41VY	n/a	n/a
The position of the apparatus shown on this plan is given without obligation and warranty, and the accuracy cannot be guaranteed. Service pipes are not shown but their presence should be anticipated. No liability of any kind whatsoever is accepted by Thames Water for any error or omission. The actual position of mains and services must be verified and established on site before any works are undertaken.		



ALS Sewer Map Key

Public Sewer Types (Operated & Maintained by Thames Water)

	Foul: A sewer designed to convey waste water from domestic and industrial sources to a treatment works.
	Surface Water: A sewer designed to convey surface water (e.g. rain water from roofs, yards and car parks) to rivers or watercourses.
	Combined: A sewer designed to convey both waste water and surface water from domestic and industrial sources to a treatment works.
	Trunk Surface Water
	Trunk Foul
	Storm Relief
	Vent Pipe
	Bio-solids (Sludge)
	Proposed Thames Surface Water Sewer
	Proposed Thames Water Foul Sewer
	Gallery
	Surface Water Rising Main
	Sludge Rising Main
	Vacuum
	Foul Rising Main
	Combined Rising Main
	Proposed Thames Water Rising Main

Notes:

- 1) All levels associated with the plans are to Ordnance Datum Newlyn.
- 2) All measurements on the plans are metric.
- 3) Arrows (on gravity fed sewers) or flecks (on rising mains) indicate direction of flow.
- 4) Most private pipes are not shown on our plans, as in the past, this information has not been recorded.
- 5) 'na' or '0' on a manhole level indicates that data is unavailable.

Sewer Fittings

A feature in a sewer that does not affect the flow in the pipe. Example: a vent is a fitting as the function of a vent is to release excess gas.

	Air Valve
	Dam Chase
	Fitting
	Meter
	Vent Column

Operational Controls

A feature in a sewer that changes or diverts the flow in the sewer. Example: A hydrobrake limits the flow passing downstream.

	Control Valve
	Drop Pipe
	Ancillary
	Weir

End Items

End symbols appear at the start or end of a sewer pipe. Examples: an Undefined End at the start of a sewer indicates that Thames Water has no knowledge of the position of the sewer upstream of that symbol. Outfall on a surface water sewer indicates that the pipe discharges into a stream or river.

	Outfall
	Undefined End
	Inlet

- 6) The text appearing alongside a sewer line indicates the internal diameter of the pipe in millimetres. Text next to a manhole indicates the manhole reference number and should not be taken as a measurement. If you are unsure about any text or symbology present on the plan, please contact a member of Property Insight on 0845 070 9148.

Other Symbols

Symbols used on maps which do not fall under other general categories

	Public/Private Pumping Station
	Change of characteristic indicator (C.O.C.I.)
	Invert Level
	Summit

Areas

Lines denoting areas of underground surveys, etc.

	Agreement
	Operational Site
	Chamber
	Tunnel
	Conduit Bridge

Other Sewer Types (Not Operated or Maintained by Thames Water)

	Foul Sewer
	Combined Sewer
	Culverted Watercourse
	Surface Water Sewer
	Gully
	Proposed
	Abandoned Sewer

Appendix D

Magic Map Geology Information

Table of Contents

- ☐ Access
- ☐ Administrative Geographies
- ☐ Countryside Stewardship Targeting
- ☐ Scoring Layers
- ☐ Designations
- ☐ Habitats and Species
- ☐ Land based Schemes
- ☐ Landscape
- ☒ Geology and Soils
 - ☒ Aquifer Designation Map (Geotrack) (England)
 - ☐ Principal
 - ☐ Secondary A
 - ☐ Secondary B
 - ☐ Secondary (undifferentiated)
 - ☐ Unproductive
 - ☐ Aquifer Designation Map (Superficial Drift) (England)
 - ☐ Groundwater Vulnerability Map (England)
 - ☐ Geological Places to Visit (England)
 - ☐ Geological Descriptions (England)
 - ☐ Seiscope (England)
- ☐ Landscape Classifications




Table of Contents

☐ Access	☐ Geology and Soils
☐ Administrative Geographies	☐ Aquifer Designation Map (Bedrock) (England)
☐ Countryside Stewardship Targeting & Scoring Layers	☒ Aquifer Designation Map (Superficial Drift) (England)
☐ Designations	☐ Principal
☐ Habitats and Species	☐ Secondary A
☐ Land Based Schemes	☐ Secondary B
☐ Landscape	☐ Secondary (undifferentiated)
	☐ Unknown (lakes+landfill)
	☐ Unproductive
	☐ Groundwater Vulnerability Map (England)
	☐ Geological Places to Visit (England)
	☐ Geological Descriptions (England)
	☐ Soilscapes (England)
	☐ Landscape Classifications




Table of Contents

- ☐ Access
- ☐ Administrative Geographies
- ☐ Countryside Stewardship Targeting & Scoring Layers
- ☐ Designations
- ☐ Habitats and Species
- ☐ Land Based Schemes
- ☒ Landscape

- ☒ Geology and Soils
 - ☐ Aquifer Designation Map (Bedrock) (England)
 - ☐ Aquifer Designation Map (Superficial Drift) (England)
 - ☒ Groundwater Vulnerability Map (England)

- ☐ Local Information
 - ☐ Soluble Rock Risk
 - High
 - Medium - High
 - Medium
 - Medium - Low
 - Low
 - ☐ Unproductive
 - ☐ Geological Places to Visit (England)
 - ☐ Geological Descriptions (England)

- ☐ Solignum (England)




Table of Contents

- ☐ + RSPB Reserves (GB)

☐ ☒ Upland Experiment Areas (England) (1)

☐ Objective 1 Areas (England) (1)

☐ Objective 2 Areas (England) (1)

☐ Drinking Water Protected Areas (Surface water) (England) (1)

☐ Drinking Water Safeguard Zones (Surface water) (England) (1)

☐ Drinking Water Safeguard Zones (Groundwater) (England) (1)

☒ Source Protection Zones merged (England) (1)

☐ + Marine Designations

☐ Habitats and Species


☐ Land Based Schemes

☐ Landscape

☐ Marine

☐ Aerial Photography

☒ Background Mapping



Appendix E

Greenfield Run-Off

Patrick Parsons Limited		Page 1
Waterloo House Thornton Street Newcastle Upon Tyne, NE1 4AP	Bidwell Gardens	
Date 01/09/2020 10:11 File	Designed by A Johnson Checked by D Brooke	
Innovyze	Source Control 2020.1	

ICP SUDS Mean Annual Flood

Input

Return Period (years)	1	Soil	0.450
Area (ha)	0.031	Urban	0.000
SAAR (mm)	800	Region Number	Region 6


Results 1/s

QBAR Rural	0.2
QBAR Urban	0.2
Q1 year	0.1
Q1 year	0.1
Q30 years	0.4
Q100 years	0.5


©1982-2020 Innovyze

Appendix F

Site Plan



Proposed Lower Ground Floor



Proposed Ground Floor

LGF and GF Plan

927.201

Wroxham House

Issue Notes

Date

Wroxham Gardens N11 2AX

Drawn By

Scale

1:100@A3

Status

Planning

Project Stage

Paul Archer Design Ltd


Unit D204 116 Commercial Street


London

E1 6NF

www.paularcherdesign.co.uk Tel. 020 3668 2668

Bitmap3790342101.jpg





Site Plan

927.200

Key

- Permeable paving
- Hard landscaping
- Soft landscaping

Areas

- GIA
- LGf
- FF - 60sqm
- FF - 100sqm
- FF - 100sqm

Issue Notes

Date

Bitmap2790342802.jpg

Wroxham House
Drawn By
Scale
Status
Project Stage

N11 2AX
AF
1:100@A3
Planning
Planning

Paul Archer Design Ltd

Unit D204 116 Commercial Street


London

E1 6NF


www.paularcherdesign.co.uk Tel. 020 3668 2668

Appendix G

Schematic Drainage Layout



GROUND FLOOR LEVEL



LOWER GROUND FLOOR LEVEL

Drainage Key

- 450mmØ PPIC chamber
- 450mmØ PPIC Catchpit
- Concrete Manhole Chamber
- Flow Control Chamber
- Proposed Foul Water (Private)
- Existing Foul Water (Public)
- Proposed Surface Water (Private)
- Partial Infiltration Pipe
- Existing Surface Water (Public)
- Road Gully
- Yard Gully
- Channel Drain
- Rodding Eye
- Water Butt
- Porous Paving
- Exceedance Flow Direction

GENERAL NOTES

1. THIS DRAWING IS COPYRIGHT AND SHOULD NOT BE REPRODUCED IN WHOLE OR PART WITHOUT THE WRITTEN CONSENT OF PATRICK PARSONS.

2. DO NOT SCALE FROM THIS DRAWING.

3. LOCATIONS OF ALL EXISTING SERVICES ON-SITE TO BE CONFIRMED & PROVIDED TO THE ENGINEER PRIOR TO COMMENCEMENT OF WORKS.

4. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT PATRICK PARSONS DRAWINGS & SPECIFICATIONS.

Drainage Construction Notes

- All materials and workmanship related to private sewers shall be in accordance with Part H of the Building Regulations and BS EN1252 and best practice.
- All materials and workmanship related to adoptable sewers shall be in accordance with the Design and Construction Guidance 2020 as published by the Water Services Association and any subsequent revisions shown by the water authority.
- All sustainable drainage systems to be designed and maintained in accordance with CIRIA C753 The SuDS Manual and best practice guidance.
- Gully and channel grating shall be ductile iron to BS EN124, Load Class D400, and kitemarked.
- Manhole covers and frames to be ductile iron to BS EN124 Class D400 in carriageways and Class S125 in verges unless otherwise specified. Covers may be kitemarked and badged "SW" or "FW" as appropriate unless otherwise instructed by the water authority. Blackbrink rolled manhole covers are not to be used on adoptable manholes.
- All dayware pipes to be vitrified clay to BS EN 295 or BS 65 and of minimum strength Class 120 or Extra Strength respectively.
- All plastic pipes to be PVC-U in accordance with BS EN 1401.
- All underfloor hung drainage to be ductile iron in accordance with BS EN 545: 1994 and BS EN 598: 1994 unless explicitly noted on the drawing.
- All carrier drains under carriageway to be constructed with BEDDING TYPES S or Z depending on depth of cover as described on Typical Drainage Details drawing.
- First flexible joint in pipes adjacent to a manhole shall be 600mm from inside face of manhole, connecting to rocker pipe. For pipes of 150-450mm, the rocker pipe length shall be 500mm-750mm and for pipe diameters 451-750 rocker pipe shall be 750mm-1000mm.
- Pipes shall be laid to their true line and level by laser or by boring each end and middle.
- All soft spots within pipe trenches shall be removed.
- No water shall be allowed to accumulate in pipe trenches during construction.
- All fill material shall be consolidated in layers not exceeding 225mm.
- P.C concrete linings to be used over pipes and ducts passing through walls, subject to design by structural engineer.
- All inlets concrete used in pipe protection to be min. grade S12 unless noted otherwise on the typical details.
- Compressible filler for interruption of concrete pipe protection shall consist of bitumen impregnated insulating board to BS 1142 at each pipe joint.
- All redundant drains shall be removed or concrete sealed.
- All pipe runs to be laid with flexible joints.
- All pipe connections to be made soffit to soffit.
- All pipework with less than 1.2m cover within roads or parking areas to have concrete bed & surround.
- If the contractor finds any discrepancies in the information provided then he must notify the engineer immediately before any materials are ordered or works undertaken.
- All underdrain drainage at minimum 1 in 40 fall unless noted on the drawing.
- All patios and external surfaces to drain away from building thresholds unless explicitly noted on the plan.

P2	SITE LAYOUT UPDATED	12.02.24	AM	DB
P1	INITIAL ISSUE	01.09.20	AJ	DB
Rev	Amendments	Date	Dwg	CHK

Revisions

PATRICK PARSONS
Build | Develop | Engineer | Consultancy

Sahelil House, 2 Nexus Park
Lyons Avenue, Ash Vale
Guilford
GU12 5QE UK

T: +44 (0)1276 700 400
E: info@patrickparsons.co.uk
W: www.patrickparsons.co.uk

Client
GT Associates

Project
Land to the rear of 10 Bidwell Gardens

Drawing
Schematic Drainage Layout

Scales 1:100 At original size A1

Date	Sep 2020	Drawn by	AJ	Checked by	DB
------	----------	----------	----	------------	----

Status **PRELIMINARY**

Drawing No. **A20193/0200** Rev. **P2**

Appendix H

Hydraulic Calculations

**Design Settings**

Rainfall Methodology	FSR	Maximum Time of Concentration (mins)	30.00
Return Period (years)	100	Maximum Rainfall (mm/hr)	50.0
Additional Flow (%)	0	Minimum Velocity (m/s)	1.00
FSR Region	England and Wales	Connection Type	Level Soffits
M5-60 (mm)	20.000	Minimum Backdrop Height (m)	1.000
Ratio-R	0.400	Preferred Cover Depth (m)	1.200
CV	0.750	Include Intermediate Ground	✓
Time of Entry (mins)	5.00	Enforce best practice design rules	✓

Nodes

Name	Area (ha)	T of E (mins)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)
PS1	0.007	5.00	60.800	180	529551.288	191130.012	0.600
PS2	0.004	5.00	62.111	450	529544.960	191136.094	2.021
PS3	0.002	5.00	60.800	450	529537.477	191128.308	0.845
PS4			60.513	450	529540.841	191121.471	0.653
PS5	0.004	5.00	58.600	450	529545.106	191122.025	0.600
PS6			60.122	1350	529545.621	191117.641	2.177
PS7	0.002	5.00	60.488	180	529550.410	191121.191	0.600
PS9			60.188	1350	529553.704	191118.590	2.345
PS10			58.590	450	529555.263	191105.314	0.914

Simulation Settings

Rainfall Methodology	FSR	Analysis Speed	Normal
FSR Region	England and Wales	Skip Steady State	x
M5-60 (mm)	20.000	Drain Down Time (mins)	120
Ratio-R	0.400	Additional Storage (m³/ha)	20.0
Summer CV	0.750	Check Discharge Rate(s)	x
Winter CV	0.840	Check Discharge Volume	x

Storm Durations

15 | 30 | 60 | 120 | 180 | 240 | 360 | 480 | 600 | 720 | 960 | 1440

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
2	0	0	0
30	0	0	0
100	40	10	0

Node PS9 Online Hydro-Brake® Control

Flap Valve	x	Objective	(HE) Minimise upstream storage
Replaces Downstream Link	✓	Sump Available	✓
Invert Level (m)	57.843	Product Number	CTL-SHE-0057-1200-0600-1200
Design Depth (m)	0.600	Min Outlet Diameter (m)	0.075
Design Flow (l/s)	1.2	Min Node Diameter (mm)	1200

Node PS4 Online Orifice Control

Flap Valve	x	Design Depth (m)	2.200	Discharge Coefficient	0.600
Replaces Downstream Link	✓	Design Flow (l/s)	2.0		
Invert Level (m)	59.860	Diameter (m)	0.025		



Node PS2 Carpark Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Invert Level (m)	60.090	Slope (1:X)	100.0
Side Inf Coefficient (m/hr)	0.00000	Time to half empty (mins)	30	Depth (m)	0.300
Safety Factor	2.0	Width (m)	4.000	Inf Depth (m)	
Porosity	0.30	Length (m)	9.250		

Node PS4 Carpark Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Invert Level (m)	59.860	Slope (1:X)	100.0
Side Inf Coefficient (m/hr)	0.00000	Time to half empty (mins)	118	Depth (m)	0.300
Safety Factor	2.0	Width (m)	3.000	Inf Depth (m)	
Porosity	0.30	Length (m)	5.000		

Node PS9 Carpark Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Invert Level (m)	59.588	Slope (1:X)	100.0
Side Inf Coefficient (m/hr)	0.00000	Time to half empty (mins)	0	Depth (m)	0.300
Safety Factor	2.0	Width (m)	3.000	Inf Depth (m)	
Porosity	0.30	Length (m)	5.000		

**Results for 2 year Critical Storm Duration. Lowest mass balance: 100.00%**

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
15 minute winter	PS1	10	60.230	0.030	1.3	0.0077	0.0000	OK
15 minute winter	PS2	11	60.127	0.037	2.0	0.0922	0.0000	OK
30 minute winter	PS3	27	60.032	0.077	1.8	0.0159	0.0000	OK
30 minute winter	PS4	27	60.032	0.172	1.8	0.6901	0.0000	SURCHARGED
15 minute summer	PS5	10	58.022	0.022	0.7	0.0065	0.0000	OK
15 minute winter	PS6	12	57.972	0.027	1.1	0.0385	0.0000	OK
15 minute winter	PS7	10	59.904	0.016	0.4	0.0014	0.0000	OK
15 minute winter	PS9	14	57.938	0.095	1.4	0.1366	0.0000	OK
15 minute summer	PS10	1	57.676	0.000	1.1	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
15 minute winter	PS1	1.000	PS2	1.3	0.573	0.188	0.0197	
15 minute winter	PS2	1.001	PS3	1.9	0.693	0.281	0.0333	
30 minute winter	PS3	1.002	PS4	1.8	0.522	0.272	0.0545	
30 minute winter	PS4	Orifice	PS6	0.5				
15 minute summer	PS5	2.000	PS6	0.7	0.494	0.104	0.0065	
15 minute winter	PS6	1.004	PS9	1.1	0.434	0.158	0.0378	
15 minute winter	PS7	3.000	PS9	0.4	0.464	0.050	0.0032	
15 minute winter	PS9	Hydro-Brake®	PS10	1.1				1.6

**Results for 30 year Critical Storm Duration. Lowest mass balance: 100.00%**

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
15 minute winter	PS1	10	60.242	0.042	2.4	0.0109	0.0000	OK
30 minute winter	PS2	27	60.156	0.066	3.0	0.2795	0.0000	OK
30 minute winter	PS3	28	60.155	0.200	3.4	0.0413	0.0000	SURCHARGED
30 minute winter	PS4	28	60.154	0.294	2.8	1.2608	0.0000	SURCHARGED
30 minute winter	PS5	26	58.054	0.054	1.1	0.0159	0.0000	OK
30 minute winter	PS6	25	58.055	0.110	1.7	0.1567	0.0000	SURCHARGED
15 minute winter	PS7	11	59.910	0.022	0.7	0.0020	0.0000	OK
30 minute winter	PS9	25	58.052	0.209	1.9	0.2986	0.0000	SURCHARGED
15 minute summer	PS10	1	57.676	0.000	1.2	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
15 minute winter	PS1	1.000	PS2	2.4	0.671	0.351	0.0316	
30 minute winter	PS2	1.001	PS3	2.9	0.698	0.431	0.0720	
30 minute winter	PS3	1.002	PS4	2.8	0.527	0.420	0.0596	
30 minute winter	PS4	Orifice	PS6	0.7				
30 minute winter	PS5	2.000	PS6	1.1	0.524	0.164	0.0269	
30 minute winter	PS6	1.004	PS9	1.4	0.410	0.204	0.0637	
15 minute winter	PS7	3.000	PS9	0.7	0.563	0.098	0.0052	
30 minute winter	PS9	Hydro-Brake®	PS10	1.2				4.0

**Results for 100 year +40% CC +10% A Critical Storm Duration. Lowest mass balance: 100.00%**

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	PS1	55	60.349	0.149	2.5	0.0420	0.0000	SURCHARGED
60 minute winter	PS2	55	60.348	0.258	3.9	2.4063	0.0000	SURCHARGED
60 minute winter	PS3	55	60.346	0.391	3.1	0.0825	0.0000	SURCHARGED
60 minute winter	PS4	55	60.344	0.484	2.7	1.3192	0.0000	FLOOD RISK
60 minute winter	PS5	60	58.418	0.418	1.4	0.1280	0.0000	FLOOD RISK
60 minute winter	PS6	60	58.418	0.473	1.8	0.6771	0.0000	SURCHARGED
15 minute winter	PS7	10	59.920	0.032	1.4	0.0031	0.0000	OK
60 minute winter	PS9	60	58.415	0.572	1.8	0.8183	0.0000	SURCHARGED
15 minute summer	PS10	1	57.676	0.000	1.2	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	PS1	1.000	PS2	2.5	0.629	0.369	0.0687	
60 minute winter	PS2	1.001	PS3	2.5	0.601	0.372	0.0845	
60 minute winter	PS3	1.002	PS4	2.7	0.527	0.397	0.0596	
60 minute winter	PS4	Orifice	PS6	0.9				
60 minute winter	PS5	2.000	PS6	1.2	0.488	0.174	0.0345	
60 minute winter	PS6	1.004	PS9	1.3	0.410	0.185	0.0637	
15 minute winter	PS7	3.000	PS9	1.4	0.675	0.193	0.0085	
60 minute winter	PS9	Hydro-Brake®	PS10	1.2				9.8

Appendix J

Environment Agency Flood Map

Flood map for planning

Your reference
A20193

Location (easting/northing)
529524/191094

Created
1 Sep 2020 10:18

Your selected location is in flood zone 1, an area with a low probability of flooding.

This means:

- you don't need to do a flood risk assessment if your development is smaller than 1 hectare and not affected by other sources of flooding
- you may need to do a flood risk assessment if your development is larger than 1 hectare or affected by other sources of flooding or in an area with critical drainage problems

Notes

The flood map for planning shows river and sea flooding data only. It doesn't include other sources of flooding. It is for use in development planning and flood risk assessments.

This information relates to the selected location and is not specific to any property within it. The map is updated regularly and is correct at the time of printing.

The Open Government Licence sets out the terms and conditions for using government data.
<https://www.nationalarchives.gov.uk/doc/open-government-licence/version/3/>

Flood map for planning

Your reference

A20193

Location (easting/northing)

529524/191094

Scale

1:2500

Created

1 Sep 2020 10:18



Selected point



Flood zone 3



Flood zone 3: areas
benefiting from flood
defences



Flood zone 2



Flood zone 1



Flood defence




Main river



Flood storage area



Page 2 of 2



UK Locations

Ash Vale
Birmingham
London
Wakefield

