



Edmansons Close, Tottenham
The Drapers Almshouse Charity

Transport Statement

For

The Drapers Company

Document Control Sheet

Edmansons Close, Tottenham

The Drapers Almshouse Charity

The Drapers Company

This document has been issued and amended as follows:

Date	Issue	Prepared by	Approved by
15/07/2022	For Submission	GL/AM	AW
09/09/2025	V1	GL	AW



Motion
84 North Street
Guildford
GU1 4AU
T 01483 531300
F 01483 531333
E info@motion.co.uk
W www.motion.co.uk

Contents

1.0 Introduction 1

2.0 Policy 2

3.0 Baseline Conditions10

4.0 Proposed Development16

5.0 Impacts of Development Proposals.....19

6.0 Framework Travel Plan21

7.0 Summary and Conclusion.....23

Figures

Figure 3.1 Strategic Site Location Plan10

Figure 3.2 Local Site Location Plan11

Appendices

A Plan of Parking Survey Locations

B Full Parking Survey Results

C Full PTAL Output

D Car and Cycle Parking Arrangement

E Refuse Vehicle Swept Path Analysis

F Delivery Van Swept Path Analysis

G Swept Path Analysis Fire Appliance

H Proposed use TRICs output

1.0 Introduction

- 1.1 This Transport Statement has been prepared on behalf of The Draper's Almshouse Charity to accompany a planning application for the redevelopment of the charity owned dwellings surrounding Edmansons Close, Tottenham (herein referred to as 'the site') and reflects extensive discussions with LN Haringey (LBH) since submission of the planning application.
- 1.2 The site is located to the east of A10 Bruce Grove and accessed via Edmansons Close. The site benefits from close proximity to the A10 Bruce Grove and the A406 North Circular Road, as well as a number of bus stops and Bruce Grove railway station. The local centre of Bruce Grove is circa 500 metres southeast of the site. The site is situated within the administrative boundary of the London Borough of Haringey (LBH).
- 1.3 The site currently consists of 48 studios, 1 x 1 bed and 12 x 2 bed, all of which are owned and maintained by The Draper's Almshouse Charity. Facilities for residents include a Community Hall for social activities within the old Chapel and a laundry building.
- 1.4 The site is seeking planning permission to include the Demolition of existing laundry building and 1970s infill building; alterations and extensions to 44 existing almshouses to create 8 x 1 bed, 12 x 2 bed and 6 x 3 bed units; alterations to existing Gatehouse to provide 1 x 2 bed unit; construction of 1 x new build 3 bed almshouse to replace 1970s infill building; construction of a new apartment building comprising 7 x studio units and 9 x 1 bed units; construction of 4 x new build 2 bed units within two new pavilions (2 units in each pavilion, 4 units in total); with landscaping; improvements to access; provision of five disabled car parking spaces; and ancillary development thereto.
- 1.5 This Transport Statement has been prepared to consider the transport aspects relating to the proposal, including the proximity of the site to sustainable modes of travel, the parking, circulation and servicing of the site and any impacts of the proposal in transport terms. It also benefits from comments received by the LBH as the Highway Authority.
- 1.6 Following this introduction, this Transport Statement is split into 5 sections as follows:
 - ▶ Section 2 outlines the transport planning policies that are considered to be relevant to this application;
 - ▶ Section 3 sets out the existing use of the site and description of the surrounding area and highway network;
 - ▶ Section 4 provides an overview of the proposed development and detail of the proposed access, parking and servicing;
 - ▶ Section 5 assess the trip generation of the proposal and considers any offsite transport impacts; and,
 - ▶ Section 6 summarises the conclusions drawn by this report.

2.0 Policy

Overview

- 2.1 There are a number of documents that contain planning policies relevant to transport. The key policy documents which set the context for the development proposals are as follows:

- ▶ National Planning Policy Framework – December 2024;
- ▶ London Plan 2021; and
- ▶ Haringey Development Management Plan, 1 July 2017;

National Policy

National Planning Policy Framework

- 2.2 The National Planning Policy Framework (NPPF) December 2024 sets out the Government's planning policies for England and how they are expected to be applied.

- 2.3 Section 9 of the NPPF deals with 'Promoting Sustainable Transport', with Paragraph 109 stating:

"Transport issues should be considered from the earliest stages of plan-making and development proposals, using a vision-led approach to identify transport solutions that deliver well-designed, sustainable and popular places. This should involve:

- a) making transport considerations an important part of early engagement with local communities;*
- b) ensuring patterns of movement, streets, parking and other transport considerations are integral to the design of schemes, and contribute to making high quality places;*
- c) understanding and addressing the potential impacts of development on transport networks;*
- d) realising opportunities from existing or proposed transport infrastructure, and changing transport technology and usage – for example in relation to the scale, location or density of development that can be accommodated;*
- e) identifying and pursuing opportunities to promote walking, cycling and public transport use; and*
- f) identifying, assessing and taking into account the environmental impacts of traffic and transport infrastructure – including appropriate opportunities for avoiding and mitigating any adverse effects, and for net environmental gains."*

- 2.4 Paragraph 110 emphasises the need for significant developments to be situated within sustainable locations, stating:

"The planning system should actively manage patterns of growth in support of these objectives. Significant development should be focused on locations which are or can be made sustainable, through limiting the need to travel and offering genuine choice of transport modes. This can help to reduce congestion and emissions, and improve air quality and public health. However, opportunities to maximise sustainable transport solutions will vary between urban and rural areas, and this should be taken into account in both plan making and decision making."

- 2.5 Off- street parking provision is referred to by Paragraph 112 which states that local planning authorities should take into account the following if setting local parking standards for development:
- a) *"the accessibility of the development;*
 - b) *the type, mix and use of development;*
 - c) *the availability of and opportunities for public transport;*
 - d) *local car ownership levels; and*
 - e) *the need to ensure an adequate provision of spaces for charging plug-in and other ultra-low emission vehicles."*
- 2.6 Paragraph 113 states:
- "Maximum parking standards for residential and non-residential development should only be set where there is a clear and compelling justification that they are necessary for managing the local road network, or for optimising the density of development in city and town centres and other locations that are well served by public transport (in accordance with chapter 11 of this Framework). In town centres, local authorities should seek to improve the quality of parking so that it is convenient, safe and secure, alongside measures to promote accessibility for pedestrians and cyclists."*
- 2.7 Paragraph 115 addresses the relationship between development and sustainable transport as follows:
- "In assessing sites that may be allocated for development in plans, or specific applications for development, it should be ensured that:*
- a) *sustainable transport modes are prioritised taking account of the vision for the site, the type of development and its location;*
 - b) *safe and suitable access to the site can be achieved for all users;*
 - c) *the design of streets, parking areas, other transport elements and the content of associated standards reflects current national guidance, including the National Design Guide and the National Model Design Code48; and*
 - d) *any significant impacts from the development on the transport network (in terms of capacity and congestion), or on highway safety, can be cost effectively mitigated to an acceptable degree through a vision-led approach."*
- 2.8 Furthermore, paragraph 116 states that:
- "Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network, following mitigation, would be severe, taking into account all reasonable future scenarios."*

2.9 Paragraph 117 suggests that, within the context of Paragraph 116, applications for development should:

- a) *"Give priority first to pedestrian and cycle movements, both within the scheme and with neighbouring areas; and second – so far as possible – to facilitating access to high quality public transport, with layouts that maximise the catchment area for bus or other public transport services, and appropriate facilities that encourage public transport use;*
- b) *Address the needs of people with disabilities and reduced mobility in relation to all modes of transport;*
- c) *Create places that are safe, secure and attractive – which minimise the scope for conflict between pedestrians, cyclists and vehicles, avoid unnecessary street clutter, and respond to local character and design standards;*
- d) *Allow for the efficient delivery of goods, and access by service and emergency vehicles; and*
- e) *Be designed to enable charging of plug-in and other ultra-low emission vehicles in safe, accessible and convenient locations."*

2.10 Paragraph 118 states:

"All developments that will generate significant amounts of movement should be required to provide a travel plan, and the application should be supported by a vision-led transport statement or transport assessment so that the likely impacts of the proposal can be assessed and monitored."

London Plan 2021

2.11 Following the Examination in Public and acceptance by The Mayor of issues raised by the Secretary of State, the new London Plan was adopted in March 2021. With regards to transport, the most pertinent to these proposals are as follows:

2.12 Policy T2 Healthy Streets:

A) Development proposals and Development Plans should deliver patterns of land use that facilitate residents making shorter, regular trips by walking or cycling.

B) Development Plans should:

1) promote and demonstrate the application of the Mayor's Healthy Streets Approach to: improve health and reduce health inequalities; reduce car dominance, ownership and use, road danger, severance, vehicle emissions and noise; increase walking, cycling and public transport use; improve street safety, comfort, convenience and amenity; and support these outcomes through sensitively designed freight facilities.

2) identify opportunities to improve the balance of space given to people to dwell, walk, cycle, and travel on public transport and in essential vehicles, so space is used more efficiently and streets are greener and more pleasant.

C) In Opportunity Areas and other growth areas, new and improved walking, cycling and public transport networks should be planned at an early stage, with delivery phased appropriately to support mode shift towards active travel and public transport. Designs for new or enhanced streets must demonstrate how they deliver against the ten Healthy Streets Indicators.

D) Development proposals should:

1) demonstrate how they will deliver improvements that support the ten Healthy Streets Indicators in line with Transport for London guidance

2) reduce the dominance of vehicles on London's streets whether stationary or moving

3) be permeable by foot and cycle and connect to local walking and cycling networks as well as public transport.

2.13 Policy T4 Assessing and mitigating transport impacts:

A) Development Plans and development proposals should reflect and be integrated with current and planned transport access, capacity and connectivity.

B) When required in accordance with national or local guidance, transport assessments/statements should be submitted with development proposals to ensure that impacts on the capacity of the transport network (including impacts on pedestrians and the cycle network), at the local, network-wide and strategic level, are fully assessed. Transport assessments should focus on embedding the Healthy Streets Approach within, and in the vicinity of, new development. Travel Plans, Parking Design and Management Plans, Construction Logistics Plans and Delivery and Servicing Plans will be required having regard to Transport for London guidance.

C) Where appropriate, mitigation, either through direct provision of public transport, walking and cycling facilities and highways improvements or through financial contributions, will be required to address adverse transport impacts that are identified.

D) Where the ability to absorb increased travel demand through active travel modes has been exhausted, existing public transport capacity is insufficient to allow for the travel generated by proposed developments, and no firm plans and funding exist for an increase in capacity to cater for the increased demand, planning permission will be contingent on the provision of necessary public transport and active travel infrastructure.

E) The cumulative impacts of development on public transport and the road network capacity including walking and cycling, as well as associated effects on public health, should be taken into account and mitigated.

F) Development proposals should not increase road danger.

2.14 Policy T5 Cycling:

A) Development Plans and development proposals should help remove barriers to cycling and create a healthy environment in which people choose to cycle. This will be achieved through:

1) supporting the delivery of a London-wide network of cycle routes, with new routes and improved infrastructure

2) securing the provision of appropriate levels of cycle parking which should be fit for purpose, secure and well-located. Developments should provide cycle parking at least in accordance with the minimum standards set out in Table 10.2 and Figure 10.2, ensuring that a minimum of two short-stay and two long-stay cycle parking spaces are provided where the application of the minimum standards would result in a lower provision.

B) Cycle parking should be designed and laid out in accordance with the guidance contained in the London Cycling Design Standards. Development proposals should demonstrate how cycle parking facilities will cater for larger cycles, including adapted cycles for disabled people.

C) Development Plans requiring more generous provision of cycle parking based on local evidence will be supported.

D) Where it is not possible to provide suitable short-stay cycle parking off the public highway, the borough should work with stakeholders to identify an appropriate on-street location for the required provision. This may mean the reallocation of space from other uses such as on street car parking. Alternatively, in town centres, adding the required provision to general town centre cycle parking is also acceptable. In such cases, a commuted sum should be paid to the local authority to secure provision.

E) Where it is not possible to provide adequate cycle parking within residential developments, boroughs must work with developers to propose alternative solutions which meet the objectives of the standards. These may include options such as providing spaces in secure, conveniently located, on-street parking facilities such as bicycle hangers.

F) Where the use class of a development is not fixed at the point of application, the highest potential applicable cycle parking standard should be applied.

Land Use	London Plan (2021) minimum Standards	
	Long stay	Short stay
C3 Dwellings (all)	1 space per studio or 1 person 1 bedroom dwelling 1.5 spaces per 2-person 1 bedroom dwelling 2 spaces per all other Dwellings	5 to 40 dwellings: 2 spaces Thereafter: 1 space per 40 dwellings

Table 2.2 - Extract of Table 10.2 London Plan Minimum Cycle Parking Standards

2.15 Policy T6 Car parking

- A) Car parking should be restricted in line with levels of existing and future public transport accessibility and connectivity.*
- B) Car-free development should be the starting point for all development proposals in places that are (or are planned to be) well-connected by public transport, with developments elsewhere designed to provide the minimum necessary parking ('car-lite'). Car-free development has no general parking but should still provide disabled persons parking in line with Part E of this policy.*
- C) An absence of local on-street parking controls should not be a barrier to new development, and boroughs should look to implement these controls wherever necessary to allow existing residents to maintain safe and efficient use of their streets.*
- D) The maximum car parking standards set out in Policy T6.1 Residential parking to Policy T6.5 Non-residential disabled persons parking should be applied to development proposals and used to set local standards within Development Plans.*
- E) Appropriate disabled persons parking for Blue Badge holders should be provided as set out in Policy T6.1 Residential parking to Policy T6.5 non-residential disabled persons parking.*
- F) Where provided, each motorcycle parking space should count towards the maximum for car parking spaces at all use classes.*
- G) Where car parking is provided in new developments, provision should be made for infrastructure for electric or other Ultra-Low Emission vehicles in line with Policy T6.1 Residential parking, Policy T6.2 Office parking, Policy T6.3 Retail parking, and Policy T6.4 Hotel and leisure uses parking. All operational parking should make this provision, including offering rapid charging. New or re-provided petrol filling stations should provide rapid charging hubs and/or hydrogen refuelling facilities.*
- H) Where electric vehicle charging points are provided on-street, physical infrastructure should not negatively affect pedestrian amenity and should ideally be located off the footway. Where charging points are located on the footway, it must remain accessible to all those using it including disabled people.*
- I) Adequate provision should be made for efficient deliveries and servicing and emergency access.*
- J) A Parking Design and Management Plan should be submitted alongside all applications which include car parking provision, indicating how the car parking will be designed and managed, with reference to Transport for London guidance on parking management and parking design.*

K) Boroughs that have adopted or wish to adopt more restrictive general or operational parking policies are supported, including borough-wide or other area-based car-free policies. Outer London boroughs wishing to adopt minimum residential parking standards through a Development Plan Document (within the maximum standards set out in Policy T6.1 Residential parking) must only do so for parts of London that are PTAL 0-1. Inner London boroughs should not adopt minimum standards. Minimum standards are not appropriate for non-residential use classes in any part of London.

L) Where sites are redeveloped, parking provision should reflect the current approach and not be re-provided at previous levels where this exceeds the standards set out in this policy. Some flexibility may be applied where retail sites are redeveloped outside of town centres in areas which are not well served by public transport, particularly in outer London.

2.16 Policy 6.1 – Residential Parking standards states the following:

"A New residential development should not exceed the maximum parking standards set out in Table 10.3. These standards are a hierarchy with the more restrictive standard applying when a site falls into more than one category.

B Parking spaces within communal car parking facilities (including basements) should be leased rather than sold.

C All residential car parking spaces must provide infrastructure for electric or Ultra-Low Emission vehicles. At least 20 per cent of spaces should have active charging facilities, with passive provision for all remaining spaces.

D Outside of the CAZ, and to cater for infrequent trips, car club spaces may be considered appropriate in lieu of private parking. Any car club spaces should have active charging facilities.

E Large-scale purpose-built shared living, student accommodation and other sui generis residential uses should be car-free.

F The provision of car parking should not be a reason for reducing the level of affordable housing in a proposed development.

G Disabled persons parking should be provided for new residential developments. Residential development proposals delivering ten or more units must, as a minimum:

1) ensure that for three per cent of dwellings, at least one designated disabled persons parking bay per dwelling is available from the outset

2) demonstrate as part of the Parking Design and Management Plan, how an additional seven per cent of dwellings could be provided with one designated disabled persons parking space per dwelling in future upon request as soon as existing provision is insufficient. This should be secured at the planning stage.

H All disabled persons parking bays associated with residential development must:

1) be for residents' use only (whether M4(2) or M4(3) dwellings)

2) not be allocated to specific dwellings, unless provided within the curtilage of the dwelling

3) be funded by the payment of a commuted sum by the applicant, if provided on-street (this includes a requirement to fund provision of electric vehicle charging infrastructure)

4) count towards the maximum parking provision for the development

5) be designed in accordance with the design guidance in BS8300vol.1

6) be located to minimise the distance between disabled persons parking bays and the dwelling or the relevant block entrance or lift core, and the route should be preferably level or where this is not possible, should be gently sloping (1:60-1:20) on a suitable firm ground surface.”

2.17 The maximum residential parking standards are contained in Table 2.2.

Location	Bedrooms	Maximum Parking Provision
PTALs 5 – 6	ALL	Car-free
Outer London PTAL 4	1,2,3+	0.5-0.75 spaces per dwelling
Outer London PTAL 2 – 3	1-2	0.75 spaces per dwelling
Outer London PTAL 2 – 3	3+	1 space per dwelling
Outer London PTAL 0 – 1	1,2,3+	1.5 spaces per dwelling

Table 2.2 – Residential Car Parking Standards

Haringey Development Management Plan

2.18 The Haringey Unitary Development Management Plan published 2017 sets out the borough’s policies for new developments and how the policies are expected to be applied.

Policy DM2 states that:

- a) *Developments should be used safely, easily and with dignity by all;*
- b) *Are designed so that the layout improves people’s access to social and community infrastructure, including local shops and public transport;*
- c) *Protect, improve and create, where appropriate, safe and accessible pedestrian and cycling routes and should not impede pedestrian and cycling permeability;*

2.19 Policy DM31 states that:

- A) *The Council will require that developments with high trip generating characteristics locate where public transport accessibility is high and car parking is minimised to mitigate generated car travel.*
- B) *The Council will support the protection, improvement and creation of pedestrian and cycle routes in the Borough to encourage walking and cycling both as a means of transport and as a recreational activity. The Council will also encourage improved links between pedestrian and cycle routes and public transport facilities, particularly at transport hubs.*
- C) *The Council will require the submission of a Travel Plan and a Transport Assessment/ Statement in support of development proposals in accordance with the Transport for London thresholds.*

2.20 Policy DM32 states that:

- A) *Development proposals will be assessed against the car parking and cycle parking standards set out in the London Plan.*
- B) *The Council will strongly encourage contributions to car club schemes or the provision of car club bays as an alternative to on-site car parking.*
- C) *The Council will support proposals for new development with limited or no on-site parking where:*
 - 1) *There are alternative and accessible means of transport available;*
 - 2) *Public transport accessibility is at least 4 as defined in the Public Transport Accessibility Index;*

- 3) A Controlled Parking Zone (CPZ) exists or will be provided prior to the occupation of the development;*
- 4) Parking is provided for disabled people; and*
- 5) Parking is designated for occupiers of developments specified as car capped.*

2.21 Policy DM37 relates to employment uses within the borough and states developments will be supported if:

A) Wherever possible, should be designed to allow for future flexibility of use including subdivision and/or amalgamation to provide for a range of business types and sizes, including small businesses;

B) Makes adequate provision of space for on-site servicing and waiting goods vehicles;

C) Improves and enhances the quality of the environment of the site and business area; and

D) Makes a demonstrable improvement in the use of the site for employment purposes, having regard to: i The quality and type of employment floorspace provided; ii The quality and density of jobs to be accommodated on-site; and The proposal's contribution to the achievement of economic objectives and outcomes set out in the Local Plan and the Council's other key plans and strategies.

3.0 Baseline Conditions

Overview

- 3.1 The following section provides a summary of the results of this review and refers to the location of the site along with the accessibility of the site by different modes of transport.

Site Details

- 3.2 The site is located 850 metres south of Tottenham, within the administrative boundary of the London Borough of Haringey. The local centre of Bruce Grove is less than 500 metres southeast of the site. The site fronts the A10 Bruce Grove and benefits from close proximity to the A406 North Circular Road, as well as a number of bus stops and railway stations. The site is shown in relation to strategic transport links in Figure 3.1 below.




Figure 3.1 Strategic Site Location Plan

- 3.3 The site is situated to the east of the A10 Bruce Grove and accessed via Edmansons Close (private road). The A10 links the site to the A406 North Circular Road northbound and provides access to Stamford Hill, Dalston and Hackney southbound. Beyond the A406 North Circular Road the A10 provides access to the M25 providing a link to the wider road network. The site in relation to its local area is illustrated in Figure 3.2 below.




Figure 3.2 Local Site Location Plan

- 3.4 The surrounding area can be characterised as mainly residential in nature, with a range of local retail facilities surrounding Bruce Grove railway station. The A10 Bruce Grove is part of the Transport for London Strategic Road Network (TLRN) and is subject to a 30 miles per hour speed limit. Due to its TLRN status, Bruce Grove is a "Red Route" and restricts parking between 07:00 and 19:00 hour Monday to Saturday along the site frontage. The surrounding road network is located within LBH's Bruce Grove North Controlled Parking Zone (CPZ), which restricts parking to permit holders only within the following time periods:

- ▶ Monday to Saturday 08:00 – 18:30 hours;
- ▶ Event days Monday to Friday 08:00 – 20:30 hours;
- ▶ Event days Saturday and Sunday 08:00 – 20:00 hours; and
- ▶ Public holidays 12:00 – 20:00 hours.

Existing Site

- 3.5 The site currently accommodates 61 small units, which are incredibly close together and in poor condition. The site is owned and maintained by the Drapers Almshouse Charity/ The Drapers Company.
- 3.6 The site currently accommodates 61 units, including 48 studios, 1 x 1 bed and 12 x 2 bed. Facilities for residents include a Community Hall for social activities within the old Chapel and a prefab laundry building. A guest room for the use of family and friends of residents is also available.
- 3.7 Access to the site is achieved via Edmansons Close, a private road, which has an entry only access to the north of the site and an exit only access to the south of the site. Edmansons Close is subject to a 10 miles per hour speed limit, with parking unrestricted throughout.

Availability of On-Street Parking

- 3.8 In order to determine the current parking demand on the roads in the vicinity of the site, parking beat surveys were undertaken on Thursday 9th July at 02.30am and Friday 10th July at 02.30am, when residential parking demand is at its highest. The surveys were undertaken using the nationally recognised Lambeth parking stress methodology. The methodology requires an area of a 200m radius from the site to be surveyed, this generally equates to a 2-minute walk from the site). In the case of Edmansons Close, this covers the following roads:
- ▶ Edmansons Close;
 - ▶ Elmhurst Road;
 - ▶ Whitley Road;
 - ▶ Radley Road;
 - ▶ Broadwater Road;
 - ▶ Linley Road;
 - ▶ Bruce Grove;
 - ▶ Lordship Lane;
 - ▶ Church Lane;
 - ▶ Hartham Road;
 - ▶ Newlyn Road and,
 - ▶ Elsdon Road.
- 3.9 A plan of the exact roads covered by the survey is included at **Appendix A**. While it should be noted that the survey was undertaken while Covid 19 restrictions were in place, it is considered the surveys are robust, as due to restrictions on travel a higher proportion of residents were remaining at home.
- 3.10 The number of existing on-street parking spaces are calculated through on-street observations and site measurement as part of the analysis. As defined by the Lambeth Methodology, it is assumed a vehicle takes up an average of 5 metres of kerb space. Therefore, where bays are not physically marked out, stretches of kerb are divided into 5 metre increments. Physical bays have been divided into 5 metre intervals. Any locations with a kerb line shorter than 5 meters or along a vehicle crossover have been eliminated from the available kerb space, in accordance with the Lambeth Methodology.
- 3.11 The survey compares the number of cars parked overnight with the number of available parking spaces in the survey area. A percentage is calculated from these values to determine the levels of parking demand in the survey area. It should be noted that if the parking demand in an area exceeds 85% capacity, the network is considered to be under 'parking stress'.
- 3.12 The full parking results are included within **Appendix B** and summarised in Tables 3.1 and 3.2 below.

Location	Maximum Number of Spaces Available	Number of Vehicles Parked	% Parking Stress
Edmansons Close	35	6	17%
Elmhurst Road	50	36	72%
Whitley Road	43	26	60%
Radley Road	49	39	80%
Broadwater Road	70	52	74%
Linley Road	48	36	75%
Bruce Grove	50	0	0%
Lordship Lane	34	3	9%
Church Lane	14	8	57%
Hartham Road	25	18	72%
Newlyn Road	9	7	78%
Elsdon Road	70	38	54%
Total	497	269	54%

Table 3.1 Parking Stress Survey Results Thursday 9th July 2020

Location	Maximum Number of Spaces Available	Number of Vehicles Parked	% Parking Stress
Edmansons Close	35	6	17%
Elmhurst Road	50	37	74%
Whitley Road	43	27	63%
Radley Road	49	37	76%
Broadwater Road	70	50	71%
Linley Road	48	37	77%
Bruce Grove	50	1	2%
Lordship Lane	34	4	12%
Church Lane	14	8	57%
Hartham Road	25	20	80%
Newlyn Road	9	6	67%
Elsdon Road	70	38	54%
Total	497	271	55%

Table 3.2 – Parking Stress Survey, Friday 10th July 2020

- 3.13 Table 3.2 shows that for the full study area on Thursday 9th July 2020 there were 228 on-street parking spaces available out of a total provision of 497 spaces, equating to a parking stress of 54%, while Table 3.1 shows that on Friday 10th July 2020 there were 226 parking spaces available, equating to a parking stress of 55%.
- 3.14 During both survey periods, the on-street parking levels were considerably below the 85% threshold at which a highway network is considered to be under parking 'stress'.

Accessibility by Active Modes

Accessibility on Foot

- 3.15 The site is easily accessible on foot via the adjacent footways on all local roads. Continuous lit footways provide access from the site to Bruce Grove centre to the south, as well as Tottenham to the north. A pedestrian refuge island is provided approximately 50 metres north of the northern access into

Edmansons Close, whilst a signalised pedestrian crossing is provided approximately 120 metres south of the southern access.

Accessibility by Cycle

- 3.16 Government guidance in respect of cycling proposes that people are prepared to cycle up to five kilometres to access local amenities or travel to work. Within five kilometres cyclists can reach Tottenham, Wood Green, Harringay, Stoke Newington, Walthamstow and Southgate.
- 3.17 TfL cycling guide 4 provides information pertaining to safe cycling in the vicinity of the site, including signed cycle paths, advised quieter routes, greenways and station protocols on cycle parking. There are numerous networks in the area supported by either route marked for cyclists or quiet roads recommended by cyclists. Cycle Superhighway 1 passes close to the site through Bruce Castle Park and south via Broadwater Road to the west of the site. Cycle Superhighway 1 runs between Tottenham to the north of the site and Stoke Newington to the south of the site. Additionally, Bruce Grove is provisioned with cycle lanes on either side of the carriageway, providing a safe route towards local amenities and Bruce Grove railway station.
- 3.18 The nearest bus stops are located adjacent to the northern entrance to the site, illustrated of Figure 3.2 above. Additional stops are located along the A109 Lordship Lane approximately 400 metres north of the site. A summary of the destinations served, and the frequency of the local bus services is provided below in Table 3.3.

Public Transport Connectivity

- 3.19 Public Transport Accessibility Levels (PTALs) are a measure of the accessibility of a site to the public transport network, considering walk access time and service availability. This method is a way of measuring the density of the public transport network at a particular point.
- 3.20 Walk times are calculated from the specified point of interest to all public transport access points including bus stops and stations within pre-defined catchments. The PTAL incorporates a measure of service frequency to calculate an average wait time based on frequency of service at each public transport access point. A reliability factor is added, and the total access time is calculated. A measure known as an Equivalent Doorstep Frequency (EDF) is then derived for each point. These are summed for all routes within the catchment and the PTALs for the different modes are then added together to give a single value. The PTAL is categorised in nine levels, 1a to 6b where 6b represents a high level of accessibility and 1a, a low level of accessibility.
- 3.21 The site is classified as a PTAL 5 location, which reflects its 'very good' location in relation to public transport. The full PTAL output is included at **Appendix C**.

Accessibility by Bus

- 3.22 The nearest bus stops are located adjacent to the northern entrance to the site, illustrated of Figure 3.2 above. Additional stops are located along the A109 Lordship Lane approximately 400 metres north of the site. A summary of the destinations served, and the frequency of the local bus services is provided below in Table 3.3.

Service Number	Route	Approximate Frequency		
		AM Peak	PM Peak	Sat Daytime
Bruce Grove				
123	Wood Green – Turnpike Lane – Bruce Grove – Tottenham Hale – Walthamstow – South Woodford – Gants Hill – Cranbrook - Ilford	Every 7 – 11 minutes	Every 7 – 11 minutes	Every 9 – 12 minutes
243	Wood Green – Bruce Grove – South Tottenham – Stamford Hill – Stoke Newington – West Hackney – Dalston – Haggerston – Hackney – St Lukes – Farringdon – Holborn – Waterloo	Every 5 – 8 minutes	Every 7 – 10 minutes	Every 8 – 12 minutes
Lordship Lane				
318	North Middlesex University Hospital – Tottenham – Bruce Grove – South Tottenham – Rookwood Road	Every 10-13 minutes	Every 10-13 minutes	Every 11-12 minutes

Table 3.3: Local Bus Services

Accessibility by Rail

- 3.23 The closest railway station to the site is Bruce Grove, located approximately 600 metres south of the site, which equates to an eight-minute walk or a three-minute cycle. Bruce Grove is on the TfL-operated Overground Line. Table 3.2 summarises the services available from Bruce Grove railway station.

Service	Destinations Served	Weekday AM Peak	Weekday PM Peak	Saturday Daytime Frequency
London Liverpool Street	Bruce Grove – Seven Sisters – Stamford Hill – Stoke Newington – Rectory Road – London Fields – Cambridge Heath – Bethnal Green – Liverpool Street	Every 15 minutes	Every 15 minutes	Every hour
Enfield Town	Brice Grove – White Hart Lane – Silver Street – Edmonton Green – Bush Hill Park – Enfield Town	Every 16-20 minutes	Every 15 minutes	Every hour
Cheshunt	Bruce Grove – White Hart Lane – Silver Street – Edmonton Green – Southbury – Turkey Street – Theobalds Grove – Cheshunt	Every 20-40 minutes	Every 30 minutes	Every hour

Table 2.4: Local Rail Services

Car Club

- 3.24 Zipcar is the main car club operator within the Bruce Grove area, with three vehicles located within a 15-minute walk from the site, along Marden Road to the southwest of the site and Mafeking Road to the southeast of the site.

Local Amenities

- 3.25 The site is located circa 500 metres northeast of the local centre of Bruce Grove and thus has access to numerous shops, restaurants and leisure facilities. Amenities include convenience stores, a supermarket and a post office. There are three primary schools within approximately 750 metres from the site, which are Risley Avenue Primary School, Asunnah Primary School and Bruce Grove Primary School. In addition, Bruce Castle Park is located approximately 170 metres north of the site and provides a large recreational area.

4.0 Proposed Development

Overview

- 4.1 The following text provides details of how the site is to be developed, along with details of the site access, servicing and parking strategy.
- 4.2 The site is seeking planning permission for the amalgamation and extension of the existing dwellings on site to provide larger family homes. The proposals also include the demolition of the laundry building and subsequent construction of the following dwellings:
- ▶ 8 one-bed houses (within existing building);
 - ▶ 12 two-bed houses (within existing building);
 - ▶ 6 three-bed houses (within existing building);
 - ▶ 1 two-bed house (within existing gatehouse);
 - ▶ a new 3-bed house (within new Almshouse);
 - ▶ 4 two-bed apartments (within new corner pavilions);
 - ▶ 7 studio apartments (within new apartment building);
 - ▶ 9 one-bed apartments (within new apartment building).
- 4.3 This will bring the total number of dwellings on the site to 48.
- 4.4 The proposed site layout plan is demonstrated below in Figure 4.1.




Figure 4.1: Proposed Site Layout

Access Arrangements

- 4.5 Vehicular access to the site will remain from Bruce Grove via the entry/exit access points into Edmansons Close. Edmansons Close will continue to operate as a one-way system consistent with the existing

arrangement. The internal carriageway, at present, varies between 3.3 metres and 4.6 metres. This width is substandard for large servicing and refuse vehicles to modern standards and thus needs to be widened (see below).

- 4.6 Pedestrian access to the site will also remain as existing via Bruce Grove, with a footway provided along the eastern side of Edmansons Close, alongside the dwellings. A path will also be located between the southernmost almshouses and the new apartment building.

Car Parking Arrangements

- 4.7 Parking along Edmansons Close is unrestricted which results in visitors and residents parking informally within the site. It is estimated that approximately 40 car parking spaces are available on Edmansons Close. Given the existing age of residents on the site, the majority of existing residents do not own a car. Therefore, there are currently very few cars parked on the site, mainly associated with visitors.

Proposed Car Parking Provision

- 4.8 The proposed level of car parking for the scheme is based on 4 main considerations, namely;
- ▶ A significant reduction in existing car parking level reflecting the high PTAL of the site to car free except for blue badge parking;
 - ▶ The financial viability of the scheme; and,
 - ▶ The need to retain the setting of the historic buildings.
- 4.9 It has thus been agreed with LBH that only 5 blue badge spaces will be provided on site.
- 4.10 The proposed car parking and cycle parking arrangements for the site are shown on Drawing 1906030-TK104A given at **Appendix D**. The parking has been arranged to minimise its impact on the historical buildings and ensure that refuse vehicles will be able to circulate around the site without encroaching onto the lawn areas. These spaces will be provided with electric vehicle charging infrastructure.
- 4.11 It is proposed that the route around the lawns will be a shared surface with to an agreed finish.

Cycle Parking Provision

- 4.12 LBH also refer to the London Plan in regard to cycle parking. The London Plan and current London Plan standards for residential cycle parking are outlined in Table 4.2 below.

Number of beds	Current London Plan
Studio Flat	1 space
1-bed unit	1.5 spaces
2+ bed units	2 spaces

Table 4.2: London Plan Residential Cycle Parking Standards

- 4.13 Based on a total of 7 x studios, 17 x 1-bed units and 24 x 2+ bed units, a total of 81 residential cycle parking spaces and 8 visitor spaces should be provided, in accordance with the London Plan. Given the proposed houses have gardens, it is expected that cycle parking can be accommodated within the curtilage of each dwelling. Whilst the flats will be provided within sheltered secure cycle stores.

Delivery Servicing Plan and Emergency Access tracks will need updating

- 4.14 At present, refuse bins are left out and collected from the A10 Bruce Grove.

- 4.15 It is proposed that refuse vehicle will circulate around the site. Drawing 1906030-TK104A at **Appendix E** demonstrates a large refuse vehicle entering the site at the northern entrance and exiting the site at the southern exit without conflicting with the proposed on-site parking spaces.
- 4.16 Bin stores will be provided for the flats/houses either side of the central area, west of the proposed apartment building and east of the new Almshouse building. The bin stores are within appropriate walk distance from each dwelling located less than 25m from Edmansons Close, minimising the distance bin collection personnel will be required to walk when collecting waste.
- 4.17 Other servicing activity for both the community and residential uses will, similarly, circulate around the site and will have the option of travelling along the existing service road before exiting the site to the east of the main exit at the existing position. Drawing 1906030-TK12A shows a Delivery Van utilising the site as shown in **Appendix F**.
- 4.18 Drawing 1906030-TK11B attached at **Appendix G** demonstrates a fire appliance entering the site at the northern entrance and exiting the site at the southern exit. The new area of 2-bed flats falls slightly outside the 45 metres required from Edmansons Close for a fire appliance. As such, either dry risers with connection pipes will be installed in the ground at 18 metre maximum distance to serve the fire appliance or, alternatively, a couple of fire hydrants will be installed to both sides of building. The fire appliance is able to get within 45 metres of all of the other dwellings.

5.0 Impacts of Development Proposals

- 5.1 This section sets out the impact of the development proposals on the highway network. The assessment focuses on the weekday morning and evening hours of 08:00-09:00 and 17:00-18:00, which constitutes the key trip generation periods for residential development. Consideration is also given to daily trips.

Residential Use

Existing Use

- 5.2 To calculate the trip attraction potential of the existing flats, an assessment utilising the TRICS database has been undertaken. The TRICS category '03 Residential: D – Affordable/Local Authority Flats' has been used, with the following criteria:
- ▶ Sites located in England, including Greater London;
 - ▶ Sites with up to 100 dwellings; and
 - ▶ Sites in areas classed as suburban area.
- 5.3 A summary of the peak hour total person and vehicular trip rates for the existing 61 flats are provided in Table 5.1 below and the full TRICS output included at [Appendix H](#).

Mode of Travel	Weekday AM Peak		Weekday PM Peak		Weekday Daily Movements	
	Arr	Dep	Arr	Dep	Arr	Dep
Total Person Trip Rates	0.107	0.544	0.284	0.195	2.923	2.962
Total Person Trips	7	33	17	12	178	181
Vehicular Trip Rates	0.051	0.121	0.088	0.056	0.800	0.814
Vehicular Trips	3	7	5	3	49	50

Table 5.1: Existing Residential Use– Trip Rates and Resultant Trips

- 5.4 Table 5.1 indicates that the existing flats could generate 40 total person trip during the weekday morning of which 10 could be vehicular. In the evening peak, the existing site could generate 29 total person trips, of which eight could be vehicular. Over an average weekday, the existing flats could generate 359 two-way total person trips, of which 99 could be vehicular.

Proposed Use

- 5.5 Given only 5 blue badge spaces are to be provided on the site, the trip generation of the site on a peak hour and daily basis will be minimal. We estimate that there may be 4, 2- way movements in the morning peak and 12, 2-way movements throughout the day consisting of delivery and blue badge holders.
- 5.6 A summary of the peak hour total person and vehicular trip rates are provided in Table 5.2 below and the full TRICS output included at [Appendix I](#).

Mode of Travel	Weekday AM Peak		Weekday PM Peak		Weekday Daily Movements	
	Arr	Dep	Arr	Dep	Arr	Dep
Total Person Trip Rates	0.118	0.485	0.471	0.250	3.076	3.221
Total Person Trips	6	23	23	12	148	154
Vehicular Trips	2	2	2	2	12	12

Table 5.2: Proposed Residential Use – Trip Rates and Associated Trips

- 5.7 Table 5.2 indicates that the proposed dwellings could generate 302 two-way total person trips, of which 121 could be vehicular.

Community Use

- 5.8 The chapel is a private property and will remain so for the use of residents. It will, thus, not lead to any material traffic flow or parking requirement.

Net Impact

- 5.9 Table 5.4 below summarises the net impact of the proposal in terms of person trips, whilst Table 5.5 summarises the impact regarding vehicle trips.

Mode of Travel	Weekday AM Peak		Weekday PM Peak		Weekday Daily Movements	
	Arr	Dep	Arr	Dep	Arr	Dep
Existing Use Total Person Trips	7	33	17	12	178	181
Proposed Total Person Trips	10	41	31	14	199	208
Net Impact	+3	+8	+14	+2	+21	+27

Table 5.4: Net Impact of Proposed Development in terms of Total Person Trips

Mode of Travel	Weekday AM Peak		Weekday PM Peak		Weekday Daily Movements	
	Arr	Dep	Arr	Dep	Arr	Dep
Existing Use Total Vehicular Trips	3	7	5	3	49	50
Proposed Total Vehicular Trips	2	2	2	2	12	12
Net Impact	-1	-5	-3	-1	-37	-38

Table 5.5: Net Impact of Proposed Development in terms of Vehicular Trips

- 5.10 Table 5.5 demonstrates that the proposals will lead to a significant reduction in the number of vehicular trips to the site on a peak hour and daily basis. This will be a significant benefit in terms of the amenity of the residents and the historical context of the site.

6.0 Framework Travel Plan

- 6.1 This section of the report sets out the Framework Travel Plan associated with development at the site. The Framework Travel Plan is an important document in increasing the use of sustainable transport modes for journeys generated by the site. This section outlines local policy guidance associated with travel planning and the various sustainable modes of travel which can be used to access the site.

Policy Guidance

The London Plan

- 6.2 The London Plan states that Travel Plans can be used to mitigate the transport related impacts of development, and should be written and used in accordance with Transport for London guidance. TfL has published four documents relating to Travel Plans as follows:

- ▶ The benefits of a travel plan;
- ▶ What a travel plan should contain;
- ▶ How we secure and enforce travel plan targets;
- ▶ How we monitor the progress of travel plans.

- 6.3 'What a Travel Plan should contain' states that

"The overarching purpose of a travel plan should be to encourage behaviour change which will lead to the use of more sustainable modes of travel and reduce overall travel to and from the site."

- 6.4 TfL considers Travel Plans critical in mitigating the impact of new developments.

Objectives

- 6.5 The Travel Plan objectives listed below have been derived from the policies and guidance set out above:

- ▶ Promote healthy/active travel;
i.e. walking, running and cycling
- ▶ Promote more efficient forms of car travel;
i.e. Sharing resources, such as car sharing and use of car club vehicles.
- ▶ Encourage the use of sustainable travel modes;
i.e. public transport or school provided bus services
- ▶ Raise staff/students'/parents' awareness of opportunities to adopt active/sustainable travel
i.e. Through information provision

Sustainable Modes of Travel

Access on Foot and by Cycle

- 6.6 The site is well located for access on foot and by cycle from the local area. Details on the walking and cycling environment in the vicinity of the site are given in '**Section 3 – Baseline Conditions**' of this report.
- 6.7 The site will be provided with 81 residential cycle parking spaces, with an additional 8 for visitors. This is elaborated upon in 'Section 4 – Development Proposals'. The availability of cycle storage on the site should encourage travel by sustainable modes.

Access by Bus

- 6.8 The closest bus stops to the site are located adjacent to the northern site access on Bruce Grove, these stops are provided with sheltered seating and serve the 123 and 243 bus services. The details of these services are contained in Table 3.3.
- 6.9 There are also stops located on 400m north of the site on Lordship Lane, these stops serve bus service 318. The details of this service are contained in Table 3.3.
- 6.10 Buses in the vicinity of the site enable travel to areas such as Walthamstow, Hackney and Waterloo.

Accessibility by Train

- 6.11 Bruce Grove station is located 600m south of the site. This equates to an 8 minute walk or 3 minute cycle.
- 6.12 Bruce Grove is situated on the Overground Line and connects Liverpool Street Station with Chestnut and Enfield. Details of the services available from the station are elaborated upon in Table 3.4.

Action Plan

- 6.13 As the site is car free apart from blue badge parking, travel by residents and visitors to the site will be sustainable modes. The purpose of the Framework Travel Plan is thus to ensure that residents have the facilities and information to undertake sustainable travel. The components will thus include:
- ▶ Suitable on site cycle storage provided on site in accordance with standards;
 - ▶ Provision of 3 year car club membership (Zipcar);
 - ▶ A notice board, displaying the details of local sustainable and active travel options will be provided; and,
 - ▶ Residents will not be able to access permits for on-street parking.

7.0 Summary and Conclusion


- 7.1 This Transport Statement has been prepared on behalf of The Draper's Almshouse Charity to accompany a planning application for the redevelopment of the charity owned dwellings surrounding Edmansons Close, Tottenham.
- 7.2 The site is seeking planning permission to include the Demolition of existing laundry building and 1970s infill building; alterations and extensions to 44 existing almshouses to create 8 x 1 bed, 12 x 2 bed and 6 x 3 bed units; alterations to existing Gatehouse to provide 1 x 2 bed unit; construction of 1 x new build 3 bed almshouse to replace 1970s infill building; construction of a new apartment building comprising 7 x studio units and 9 x 1 bed units; construction of 4 x new build 2 bed units within two new pavilions (2 units in each pavilion, 4 units in total); with landscaping; improvements to access; provision of five disabled car parking spaces; and ancillary development thereto. In summary, this TS has identified the following:
- ▶ Bus services are accessible within close proximity of the site;
 - ▶ Regular services are available from Bruce Grove railway station;
 - ▶ The site benefits from good access on foot and by cycle to Bruce Grove centre. Indeed, there are many local amenities within close walk and cycle distance of the site meaning that residents would have less need to own a car;
 - ▶ Vehicular and pedestrian access to the site would be achieved from Bruce Grove;
 - ▶ Cycle parking will be provided on-site in conformity with London Plan standards;
 - ▶ The development will be car free apart from 5 blue badge spaces reflecting the very good PTAL;
 - ▶ The proposals will lead to a significant reduction in the number of vehicular trips to the site on a peak hour and daily basis. This will be a significant benefit in terms of the amenity of the residents and the historical context of the site.
 - ▶ The proposals could result in no material change in traffic generation on the surrounding road network in the weekday peak hour and over a typical weekday.
 - ▶ As the site is car free apart from blue badge parking, travel by residents and visitors to the site will be sustainable modes. The purpose of the Framework Travel Plan is thus to ensure that residents have the facilities and information to undertake sustainable travel.

Conclusion

- 7.3 In view of the above, the proposed development is considered to be acceptable in transport terms and meets with local and national policy criteria. The assessment work undertaken has shown that there would not be any demonstratable harm arising from the proposed scheme and it will not cause any severe impacts. Therefore, there are no traffic and transport related reasons why the development should not be granted planning consent.

Appendix A

Plan of Parking Survey Locations



Appendix B

Full Parking Survey Results

K&M TRAFFIC SURVEYS


DATE : 9th AND 10th JULY 2020

DAY : THURSDAY & FRIDAY

LOCATION : EDMANSO		FRIDAY 10th JULY 2020	
		TIME : 0230	
ROAD NAME	PARKED	OBSERVED SPACES	%RESTRICTION STRESS
ELMHURST RD	1	1	50.0%
	2	0	100.0%
	16	2	88.9%
	1	0	100.0%
WHITLEY RD	5	0	100.0%
	12	5	70.6%
	7	1	87.5%
RADLEY RD	10	1	90.9%
BROADWATER RD			
	13	3	81.3%
	0	1	0.0%
	1	4	20.0%
	2	0	100.0%
	1	0	100.0%
	14	2	87.5%
LINLEY RD	1	0	100.0%
	17	2	89.5%
	20	0	100.0%
BROADWATER RD	7	0	100.0%
	1	0	100.0%
RADLEY RD	18	1	94.7%
	1	1	50.0%
	1	0	100.0%
	10	1	90.9%
WHITLEY RD			
ELMHURST RD	10	2	83.3%
	14	3	82.4%
	1	0	100.0%
	2	0	100.0%
BRUCE GROVE			
	0	7	0.0%
	1	10	9.1%
LORDSHIP LN			
CHURCH LN	0	3	0.0%
	7	2	77.8%
	1		
LORDSHIP LN			
	4	20	16.7%
ELSDON RD	16	12	57.1%
HARTHAM RD	1	0	100.0%
	7	0	100.0%
NEWLYN RD	4	2	66.7%
	2	1	66.7%
HARTHAM RD	10	1	90.9%
	1	0	100.0%
	1		
	1	1	50.0%
ELSDON RD	19	7	73.1%
	2	0	100.0%
LORDSHIP LN			
BRUCE GROVE	0	8	0.0%
	0	1	0.0%
	0	19	0.0%
	0	11	0.0%
	0	1	0.0%
EDMANSONS CLOSE	6	32	15.8%

Appendix C

Full PTAL Output



PTAL output for Base Year 5

1 Linley Rd, London N17 6RP, UK
Easting: 533511, Northing: 190535


Grid Cell: 134421

Report generated: 30/03/2022

Calculation Parameters

Day of Week	M-F
Time Period	AM Peak
Walk Speed	4.8 kph
Bus Node Max. Walk Access Time (mins)	8
Bus Reliability Factor	2.0
LU Station Max. Walk Access Time (mins)	12
LU Reliability Factor	0.75
National Rail Station Max. Walk Access Time (mins)	12
National Rail Reliability Factor	0.75

Map key - PTAL



Map layers

 PTAL (cell size: 100m)


Calculation data

Mode	Stop	Route	Distance (metres)	Frequency(vph)	Walk Time (mins)	SWT (mins)	TAT (mins)	EDF	Weight	AI
Bus	BRUCE GROVE LORDSHIP LN	243	120.56	11	1.51	4.73	6.23	4.81	1	4.81
Bus	BRUCE GROVE LORDSHIP LN	123	120.56	5.5	1.51	7.45	8.96	3.35	0.5	1.67
Bus	LORDSHIP LN BRUCE GROVE	318	232.19	4	2.9	9.5	12.4	2.42	0.5	1.21
Bus	RADLEY ROAD BRUCE GROVE	W4	170.12	6	2.13	7	9.13	3.29	0.5	1.64
Bus	Tottenham Scotland Green	349	590.29	7.5	7.38	6	13.38	2.24	0.5	1.12
Bus	Tottenham Scotland Green	259	590.29	8	7.38	5.75	13.13	2.29	0.5	1.14
Bus	Tottenham Scotland Green	279	590.29	10.5	7.38	4.86	12.24	2.45	0.5	1.23
Bus	Tottenham Scotland Green	476	590.29	7.5	7.38	6	13.38	2.24	0.5	1.12
Bus	Tottenham Scotland Green	149	590.29	12	7.38	4.5	11.88	2.53	0.5	1.26
Bus	Tottenham Scotland Green	341	590.29	6	7.38	7	14.38	2.09	0.5	1.04
Rail	Bruce Grove	'CHESHNT-LIVST 2D03'	599.74	2	7.5	15.75	23.25	1.29	0.5	0.65
Rail	Bruce Grove	'ENFLDTN-LIVST 2U05'	599.74	2	7.5	15.75	23.25	1.29	0.5	0.65
Rail	Bruce Grove	'ENFLDTN-LIVST 2U07'	599.74	2	7.5	15.75	23.25	1.29	0.5	0.65
Rail	Bruce Grove	'LIVST-ENFLDTN 2U10'	599.74	3.33	7.5	9.76	17.26	1.74	1	1.74
Rail	Bruce Grove	'LIVST-CHESHNT 2D10'	599.74	0.33	7.5	91.66	99.16	0.3	0.5	0.15
Rail	Bruce Grove	'LIVST-CHESHNT 2D12'	599.74	1	7.5	30.75	38.25	0.78	0.5	0.39
Rail	Bruce Grove	'LIVST-CHESHNT 2D18'	599.74	0.67	7.5	45.53	53.02	0.57	0.5	0.28
Total Grid Cell AI:										20.77


Appendix D

Car and Cycle Parking Arrangement

NOTE: THIS DRAWING MUST NOT BE SCALED.
THE CONTRACTOR IS TO CHECK ALL DIMENSIONS ON SITE



GROUND FLOOR - 1:500 @ A2



PROJECT
Edmansons Close
Bruce Grove
Haringey

CLIENT
The Drapers'


DRAWING ORIGINATOR
d+b studios
85 HOLMESDALE ROAD
TEDDINGTON TW11 9LQ
+44 (0) 7810 481 900
www.dplusbstudios.com

DRAWING TITLE
Ground Floor
Proposed


JOB NO db-001		SCALE 1:500 @ A2	DRAWN BY PD		ISSUE DATE SEPT 2022		REVISION 02
DRAWING STATUS Planning			CHECKED BY PD		PAPER SIZE A2		
PROJECT CODE	COMPANY CODE	DOC. CODE	PACKAGE NO CODE	LEVEL	ZONE / SUBZONE	SUB ZONE	DRAWING NUMBER
EC	d+b	GA	XXX	00	XX	XXX	032

Appendix E


Refuse Vehicle Swept Path Analysis



C:\Users\glester\Motion\StaffSite - Dredma 1906030\Drawings\1906030-TK1041, TK105G.dwg



- Notes
1. All levels and dimensions to be checked on site before any work commences. All dimensions in metres unless stated otherwise.
 2. This drawing is based on topographical survey information and Motion cannot guarantee the accuracy of the data provided.
 3. This drawing is based on OS mapping and Motion cannot guarantee the accuracy of the data.
 4. Motion accepts no liability for any vehicle specification errors or inaccuracies within the vehicle tracking software used / or it's vehicle libraries. The vehicles speeds used for the analysis are as follows: forward 6mph / reversing 6mph.



 Protected surface -
grasscrete or similar TBC

K	Updated	GL	AW	AW	02/09/2025
J	Updated Tracking	AG	AW	AW	17/07/2025
I	Updated Arrangements	EU	AW	AW	11/07/2025
H	Updated Arrangements	EU	AW	AW	11/07/2025
G	Updated Arrangements	EU	AW	AW	10/07/2025
F	Updated Arrangements	WMC	AW	AW	10/07/2025
E	Updated Arrangements	WMC	AW	AW	10/07/2025
D	Updated Arrangements	WMC	AW	AW	09/07/2025
C	Updated Arrangements	WMC	AW	AW	02/07/2025
B	Updated Arrangements	GL	AW	AW	07/01/2025
A	Updated Arrangements	GL	AW	AW	16/09/2024
-	First Issue	GL	AW	AW	27/08/2024
Rev.	Description	Drm	Chk	App	Date

Drawing Status:

FOR PLANNING
NOT FOR CONSTRUCTION



Client:
The Draper's Company

Project:
Edmanson's Close, Tottenham

Title:
**Swept Path Analysis
Refuse Vehicle**

Scale: 1:1000 (@ A3)

Drawing:
1906030-TK104

Revision:
K

Appendix F

Delivery Van Swept Path Analysis



Lordship Lane

Linley Road

Bruce Grove

Radley Road


Elsden Road

Hartham Road



Notes

1. All levels and dimensions to be checked on site before any work commences. All dimensions in metres unless stated otherwise.
2. This drawing is based on topographical survey information and Motion cannot guarantee the accuracy of the data provided.
3. This drawing is based on OS mapping and Motion cannot guarantee the accuracy of the data.
4. Motion accepts no liability for any vehicle specification errors or inaccuracies within the vehicle tracking software used / or it's vehicle libraries. The vehicles speeds used for the analysis are as follows: forward 6mph / reversing 6mph.



Delivery Van

Width	: 2.10
Track	: 2.10
Lock to Lock Time	: 6.0
Steering Angle	: 46.2

 Protected surface -
grasscrete or similar TBC

C	Updated Arrangements	AG	AW	AW	17/07/2025
B	Updated Arrangements	AG	EU	AW	15/07/2025
A	First Issue	GL	AW	AW	27/08/2024
Rev.	Description	Drm	Chk	App	Date

Drawing Status:

FOR PLANNING
NOT FOR CONSTRUCTION



Guildford - Reading - London
www.motion.co.uk

Client:
The Draper's Company

Project:
Edmanson's Close, Tottenham

Title:
**Swept Path Analysis
Delivery Van**

Scale: 1:1000 (@ A3)

Drawing: **1906030-TK12** Revision: **C**

Appendix G

Swept Path Analysis Fire Appliance



Lordship Lane

Linley Road

Bruce Grove

Radley Road


Elsden Road

Hartham Road



Notes

1. All levels and dimensions to be checked on site before any work commences. All dimensions in metres unless stated otherwise.
2. This drawing is based on topographical survey information and Motion cannot guarantee the accuracy of the data provided.
3. This drawing is based on OS mapping and Motion cannot guarantee the accuracy of the data.
4. Motion accepts no liability for any vehicle specification errors or inaccuracies within the vehicle tracking software used / or it's vehicle libraries. The vehicles speeds used for the analysis are as follows: forward 6mph / reversing 6mph.



Mercedes Atego 1325F FRU
meters
Width : 2.30
Track : 2.30
Lock to Lock Time : 6.0
Steering Angle : 36.3

 Protected surface -
grasscrete or similar TBC

D	Updated	GL	AW	AW	02/09/2025
C	Updated Arrangements	AG	AW	AW	17/07/2025
B	Updated Arrangements	AG	EU	AW	15/07/2025
A	First Issue	GL	AW	AW	27/08/2024
Rev.	Description	Drm	Chk	App	Date

Drawing Status:

FOR PLANNING
NOT FOR CONSTRUCTION



Guildford - Reading - London
www.motion.co.uk

Client:
The Draper's Company

Project:
Edmanson's Close, Tottenham

Title:
**Swept Path Analysis
Fire Appliance**

Scale: 1:1000 (@ A3)

Drawing: **1906030-TK11** Revision: **D**

Appendix H

Existing Flat TRICs data

Calculation Reference: AUDIT-734001-200313-0302

TRIP RATE CALCULATION SELECTION PARAMETERS:

Land Use : 03 - RESIDENTIAL
 Category : D - AFFORDABLE/LOCAL AUTHORITY FLATS
 MULTI-MODAL VEHICLES

Selected regions and areas:

01	GREATER LONDON	
	HG HARINGEY	1 days
	IS ISLINGTON	1 days
02	SOUTH EAST	
	ES EAST SUSSEX	1 days
05	EAST MIDLANDS	
	LN LINCOLNSHIRE	1 days
	NT NOTTINGHAMSHIRE	1 days
08	NORTH WEST	
	CH CHESHIRE	1 days

This section displays the number of survey days per TRICS® sub-region in the selected set

Secondary Filtering selection:

This data displays the chosen trip rate parameter and its selected range. Only sites that fall within the parameter range are included in the trip rate calculation.

Parameter: Number of dwellings
 Actual Range: 15 to 90 (units:)
 Range Selected by User: 6 to 100 (units:)

Parking Spaces Range: All Surveys Included

Bedrooms per Dwelling Range: All Surveys Included

Percentage of dwellings privately owned: All Surveys Included

Public Transport Provision:

Selection by: Include all surveys

Date Range: 01/01/11 to 01/07/15

This data displays the range of survey dates selected. Only surveys that were conducted within this date range are included in the trip rate calculation.

Selected survey days:

Tuesday	1 days
Wednesday	1 days
Thursday	3 days
Friday	1 days

This data displays the number of selected surveys by day of the week.

Selected survey types:

Manual count	6 days
Directional ATC Count	0 days

This data displays the number of manual classified surveys and the number of unclassified ATC surveys, the total adding up to the overall number of surveys in the selected set. Manual surveys are undertaken using staff, whilst ATC surveys are undertaken using machines.

Selected Locations:

Suburban Area (PPS6 Out of Centre)	6
------------------------------------	---

This data displays the number of surveys per main location category within the selected set. The main location categories consist of Free Standing, Edge of Town, Suburban Area, Neighbourhood Centre, Edge of Town Centre, Town Centre and Not Known.

Selected Location Sub Categories:

Residential Zone	6
------------------	---

This data displays the number of surveys per location sub-category within the selected set. The location sub-categories consist of Commercial Zone, Industrial Zone, Development Zone, Residential Zone, Retail Zone, Built-Up Zone, Village, Out of Town, High Street and No Sub Category.

Motion High Street Guildford

Licence No: 734001

Secondary Filtering selection:

Use Class:

C3

6 days

This data displays the number of surveys per Use Class classification within the selected set. The Use Classes Order 2005 has been used for this purpose, which can be found within the Library module of TRICS®.

Population within 1 mile:

15,001 to 20,000

1 days

25,001 to 50,000

2 days

50,001 to 100,000

2 days

100,001 or More

1 days

This data displays the number of selected surveys within stated 1-mile radii of population.

Population within 5 miles:

100,001 to 125,000

1 days

125,001 to 250,000

1 days

250,001 to 500,000

2 days

500,001 or More

2 days

This data displays the number of selected surveys within stated 5-mile radii of population.

Car ownership within 5 miles:

0.5 or Less

1 days

0.6 to 1.0

4 days

1.1 to 1.5

1 days

This data displays the number of selected surveys within stated ranges of average cars owned per residential dwelling, within a radius of 5-miles of selected survey sites.

Travel Plan:

No

6 days

This data displays the number of surveys within the selected set that were undertaken at sites with Travel Plans in place, and the number of surveys that were undertaken at sites without Travel Plans.

PTAL Rating:

No PTAL Present

4 days

4 Good

1 days

6a Excellent

1 days

This data displays the number of selected surveys with PTAL Ratings.

LIST OF SITES relevant to selection parameters

1	CH-03-D-01 HEATH LANE CHESTER BOUGHTON HEATH Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: THURSDAY	BLOCK OF FLATS 30 24/05/12	CESHIRE Survey Type: MANUAL
2	ES-03-D-06 WELLINGTON ROAD BRIGHTON Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: THURSDAY	FLATS & HOUSES 15 16/10/14	EAST SUSSEX Survey Type: MANUAL
3	HG-03-D-03 COMMERCE ROAD WOOD GREEN WOODSIDE PARK Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: FRIDAY	BLOCKS OF FLATS 90 26/09/14	HARINGEY Survey Type: MANUAL
4	IS-03-D-03 HAWES STREET ISLINGTON Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: THURSDAY	BLOCK OF FLATS 36 21/11/13	ISLINGTON Survey Type: MANUAL
5	LN-03-D-02 ADDISON DRIVE LINCOLN Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: WEDNESDAY	FLATS 22 01/07/15	LINCOLNSHIRE Survey Type: MANUAL
6	NT-03-D-02 WATCOMBE ROAD NOTTINGHAM CARRINGTON Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: Survey date: TUESDAY	BLOCK OF FLATS 22 23/06/15	NOTTINGHAMSHIRE Survey Type: MANUAL

This section provides a list of all survey sites and days in the selected set. For each individual survey site, it displays a unique site reference code and site address, the selected trip rate calculation parameter and its value, the day of the week and date of each survey, and whether the survey was a manual classified count or an ATC count.

Motion High Street Guildford

Licence No: 734001

TRIP RATE for Land Use 03 - RESIDENTIAL/D - AFFORDABLE/LOCAL AUTHORITY FLATS

MULTI-MODAL VEHICLES

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	6	36	0.070	6	36	0.065	6	36	0.135
08:00 - 09:00	6	36	0.051	6	36	0.121	6	36	0.172
09:00 - 10:00	6	36	0.056	6	36	0.102	6	36	0.158
10:00 - 11:00	6	36	0.079	6	36	0.084	6	36	0.163
11:00 - 12:00	6	36	0.042	6	36	0.042	6	36	0.084
12:00 - 13:00	6	36	0.056	6	36	0.070	6	36	0.126
13:00 - 14:00	6	36	0.079	6	36	0.051	6	36	0.130
14:00 - 15:00	6	36	0.065	6	36	0.047	6	36	0.112
15:00 - 16:00	6	36	0.070	6	36	0.060	6	36	0.130
16:00 - 17:00	6	36	0.088	6	36	0.065	6	36	0.153
17:00 - 18:00	6	36	0.088	6	36	0.056	6	36	0.144
18:00 - 19:00	6	36	0.056	6	36	0.051	6	36	0.107
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.800			0.814			1.614

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

The survey data, graphs and all associated supporting information, contained within the TRICS Database are published by TRICS Consortium Limited ("the Company") and the Company claims copyright and database rights in this published work. The Company authorises those who possess a current TRICS licence to access the TRICS Database and copy the data contained within the TRICS Database for the licence holders' use only. Any resulting copy must retain all copyrights and other proprietary notices, and any disclaimer contained thereon.

The Company accepts no responsibility for loss which may arise from reliance on data contained in the TRICS Database. [No warranty of any kind, express or implied, is made as to the data contained in the TRICS Database.]

Parameter summary

Trip rate parameter range selected:	15 - 90 (units:)
Survey date range:	01/01/11 - 01/07/15
Number of weekdays (Monday-Friday):	6
Number of Saturdays:	0
Number of Sundays:	0
Surveys automatically removed from selection:	0
Surveys manually removed from selection:	0

This section displays a quick summary of some of the data filtering selections made by the TRICS® user. The trip rate calculation parameter range of all selected surveys is displayed first, followed by the range of minimum and maximum survey dates selected by the user. Then, the total number of selected weekdays and weekend days in the selected set of surveys are shown. Finally, the number of survey days that have been manually removed from the selected set outside of the standard filtering procedure are displayed.

Motion High Street Guildford

Licence No: 734001

TRIP RATE for Land Use 03 - RESIDENTIAL/D - AFFORDABLE/LOCAL AUTHORITY FLATS

MULTI-MODAL TOTAL PEOPLE

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	6	36	0.121	6	36	0.251	6	36	0.372
08:00 - 09:00	6	36	0.107	6	36	0.544	6	36	0.651
09:00 - 10:00	6	36	0.177	6	36	0.298	6	36	0.475
10:00 - 11:00	6	36	0.219	6	36	0.233	6	36	0.452
11:00 - 12:00	6	36	0.163	6	36	0.153	6	36	0.316
12:00 - 13:00	6	36	0.205	6	36	0.251	6	36	0.456
13:00 - 14:00	6	36	0.237	6	36	0.200	6	36	0.437
14:00 - 15:00	6	36	0.270	6	36	0.214	6	36	0.484
15:00 - 16:00	6	36	0.447	6	36	0.242	6	36	0.689
16:00 - 17:00	6	36	0.391	6	36	0.223	6	36	0.614
17:00 - 18:00	6	36	0.284	6	36	0.195	6	36	0.479
18:00 - 19:00	6	36	0.302	6	36	0.158	6	36	0.460
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			2.923			2.962			5.885

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

Appendix I

Proposed use TRICs output

Calculation Reference: AUDIT-734001-200313-0326

TRIP RATE CALCULATION SELECTION PARAMETERS:

Land Use : 03 - RESIDENTIAL
 Category : A - HOUSES PRIVATELY OWNED
 MULTI-MODAL VEHICLES

Selected regions and areas:

02	SOUTH EAST	
	HC HAMPSHIRE	1 days
	KC KENT	1 days
	WS WEST SUSSEX	1 days
03	SOUTH WEST	
	DV DEVON	2 days
	WL WILTSHIRE	1 days
04	EAST ANGLIA	
	CA CAMBRIDGESHIRE	2 days
	NF NORFOLK	2 days
	SF SUFFOLK	2 days
05	EAST MIDLANDS	
	LN LINCOLNSHIRE	1 days
06	WEST MIDLANDS	
	WK WARWICKSHIRE	1 days
07	YORKSHIRE & NORTH LINCOLNSHIRE	
	NY NORTH YORKSHIRE	3 days
	SY SOUTH YORKSHIRE	1 days
08	NORTH WEST	
	CH CHESHIRE	2 days
	MS MERSEYSIDE	1 days
09	NORTH	
	DH DURHAM	1 days
	TW TYNE & WEAR	1 days

This section displays the number of survey days per TRICS® sub-region in the selected set

Secondary Filtering selection:

This data displays the chosen trip rate parameter and its selected range. Only sites that fall within the parameter range are included in the trip rate calculation.

Parameter: Number of dwellings
 Actual Range: 6 to 98 (units:)
 Range Selected by User: 6 to 100 (units:)

Parking Spaces Range: All Surveys Included

Bedrooms per Dwelling Range: All Surveys Included

Percentage of dwellings privately owned: All Surveys Included

Public Transport Provision:

Selection by: Include all surveys

Date Range: 01/01/11 to 19/09/19

This data displays the range of survey dates selected. Only surveys that were conducted within this date range are included in the trip rate calculation.

Selected survey days:

Monday	6 days
Tuesday	7 days
Wednesday	4 days
Thursday	4 days
Friday	2 days

This data displays the number of selected surveys by day of the week.

Selected survey types:

Manual count	23 days
Directional ATC Count	0 days

This data displays the number of manual classified surveys and the number of unclassified ATC surveys, the total adding up to the overall number of surveys in the selected set. Manual surveys are undertaken using staff, whilst ATC surveys are undertaken using machines.

Selected Locations:

Suburban Area (PPS6 Out of Centre) 23

This data displays the number of surveys per main location category within the selected set. The main location categories consist of Free Standing, Edge of Town, Suburban Area, Neighbourhood Centre, Edge of Town Centre, Town Centre and Not Known.

This data displays the number of surveys per location sub-category within the selected set. The location sub-categories consist of Commercial Zone, Industrial Zone, Development Zone, Residential Zone, Retail Zone, Built-Up Zone, Village, Out of Town, High Street and No Sub Category.

Secondary Filtering selection:

Use Class:

C3

23 days

This data displays the number of surveys per Use Class classification within the selected set. The Use Classes Order 2005 has been used for this purpose, which can be found within the Library module of TRICS®.

Population within 1 mile:

1,001 to 5,000	2 days
5,001 to 10,000	6 days
10,001 to 15,000	3 days
15,001 to 20,000	4 days
20,001 to 25,000	3 days
25,001 to 50,000	5 days

This data displays the number of selected surveys within stated 1-mile radii of population.

Population within 5 miles:

5,001 to 25,000	1 days
25,001 to 50,000	1 days
50,001 to 75,000	3 days
75,001 to 100,000	5 days
100,001 to 125,000	1 days
125,001 to 250,000	9 days
250,001 to 500,000	3 days

This data displays the number of selected surveys within stated 5-mile radii of population.

Car ownership within 5 miles:

0.6 to 1.0	9 days
1.1 to 1.5	14 days

This data displays the number of selected surveys within stated ranges of average cars owned per residential dwelling, within a radius of 5-miles of selected survey sites.

Travel Plan:

Yes	4 days
No	19 days

This data displays the number of surveys within the selected set that were undertaken at sites with Travel Plans in place, and the number of surveys that were undertaken at sites without Travel Plans.

PTAL Rating:

No PTAL Present	23 days
-----------------	---------

This data displays the number of selected surveys with PTAL Ratings.

LIST OF SITES relevant to selection parameters

1	CA-03-A-04	DETACHED		CAMBRIDGESHIRE
	PETERBOROUGH			
	THORPE PARK ROAD			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	9		
	Survey date: TUESDAY	18/10/11		Survey Type: MANUAL
2	CA-03-A-05	DETACHED HOUSES		CAMBRIDGESHIRE
	EASTFIELD ROAD			
	PETERBOROUGH			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	28		
	Survey date: MONDAY	17/10/16		Survey Type: MANUAL
3	CH-03-A-08	DETACHED		CHESHIRE
	WHITCHURCH ROAD			
	CHESTER			
	BOUGHTON HEATH			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	11		
	Survey date: TUESDAY	22/05/12		Survey Type: MANUAL
4	CH-03-A-11	TOWN HOUSES		CHESHIRE
	LONDON ROAD			
	NORTHWICH			
	LEFTWICH			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	24		
	Survey date: THURSDAY	06/06/19		Survey Type: MANUAL
5	DH-03-A-01	SEMI DETACHED		DURHAM
	GREENFIELDS ROAD			
	BISHOP AUCLAND			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	50		
	Survey date: TUESDAY	28/03/17		Survey Type: MANUAL
6	DV-03-A-01	TERRACED HOUSES		DEVON
	BRONSHILL ROAD			
	TORQUAY			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	37		
	Survey date: WEDNESDAY	30/09/15		Survey Type: MANUAL
7	DV-03-A-03	TERRACED & SEMI DETACHED		DEVON
	LOWER BRAND LANE			
	HONITON			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	70		
	Survey date: MONDAY	28/09/15		Survey Type: MANUAL
8	HC-03-A-20	HOUSES & FLATS		HAMPSHIRE
	CANADA WAY			
	LIPHOOK			
	Suburban Area (PPS6 Out of Centre)			
	Residential Zone			
	Total Number of dwellings:	62		
	Survey date: TUESDAY	20/11/18		Survey Type: MANUAL

Total Number of dwellings: 51
Survey date: THURSDAY 14/07/16

Survey Type: MANUAL
LINCOLNSHIRE

10 LN-03-A-03 SEMI DETACHED

Total Number of dwellings: 22
Survey date: TUESDAY 18/09/12

Survey Type: MANUAL
MERSEYSIDE

11 MS-03-A-03 DETACHED

Total Number of dwellings: 15
Survey date: FRIDAY 21/06/13

Survey Type: *MANUAL*
NOBOLK

12 NF-03-A-01 SEMI DET. & BUNGALOWS

YARMOUTH ROAD
CAISTER-ON-SEA

Total Number of dwellings: 27
Survey date: TUESDAY 16/10/12

Survey Type: MANUAL
NORFOLK

13 NF-03-A-02 HOUSES & FLATS

DEREHAM ROAD
NORWICH

Total Number of dwellings: 98
Survey date: MONDAY 22/10/12

Survey Type: MANUAL
NORTH YORKSHIRE

14 NY-03-A-08 TERRACED HOUSES

NICHOLAS STREET
YORK

Total Number of dwellings: 21
Survey date: MONDAY 16/09/13

Survey Type: MANUAL
NORTH YORKSHIRE

15	NY-03-A-09	MIXED HOUSING
----	------------	---------------

GRAMMAR SCHOOL LANE
NORTHALLERTON

Total Number of dwellings: 52
Survey date: MONDAY 16/09/13

Survey Type: MANUAL
NORTH YORKSHIRE

16 NY-03-A-13 TERRACED HOUSES

Total Number of dwellings: 10
Survey date: WEDNESDAY 10/05/17

Survey Type: *MANUAL*
SUFFOLK

17	SF-03-A-04	DETACHED & BUNGALOWS
----	------------	----------------------

NORMANSTON DRIVE
LOWESTOFT

Total Number of dwellings: 7
Survey date: TUESDAY 23/10/12

Survey Type: MANUAL

LIST OF SITES relevant to selection parameters (Cont.)

18	SF-03-A-07 FOXHALL ROAD IPSWICH	MIXED HOUSES		SUFFOLK
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 73 Survey date: THURSDAY 09/05/19 Survey Type: MANUAL			
19	SY-03-A-01 A19 BENTLEY ROAD DONCASTER BENTLEY RISE	SEMI DETACHED HOUSES		SOUTH YORKSHIRE
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 54 Survey date: WEDNESDAY 18/09/13 Survey Type: MANUAL			
20	TW-03-A-02 WEST PARK ROAD GATESHEAD	SEMI-DETACHED		TYNE & WEAR
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 16 Survey date: MONDAY 07/10/13 Survey Type: MANUAL			
21	WK-03-A-01 ARLINGTON AVENUE LEAMINGTON SPA	TERRACED / SEMI / DET.		WARWICKSHIRE
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 6 Survey date: FRIDAY 21/10/11 Survey Type: MANUAL			
22	WL-03-A-02 HEADLANDS GROVE SWINDON	SEMI DETACHED		WILTSHIRE
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 27 Survey date: THURSDAY 22/09/16 Survey Type: MANUAL			
23	WS-03-A-05 UPPER SHOREHAM ROAD SHOREHAM BY SEA	TERRACED & FLATS		WEST SUSSEX
	Suburban Area (PPS6 Out of Centre) Residential Zone Total Number of dwellings: 48 Survey date: WEDNESDAY 18/04/12 Survey Type: MANUAL			

This section provides a list of all survey sites and days in the selected set. For each individual survey site, it displays a unique site reference code and site address, the selected trip rate calculation parameter and its value, the day of the week and date of each survey, and whether the survey was a manual classified count or an ATC count.

Motion High Street Guildford

Licence No: 734001

TRIP RATE for Land Use 03 - RESIDENTIAL/A - HOUSES PRIVATELY OWNED
 MULTI-MODAL VEHICLES
 Calculation factor: 1 DWELLS
 BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	23	36	0.070	23	36	0.297	23	36	0.367
08:00 - 09:00	23	36	0.130	23	36	0.405	23	36	0.535
09:00 - 10:00	23	36	0.144	23	36	0.174	23	36	0.318
10:00 - 11:00	23	36	0.116	23	36	0.133	23	36	0.249
11:00 - 12:00	23	36	0.152	23	36	0.134	23	36	0.286
12:00 - 13:00	23	36	0.164	23	36	0.153	23	36	0.317
13:00 - 14:00	23	36	0.160	23	36	0.176	23	36	0.336
14:00 - 15:00	23	36	0.149	23	36	0.194	23	36	0.343
15:00 - 16:00	23	36	0.240	23	36	0.177	23	36	0.417
16:00 - 17:00	23	36	0.282	23	36	0.181	23	36	0.463
17:00 - 18:00	23	36	0.344	23	36	0.163	23	36	0.507
18:00 - 19:00	23	36	0.241	23	36	0.161	23	36	0.402
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			2.192			2.348			4.540

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

The survey data, graphs and all associated supporting information, contained within the TRICS Database are published by TRICS Consortium Limited ("the Company") and the Company claims copyright and database rights in this published work. The Company authorises those who possess a current TRICS licence to access the TRICS Database and copy the data contained within the TRICS Database for the licence holders' use only. Any resulting copy must retain all copyrights and other proprietary notices, and any disclaimer contained thereon.

The Company accepts no responsibility for loss which may arise from reliance on data contained in the TRICS Database. [No warranty of any kind, express or implied, is made as to the data contained in the TRICS Database.]

Parameter summary

Trip rate parameter range selected: 6 - 98 (units:)
 Survey date range: 01/01/11 - 19/09/19
 Number of weekdays (Monday-Friday): 23
 Number of Saturdays: 0
 Number of Sundays: 0
 Surveys automatically removed from selection: 3
 Surveys manually removed from selection: 0

This section displays a quick summary of some of the data filtering selections made by the TRICS® user. The trip rate calculation parameter range of all selected surveys is displayed first, followed by the range of minimum and maximum survey dates selected by the user. Then, the total number of selected weekdays and weekend days in the selected set of surveys are shown. Finally, the number of survey days that have been manually removed from the selected set outside of the standard filtering procedure are displayed.

Motion High Street Guildford

Licence No: 734001

TRIP RATE for Land Use 03 - RESIDENTIAL/A - HOUSES PRIVATELY OWNED

MULTI-MODAL TOTAL PEOPLE

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	23	36	0.115	23	36	0.533	23	36	0.648
08:00 - 09:00	23	36	0.218	23	36	0.859	23	36	1.077
09:00 - 10:00	23	36	0.243	23	36	0.323	23	36	0.566
10:00 - 11:00	23	36	0.216	23	36	0.279	23	36	0.495
11:00 - 12:00	23	36	0.268	23	36	0.225	23	36	0.493
12:00 - 13:00	23	36	0.301	23	36	0.274	23	36	0.575
13:00 - 14:00	23	36	0.275	23	36	0.311	23	36	0.586
14:00 - 15:00	23	36	0.264	23	36	0.322	23	36	0.586
15:00 - 16:00	23	36	0.598	23	36	0.328	23	36	0.926
16:00 - 17:00	23	36	0.583	23	36	0.318	23	36	0.901
17:00 - 18:00	23	36	0.643	23	36	0.284	23	36	0.927
18:00 - 19:00	23	36	0.428	23	36	0.284	23	36	0.712
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			4.152			4.340			8.492

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.