




Room Schedule - Ground Floor Level				
Number	Area	Name	Comments	
RM-01	7.79 m ²	LU Multipurpose		
RM-02	19.09 m ²	LU Kitchen/mess		
RM-03	3.28 m ²	Kitchen/Mess Lobby		
RM-04	3.25 m ²	LU Cleaner's Tea Point		
RM-05	10.08 m ²	Cleaning Machine Room		
RM-06	4.13 m ²	Cleaner's Dry Service Room		
RM-07	7.09 m ²	Public Accessible WC		
RM-08	11.05 m ²	Fan Room		LU Room 1/776
RM-09	4.72 m ²	LU Staff Ladies Changing Room		
RM-10	5.11 m ²	LU Staff Ladies WC		
RM-11	4.97 m ²	LU Staff Gents WC		
RM-12	4.94 m ²	LU staff Gents Changing Room		
RM-13	2.82 m ²	LU Drying Cupboard Lobby		
RM-14	2.91 m ²	LU Staff Shower Room		
RM-15	8.04 m ²	UMC Access / Escalator Machine Room Entrance		LU Room 1/151
RM-17	8.54 m ²	SCR		LU Room 1/746

Room Schedule - Ground Floor Level				
Number	Area	Name	Comments	
RM-18	23.87 m ²	CER		LU Room 1/732
RM-19	23.08 m ²	LU Lift Passage		
RM-20	42.62 m ²	Independent Retail Unit		
RM-21	7.57 m ²	Ladder Store		LU Room 1/411
RM-22	17.17 m ²	E1 Switch Room		LU Room 1/661
RM-23	5.85 m ²	E3 Switch Room		LU Room 1/662
RM-24	23.53 m ²	DNO / OLB1 Room		
RM-25	35.48 m ²	Transformer Room		LU Room 1/781
RM-28	7.25 m ²	Lobby		
RM-29	19.22 m ²	STN. OPS. RM		LU Room 1/751
RM-30	9.86 m ²	Bin Store		
RM-31	59.42 m ²	External Service Yard		
RM-32	4.13 m ²	STAIR G-5		
RM-33	116.32 m ²	LU Paid Concourse		LU Room 1/071
RM-34	554.37 m ²	TH Unpaid Concourse		LU Room 1/001
RM-35	15.03 m ²	Plant Roof Access Staircase		

Room Schedule - Ground Floor Level				
Number	Area	Name	Comments	
RM-36	74.99 m ²	Retail / OSD Core		
RM-37	5.39 m ²	ATM Room		
RM-38	3.46 m ²	LU ACR Secure Lobby		
RM-39	18.58 m ²	LU ACR Room		
RM-41	9.52 m ²	Allocated to NR		
RM-42	6.04 m ²	Allocated to NR		
RM-43	3.40 m ²	Allocated to NR		
RM-44	259.41 m ²	NR Paid Concourse		
RM-45	6.60 m ²	Lobby To SCR Rooms		LU Room 1/082
RM-46	1.31 m ²	MDF		LU Room 1/731
RM-47	8.21 m ²	Lobby to Changing Rooms		
RM-48	9.66 m ²	Sprinkler Valve Chamber		LU Room 1/396
RM-49	4.54 m ²	Allocated to NR		
RM-50	13.59 m ²	Allocated to NR		
RM-54	9.34 m ²	Void 1		
RM-55	4.33 m ²	Void 2		
RM-56	1.09 m ²	UKPN / DNO		

Room Schedule - Withdrawn Rooms		
Number	Name	Comments
RM-16	Draught Relief	WITHDRAWN
RM-26	OLB1 Room	WITHDRAWN
RM-27	SO WC	WITHDRAWN
RM-40	Void Under Plant Roof Access Stair	WITHDRAWN
RM-53	Electrical Cupboard	WITHDRAWN

NOTE

This drawing is to be read in conjunction with the following:
2383-HUK-PRM-DRG-0021: GA First Floor Level Plan
2383-HUK-PRM-DRG-0023: GA Roof Level plan
2383-HUK-PRM-DRG-0025: GA Basement Level Plan
2383-HUK-PRM-DRG-0026: General Section A-A
2383-HUK-PRM-DRG-0027: General Section B-B & C-C
2383-HUK-PRM-DRG-0028: West & North Elevations
2383-HUK-PRM-DRG-0029: East & South Elevations

2383-HUK-PRM-DRG-0511: Fire Strategy

2383-HUK-PRM-DRG-6050: Reflected Ceiling Plan - 1:100
Refer to dwg's 6011 to 6015: General Arrangements - 1:50
Refer to dwg's 6110 to 6114: Floor Finishes - 1:50
Refer to dwg's 6115 to 6119: Reflected Ceilings - 1:50

SAFETY, HEALTH & ENVIRONMENTAL INFORMATION			
IN ADDITION TO THE HAZARDS NORMALLY ASSOCIATED WITH THE TYPES OF WORK DETAILED ON THIS DRAWING, NOTE THE FOLLOWING:			
CONSTRUCTION			
MAINTENANCE/CLEANING			
DECOMMISSIONING/DEMOLITION			
IT IS ASSUMED THAT ALL WORKS WILL BE CARRIED OUT BY A COMPETENT CONTRACTOR WORKING, WHERE APPROPRIATE, TO AN APPROVED METHOD STATEMENT			


This drawing is copyright and owned by Capita Property & Infrastructure, and is for use on this site only unless contractually stated otherwise.
DO NOT SCALE this drawing (printed or electronic version). Contractors must check all dimensions from site.

All other design team elements, where indicated, have been imported from the consultant's drawings and reference should be made to the individual consultant's drawings for exact setting out, size and type of component.

Discrepancies and / or ambiguities within this drawing, between 1 and information given elsewhere, must be reported immediately to the Consultant for clarification before proceeding.
All works are to be carried out in accordance with the latest LU Standards, Eurocodes, British Standards and Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or if issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when compared to the original paper or electronic image. Graphical representations of equipment on this drawing have been coordinated, but are approximations only. Please refer to the Specifications and / or Details for actual sizes and / or specific contractor construction information.
This original document is issued for the purpose indicated below and contains information of confidential nature. Further copies and circulation will be strictly in accordance with the confidentiality agreement under the contract. This original must be destroyed or returned to the contractor.

SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION
Refer to the relevant Construction (Design and Management) documentation where applicable.
It is assumed that all works on this drawing will be carried out by a competent contractor, working where appropriate to an approved method statement.

KEY PLAN:**NOTES**

014	JH	NO	GU	Issue for Construction: DNO Cabinet added (RM-56) Contract Instruction No. CI 68	25/11/19
013	JH	NO	GU	Issue for Construction: Changes as per survey reviewed 29/3/19 - Alternative Design. Review NR opening and new pier. External walls Grid A revised	13/07/19
012	JH	NO	GU	Changes as per survey reviewed 29.03.19	02/04/19
011	JH	NO	GU	CI 053 Repeater Fire Panel Emergency control & emergency control microphone incorporated. Ceiling Height revised. duct information added & minor corrections	02/01/19
010	JH	NO	GU	Wall on grid E repositioned (LU TVM's). Lobby RM-28 revised to add cup'd to MEP requirement	02/11/18
09	JH	NO	GU	For Acceptance - Alternative Design - Changes from Contract Instruction No's CI 24, CI 31, CI 32, CI 36, CI 37, CI 42, CI 45 & CI 48. Vent duct Relocated. Capita address changed in Title Block	15/10/18
08	JH	NO	GU	Existing Floor retained (CI 37) - Existing UMC access cover retained (CI 32) - New Lift omitted (CI 31) - Stair S1 retained (CI 31) - New Stair access to platform 2 (G9) - Existing LU Gateline retained (CI 38) - Combined OLB1 and DNO room (RM 24 & CI 38) - Proposed Cladding removed, concrete wall to be tiled up to ceiling (CI 48) Concrete to be exposed Grid 2 b/w A-C (CI 42) level 1 - Ramp 1 modified (CI 34) - Retained PHP (CI 45) - Back painted glass level 1 replaced by exposed concrete blockwork no finish and Grid G & 5 NR boundary ground level only to be blockwork 1 hour fire separation, cladding remains (CI 48) - Capita address changed in Title Block	04/09/18
07	JH	NO	GU	For Acceptance	07/03/18
06	JH	SV	GU	For Acceptance	08/01/18
05	JH	WL	GU	For Review	20/10/17
04	JH	WL	GU	For Review	21/09/17
03	JH	SV	GU	For Review	31/07/17
02	JH	WL	GU	For Review	02/05/17
01	JH	WL	GU	For Review	24/04/17

Rev	Drawn	Chkd	App'd	Description	Date
-----	-------	------	-------	-------------	------

Purpose of Issue	Status
For Construction	Construction
Classification	
Commercial in confidence	
Client	



Project	TOTTENHAM HALE STATION UPGRADE
Workstream	STATION WORKS

Drawing
PROPOSED GENERAL ARRANGEMENT TICKET HALL LEVEL PLAN

Scale @ A1	Drawn	Checked	Approved
1:100	JH	SV	GU
Project No.	Date		
CS/081301	01/03/2017		

Drawing Identifier
Project - Originator - Discipline Code - Document Code - Sequential Number
2383-HUK-PRM- DRG -0019 014

CAPITA
Property and infrastructure

65 Gresham Street, London EC2V 7NQ
T +44 (0) 20 7580 5886
www.capitaproperty.co.uk
Registered office: 71 Victoria Street, Westminster, London, SW1H 0XA. Registered in England and Wales No. 2018542 Part of the Capita Group Plc. www.capita.co.uk